



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

HARVARD UNIVERSITY.



LIBRARY

OF THE


MUSEUM OF COMPARATIVE ZOÖLOGY

52,753

BEQUEST OF

WILLIAM BREWSTER

November 21, 1919.



NOV 01 1919

To Mr. Parmenter Esq.

With J. A. HARVIE-BROWN'S
compliments and regards.

THE BIRDS OF BERWICKSHIRE

VOL. II.

Edinburgh : Printed by George Waterston & Sons

FOR

DAVID DOUGLAS.

LONDON, . . SIMPKIN, MARSHALL, HAMILTON, KENT, AND CO., LIMITED.

CAMBRIDGE, . MACMILLAN AND BOWES.

GLASGOW, . . JAMES MACLEHOSE AND SONS.



FIG. 1. Fossil of a small, round, textured object.

.....

.

.

.

.....

.

.....

.....

.....

.....

.

THE BIRDS OF BERWICKSHIRE

WITH REMARKS ON THEIR LOCAL DISTRIBUTION
MIGRATION, AND HABITS, AND ALSO ON THE
FOLK-LORE, PROVERBS, POPULAR RHYMES
AND SAYINGS CONNECTED WITH THEM

BY
GEORGE MUIRHEAD, F.R.S.E., F.Z.S.

MEMBER OF THE BRITISH ORNITHOLOGISTS' UNION, MEMBER OF
THE BERWICKSHIRE NATURALISTS' CLUB, ETC.

IN TWO VOLUMES



*No more the screaming bittern, bellowing harsh,
To its dark bottom shakes the shuddering marsh.*

VOL. II.

EDINBURGH: DAVID DOUGLAS

1895
S

[All rights reserved.]

*Nature never did betray
The heart that loved her; 'tis her privilege,
Through all the years of this our life, to lead
From joy to joy.*

WORDSWORTH.

CONTENTS OF VOL. II.

		PAGE
FALCONIDÆ.		
<i>Falco peregrinus.</i>	Peregrine Falcon,	1
Falconry in Berwickshire,		10
<i>Falco subbuteo.</i>	Hobby,	20
„ <i>caalon.</i>	Merlin,	21
„ <i>tinnunculus.</i>	Kestrel,	25
<i>Pandion hallæetus.</i>	Osprey,	27
ACCIPITRES.		
PELECANIDÆ.		
<i>Phalacrocorax carbo.</i>	Common Cormorant,	30
„ <i>graculus.</i>	Shag or Green Cormorant,	33
<i>Sula bassana.</i>	Gannet or Solan Goose,	35
HERODIONES.		
ARDEIDÆ.		
<i>Ardea cinerea.</i>	Common Heron,	39
<i>Nycticorax griseus.</i>	Night Heron,	52
<i>Botaurus stellaris.</i>	Common Bittern,	53
CICONIIDÆ.		
<i>Ciconia alba.</i>	White Stork,	64
ANSERES.		
ANATIDÆ.		
<i>Anser segetum.</i>	Bean Goose,	66
„ <i>brachyrhynchus.</i>	Pink-footed Goose,	66
„ <i>albifrons.</i>	White-fronted Goose,	90
<i>Bernicla brenta.</i>	Brent Goose,	91
„ <i>leucopsis.</i>	Bernacle Goose,	93
„ <i>canadensis.</i>	Canada Goose,	95
<i>Oxygnus musicus.</i>	Whooper,	96
<i>Oxygnus Bewicki.</i>	Bewick's Swan,	99
<i>Tadorna cornuta.</i>	Common Sheld-Duck,	100
<i>Anas boschas.</i>	Mallard or Wild Duck,	101
<i>Spatula clypeata.</i>	Shoveller,	107
<i>Dasila acuta.</i>	Pintail Duck,	109
<i>Querquedula crecca.</i>	Teal,	110
„ <i>circia.</i>	Garganey,	112

ANATIDÆ—continued.

<i>Mareca penelope.</i>
<i>Fuligula ferina.</i>
„ <i>cristata.</i>
„ <i>marila.</i>
„ <i>clangula.</i>
<i>Harelda glacialis.</i>
<i>Somateria mollissima.</i>
<i>Eidemia nigra.</i>
„ <i>fusca.</i>
<i>Mergus merganser.</i>
„ <i>albellus.</i>

COLUMBIDÆ.

<i>Columba palumbus.</i>
„ <i>cenas.</i>
„ <i>livia.</i>
<i>Turtur communis.</i>
<i>Ectopistes migratorius.</i>

PTEROCLIDÆ.

<i>Syrnhytes paradoxus.</i>

TETRAONIDÆ.

<i>Tetrao tetrix.</i>
<i>Lagopus scoticus.</i>

PHASIANIDÆ.

<i>Phasianus colchicus.</i>
<i>Perdix cinerea.</i>
<i>Coturnix communis.</i>

RALLIDÆ.

<i>Orex pratensis.</i>
<i>Porzana maruetta.</i>
<i>Rallus aquaticus.</i>
<i>Gallinula chloropus.</i>
<i>Fulica atra.</i>

ANSERES—continued.

	PAGE
Wigeon,	113
Pochard,	115
Tufted Duck,	118
Scaup Duck,	119
Golden-Eye,	120
Long-tailed Duck,	122
Eider Duck,	123
Common Scoter,	126
Velvet Scoter,	127
Goosander,	128
Smew,	130

COLUMBÆ.

Ring Dove,	131
Stock Dove,	141
Rock Dove,	145
Turtle Dove,	151
Passenger Pigeon,	153

PTEROCLETES.

Pallas's Sand Grouse,	155
---------------------------------	-----

GALLINÆ.

Black Grouse,	158
Red Grouse,	162

Pheasant,	170
Common Partridge,	178
Common Quail,	190

FULICARIÆ.

Landrail,	194
Spotted Crane,	198
Water Rail,	200
Moor Hen,	202
Common Coot,	204

CONTENTS.

vii

ALECTORIDES.

OTIDIDÆ.	PAGE
<i>Otis tarda.</i>	207

LIMICOLÆ.

CHARADRIIDÆ.	
<i>Charadrius morinellus.</i>	210
„ <i>pluvialis.</i>	231
<i>Ægialitis hiaticula.</i>	224
<i>Vanellus vulgaris.</i>	225
<i>Hematopus ostralegus.</i>	231

SCOLOPACIDÆ.

<i>Phalaropus fulicarius.</i>	232
<i>Scalopax rusticula.</i>	233
<i>Gallinago major.</i>	240
„ <i>caelestis.</i>	241
„ <i>gallinula.</i>	244
<i>Tringa alpina.</i>	246
„ <i>striata.</i>	247
<i>Machetes pugnax.</i>	248
<i>Totanus hypoleucus.</i>	250
„ <i>ochropus.</i>	252
„ <i>calidris.</i>	254
„ <i>canescens.</i>	256
<i>Limosa cægocephala.</i>	257
<i>Numenius arquata.</i>	258
„ <i>phaeopus.</i>	263

GAVIÆ.

LARIDÆ.	
<i>Hydrochelidon nigra.</i>	264
<i>Sterna fluviatilis.</i>	265
<i>Larus minutus.</i>	266
„ <i>ridibundus.</i>	268
„ <i>canus.</i>	275
„ <i>argentatus.</i>	279
„ <i>fuscus.</i>	285
„ <i>marinus.</i>	286
„ <i>glaucus.</i>	287
<i>Rissa tridactyla.</i>	288
<i>Stercorarius pomatorhinus.</i>	292
„ <i>crepidatus.</i>	293
„ <i>parasiticus.</i>	294

ALCIDÆ		PAGE
<i>Alca torda.</i>	Razor-Bill,	295
<i>Uria troile.</i>	Common Guillemot,	297
„ <i>grylle.</i>	Black Guillemot,	303
<i>Mergulus alle.</i>	Little Auk,	305
<i>Fratercula arctica.</i>	Puffin,	307
COLYMBIDÆ		
<i>Colymbus glacialis.</i>	Great Northern Diver,	309
„ <i>septentrionalis.</i>	Red-throated Diver,	311
PODICIPEDIDÆ		
<i>Podiceps cristatus.</i>	Great Crested Grebe,	313
„ <i>griseigena.</i>	Red-necked Grebe,	315
„ <i>nigricollis.</i>	Eared Grebe,	317
„ <i>fluvialis.</i>	Little Grebe or Dabchick,	318
PROCELLARIIDÆ		
<i>Procellaria pelagica.</i>	Storm Petrel,	321
MIGRATION OF BIRDS IN BERWICKSHIRE,		324
TABLE OF ORNITHOLOGICAL OBSERVATIONS MADE IN BERWICKSHIRE from 1799 until 1887,		329
CALENDAR OF MIGRATIONS AND OBSERVATIONS OF BIRDS IN BERWICK- SHIRE, 1799-1887,		335
TABLE showing the earliest, latest, and average dates of the arrivals and departures of the true migratory birds which visit Berwickshire annually, with approximate notes regarding the average temperatures, and the prevailing winds, during the periods when their migrations took place, 1799-1887,		351
TABLE showing mean monthly temperatures at Milne Graden, Berwickshire, 1857-87,		356
APPENDIX.		
Hawfinch,		358
Great Spotted Woodpecker,		359

ILLUSTRATIONS

IN VOL. II.

	PAGE
BILLIE MIRE. By JOHN BLAIR,	<i>Title-page</i>
HAWKSHEUGH, NEAR FAST CASTLE. By JOHN BLAIR, from Photograph, .	9
HAWK'S HOOD. By MRS. MUIRHEAD,	19
KIMMERGHAME HOUSE. By MRS. MUIRHEAD, from Photograph, .	20
MERLIN ON FALCONER'S GLOVE. By GEORGE E. LODGE,	24
OSPREY. By MRS. MUIRHEAD,	29
COMMON CORMORANTS. By MRS. MUIRHEAD,	32
SEA SHELL. By MRS. MUIRHEAD,	34
GANNET AND ITS YOUNG. By MRS. MUIRHEAD, from Photograph by WM. GREEN, Berwick-on-Tweed,	38
MEETOUN. By the HON. R. H. SCOTT,	<i>facing page 48</i>
HERON'S NEST. From Nature, by MRS. MUIRHEAD,	51
HIRSEL LOCH. By MRS. MUIRHEAD, from Photograph,	52
PLAN OF BILLIE MIRE AS IT WAS IN 1759 AND 1816. By GEORGE MUIRHEAD, from Old Plans,	<i>facing page 58</i>
HOME CASTLE. By JOHN BLAIR, from Photograph,	63
COLDINGHAM VILLAGE. By JOHN BLAIR,	65
THE HULE MOSS, WITH DIRKINGTONS AND TWINLAW CAIRNS IN DISTANCE. By JOHN BLAIR,	<i>facing page 86</i>
SHEPHERD'S HOUSE AT WEDDERLIE. By JOHN BLAIR,	89
COVE HARBOUR, NEAR COCKBURNSPATH. By JOHN BLAIR,	92
BATTY'S STANE, NEAR REMAINS OF ST. ABB'S KIRK. By JOHN BLAIR, .	94

	PAGE
HEAD OF CANADA GOOSE. By MRS. MUIRHEAD,	95
WILD SWANS. From Nature, by MRS. MUIRHEAD,	98
HEAD OF BEWICK'S SWAN. By MRS. MUIRHEAD,	99
COMMON WILD DUCK'S NEST. From Nature, by MRS. MUIRHEAD,	106
DUNS CASTLE. By MRS. MUIRHEAD, from Photograph by GEORGE FORTUNE, Duns,	108
SALMON FISHING ON THE TWEED. By JOHN BLAIR,	109
TEAL'S NEST. From Nature, by MRS. MUIRHEAD,	112
STAR FISH. By MRS. MUIRHEAD,	114
OLD BRIDGE ON THE LEADER AT EARLSTON. By JOHN BLAIR, . .	117
SEA SHELL. By MRS. MUIRHEAD,	119
ABBAY ST. BATHANS. By MRS. MUIRHEAD, from Photograph, . .	121
EIDER DUCK'S NEST. From Nature, by MRS. MUIRHEAD, . . .	125
TRAP FOR CATCHING CRABS. By JOHN BLAIR,	126
THE WHEAT STACK ROCK, NEAR FAST CASTLE. By JOHN BLAIR, from Photograph,	127
LADYKIRK ON THE TWEED. By JOHN BLAIR,	129
THE HIRSEL. By MRS. MUIRHEAD, from Photograph,	130
WOOD PIGEON'S NEST. From Nature, by MRS. MUIRHEAD, . . .	140
GALIUM APARINE. By MRS. MUIRHEAD,	144
THE CLEAVER ROCK, ST. ABB'S HEAD. By JOHN BLAIR, <i>facing page</i>	146
DOOOOT AT MERTOUN. By JOHN BLAIR,	150
ROCKS ON WHITADDER AT EDRINGTON. By JOHN BLAIR,	152
MELLERSTAIN HOUSE. By JOHN BLAIR, from Photograph, . . .	154
SPITAL HOUSE. By MRS. MUIRHEAD, from Photograph,	157
BYREOLEUGH. By JOHN BLAIR, <i>facing page</i>	164
BLANBERRIES. By MRS. MUIRHEAD,	169
LEITHOLM VILLAGE. By JOHN BLAIR,	189

ILLUSTRATIONS.

xi

	PAGE
NISSET HOUSE. By JOHN BLAIR,	193
CORNORAKE'S NEST. From Nature, by MRS. MUIRHEAD, . . .	197
DOORWAY, GREENKNOWE TOWER. By JOHN BLAIR,	199
COOT'S NEST. From Nature, by MRS. MUIRHEAD,	206
REMAINS OF BUNCLE CASTLE. By MRS. MUIRHEAD, from Photograph,	209
GOLDEN PLOVER'S NEST. From Nature, by MRS. MUIRHEAD, . .	223
RINGED PLOVER. By MRS. MUIRHEAD,	224
LAPWING'S NEST. From Nature, by MRS. MUIRHEAD,	230
OYSTER CATCHER. By MRS. MUIRHEAD,	231
NENTHORN HOUSE. By MRS. MUIRHEAD, from a Sketch, . . .	232
WOODCOCK'S NEST. From Nature, by MRS. MUIRHEAD, . . .	239
LONGFORMACUS BRIDGE. By JOHN BLAIR,	245
SEA WEED. By MRS. MUIRHEAD,	247
COMMON SANDPIPER'S NEST. From Nature, by MRS. MUIRHEAD, .	251
OLDCAMBUS DEAN. By JOHN BLAIR,	253
COMMON REDSHANK'S NEST. From Nature, by MRS. MUIRHEAD, .	255
SEA SHELLS. By MRS. MUIRHEAD,	257
COMMON CURLEW'S NEST. From Nature, by MRS. MUIRHEAD, . .	262
SEA SHELL. By MRS. MUIRHEAD,	263
CRAB. By MRS. MUIRHEAD,	264
TERNs AND THEIR YOUNG. By MRS. MUIRHEAD,	265
COLDINGHAM LOCH. By JOHN BLAIR,	267
BLACK-HEADED GULL'S NEST. From Nature, by MRS. MUIRHEAD,	274
TOP OF FOUL CARR, FROM CLIFF NEAR REMAINS OF ST. ABB'S NUNNERY. By JOHN BLAIR, from Photograph,	284
GULL'S FOOT. By JOHN BLAIR,	285
HERRING BOATS AT EYEMOUTH. By MRS. MUIRHEAD, from Photograph,	287

	PAGE
FLOT CARR AND SKELLY. By JOHN BLAIR,	291
ON THE BERWICKSHIRE COAST. By the HON. R. H. SCOTT, . . .	292
STEEPLE ROCK, PETTICOWICK. By JOHN BLAIR,	294
EYEMOUTH, FROM NEAR THE FORT. By JOHN BLAIR,	<i>facing page 294</i>
WHITEHEUGH. By JOHN BLAIR,	<i>facing page 298</i>
PLAN OF ST. ABB'S HEAD,	<i>facing page 300</i>
COMMON GUILLEMOTS. By MRS. MUIRHEAD, from Photograph by WILLIAM GREEN, Berwick-on-Tweed,	302
HORSE CASTLE COVE. By JOHN BLAIR,	304
LITTLE AUK. By MRS. MUIRHEAD,	306
FOUL CARR AND THE STACK. By JOHN BLAIR, from Photograph, .	308
SALMON FISHERS' SHIEL ON THE TWEED. By JOHN BLAIR, . . .	310
COAST OF BERWICKSHIRE, FROM THE NEIGHBOURHOOD OF COCK- BURNSPATH. By JOHN BLAIR,	312
HORNDEN CHURCHYARD. By JOHN BLAIR,	314
WEDDERLIE HOUSE. By JOHN BLAIR,	316
FISHING ON THE DYE. By JOHN BLAIR,	320
ST. ABB'S HEAD: STORM ON THE 14TH OF OCTOBER 1881. By J. CAMPBELL NOBLE, R.S.A.,	323
SWALLOWS. By MRS. MUIRHEAD,	328
CUCKOO. By MRS. MUIRHEAD,	350
THE "RIDING TREE" AT SALTON, EAST LoTHIAN. By Mrs. MUIRHEAD, from Photograph,	358
WHITSOME VILLAGE. By JOHN BLAIR,	359
PORCH OF AUTHOR'S HOUSE AT PAXTON. By JOHN BLAIR, . . .	383
BEEHIVES. By JOHN BLAIR,	390

THE PEREGRINE FALCON.

BLUE HAWK, HUNTING HAWK, GOSHAWK, GAME HAWK,
GREY HAWK, FALCON, COMMON FALCON.

Falco peregrinus.

The Blue Hawk, The Hunting Hawk, The Goshawk.

A Faucon Peregrine seemed she of fremde londe.

CHAUCER, *Squire's Tale*.

*As a Faucon fayre,
That once hath failed of her souse full neare,
Remounts againe into the open ayre,
And unto better fortune doth herselfe prepayre.*

SPENSER, *Fairie Queen*.

THIS noble bird, which has obtained the name of the Hunting Hawk on account of its having been so much used in former times for the chase, breeds annually on the sea-coast of Berwickshire, in the neighbourhood of St. Abb's Head and Fast Castle, where it has had its eyrie from time immemorial.¹

Writing in 1833 regarding a visit of the Berwickshire Naturalists' Club to St. Abb's Head on the 19th of June of that year, Selby, the well-known ornithologist, mentions that on reaching the cliffs immediately north of the Head, where they rise from the sea in fine, broken, and perpendicular faces to the height of several hundred feet, the attention of the members was attracted to the cry of two Peregrine Falcons—a male and a female—which were seen soaring at

¹ In an ancient Rental of Coldingham drawn up after the battle of Falkirk in 1298, there is an entry of "two aeries of Falcons," which were doubtless situated on the adjoining coast.

a considerable height in the air, the cause of their solicitude being two of their young, which had apparently just quitted the nest, and which were seen perched on a projecting angle of the rock.¹

The Rev. Andrew Baird, in his report on the united parishes of Cockburnspath and Oldcambus written for the *New Statistical Account of Scotland* in 1834, states that the "Hunting Hawk" is frequently seen on the Redheugh Coast.²

Mr. Robert Cowe, Oldcastles, who lived at Dowlaw for many years, has informed me that, from 1839 to 1850, it nested regularly every season near Fast Castle; and Mr. Archibald Hepburn, who contributed many interesting notes to Macgillivray's *History of British Birds*, records in 1850 that "four pairs of the Peregrine Falcon breed on the coast of Berwickshire; one at Burnmouth, one at Petticowick Cove to the west of St. Abb's, one at Ernesheugh, and a fourth at Fast Castle."³ My friend Mr. Hardy, Oldcambus, writes that the Peregrine nested at Halternsloup near Coldingham Shore in 1836 and 1853, and has occasionally bred in a steep, massive rock,⁴ a short distance to the east of the Rammel Cove, since 1856. He adds that it had its eyrie at Fast Castle, Whiteheugh, and near Burnmouth, in 1857, and that it was from the last-mentioned locality that Mr. Baird of Newbyth sometimes got his Falcons.⁵ Mr. Robert Calder, Little Swinton, who spent his youth at Fairnieside, a farm on the coast near Burnmouth, of which his father was tenant, relates that the Peregrine often nested, previous to 1857, in "the cliff of the high perpendicular rock over-

¹ *Hist. Ber. Nat. Club*, vol. i. p. 21.

² *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 299.

³ *Hist. Ber. Nat. Club*, vol. iii. p. 71.

⁴ Mr. Hardy says that an old fisherman named James Fairbairn, who lived at the Cove, told him that long ago the Raven used to have its nest on this rock.

⁵ Letter from Mr. Hardy, Oldcambus, dated the 5th of November 1884.

hanging the well-known Gull Rock, and that Mr. Belany¹ frequently got the young Falcons from the nest there, and trained them, a man or boy being lowered down to the nest by a rope.²

Two pairs of Falcons appear to have bred in the vicinity of St. Abb's Head in 1859;³ and in 1860 there was a nest in the precipice at Hawksheugh immediately to the east of Fast Castle, which seems to have been occupied on the 3rd of May 1865, when I visited that part of the coast with Mr. William Cowe, Dowlaw, who showed me the cliff at Hawksheugh up which his brother, Mr. Peter Cowe, was drawn with a rope to get the young Falcons from their eyrie in 1860.⁴

Mr. John Wilson, Chapelhill, Cockburnspath, has kindly furnished me with the following interesting account of the taking of the young Falcons from their eyrie in the precipice at Hawksheugh in June 1866—the parties engaged in the adventure being Mr. Wilson, Mr. Frederick Smith, Hoprig, and Mr. William Cowe, Dowlaw. “The nest,” says Mr. Wilson, “was just a little to the east of the castle, and from that point we could see the young ones sitting in it. We attached a blanket to a rope and dangled it over the nest, so that the Hawks might strike at it, and we thought we could draw them up to the top of the cliff while they

¹ Mr. James Cockburn Belany was a surgeon in Ayton, and kept Hawks there at one time. On the occasion of the Highland and Agricultural Society's Show at Berwick, in 1841, he exhibited his Falcons flying at Pigeons in the Magdalen Fields. He wrote a treatise upon Falconry, which was printed in Berwick in the above year.

² Letter from Mr. Robert Calder, Little Swinton, dated 29th November 1884.

³ *Hist. Ber. Nat. Club*, vol. iv. p. 131.

⁴ Mr. Peter Cowe, Lochton, who formerly lived at Dowlaw, informed me on the 5th of August 1886, that, in the beginning of June 1860, he took four young Peregrines out of their nest in the precipice at Hawksheugh, immediately to the east of Fast Castle. He was drawn up the face of the cliff from the beach, by four or five men stationed at the top of the rock, with a long rope, a chain being attached to the upper part of the rope to come in contact with the rocks and thus prevent the danger of it chafing on their sharp points.

were holding on by their talons. When they found they were being pulled up, they took to wing—being almost fully fledged—and alighted on the rocks down at the beach. We marked the spots where they settled, and, going down, had no difficulty in catching them, as they were too inexperienced to attempt a second flight. I think we got four—Mr. Smith taking two and Mr. Cowe two. Mr. Smith reared his and had them six or eight months, when, after a long fast, they were fed unhooded, and fought over the food, the result being that one was killed in the fight, and the other died some days afterwards. Mr. Smith had begun to train them, and they would take long flights and come back at his call, and settle on his hand, but he had never flown them at game. Mr. Cowe reared one, and had it for a year or more, but it flew away and did not return, though it remained in the neighbourhood for several seasons, and used to attend him at a safe distance when he was out shooting, to pick up wounded birds.”¹

Dr. Stuart of Chirnside records that upon one occasion a “cottoned” fleece—that is, one taken from a sheep out of health, and in which the wool is all matted together—was lowered over the precipice at Hawksheugh to the Falcon’s nest for the same purpose as the blanket was employed by Mr. Wilson and his friends.²

The Peregrine is said to have bred at Blakey on the coast near Burnmouth in 1875, when a young one was found at the bottom of the rock there;³ and Mr. Hardy notes that on the 12th of June 1877 he saw a pair of Falcons fly from their eyrie below the Standing Man or Souter Rock, a short distance to the west of the mouth

¹ Letter from Mr. John Wilson, Chapelhill, Cockburnspath, dated the 2nd of July 1888.

² *Hist. Ber. Nat. Club*, vol. xi. p. 242.

³ Information from Mr. John Crockett, salmon-fisher, Burnmouth.

of Dowlaw Burn.¹ The Peregrine nested at Fast Castle in 1879, and at Lumsden rocks in 1880.² In 1881 it had its eyrie in the cliff at Hawksheugh, near Fast Castle;³ and in the following year it appears to have nested at Blakey.⁴ Mr. J. Campbell-Noble has informed me that the eyrie was at Earnsheugh in 1885. On the 22nd of April 1886, a pair of Peregrines were seen by Mr. W. Evans, Edinburgh, at Fast Castle, where they appeared to be nesting; and the young were observed there in the following June.⁵ The eyrie at Fast Castle was again occupied in the summers of 1887 and 1888.⁶

In former times this species had its home in precipices on the banks of the Whitadder, and in the Lammermuirs, as well as upon the sea-coast. Mr. John Wilson, late of Edington Mains, the well-known author of *British Agriculture*, has informed me that, about the beginning of this century, it bred every year in a high, red scaur at the "Blue Braes" on the south bank of the Whitadder, a short distance above Hutton Hall Mill, the nest being placed under an overhanging ledge of rocks immediately above a very deep pool called "Patie's Pat." The picturesque scenery on the river there, near the old tower of Hutton Hall⁷—the ancient seat of the Homes and the Johnstons—would then possess an additional interest to all lovers of

¹ Mr. Hardy's *M.S. Notes*.

² *Hist. Ber. Nat. Club*, vol. ix. p. 387.

³ Information from Mr. W. Edington, Dowlaw.

⁴ Information from Mr. John Crockett, salmon-fisher, Burnmouth.

⁵ Information from Mr. W. Evans, Edinburgh.

⁶ Information from Mr. W. Edington, Dowlaw, in letter dated the 20th of July 1888.

⁷ One of the most picturesque seats on the banks of the Whitadder, mentioned in a ballad celebrating one of Johnnie Armstrong's rides—

Then they're come on to Hutton-ha,
They rade that proper place about;
But the laird he was the wiser man,
For he had left na geir about.

Pennant's Tour, ii. p. 276

nature, for, to its romantic beauty in the spring and early summer months, would be added the charm of

A pair of Falcons wheeling on the wing,
In clamorous agitation.

WORDSWORTH, *Excursion*.

My friend Dr. Stuart of Chirnside mentions that his brother-in-law, the late Mr. Abraham Edgar of Hutton Manse, was lowered over the cliff at the "Blue Braes" with a rope, about 1826, and took the young Falcons from the nest.¹ The Peregrine seems to have occasionally frequented this neighbourhood for some years afterwards, for Mrs. Fairbairn, late of Allanton, relates that a specimen in the second year's plumage was shot between Hutton Hall and the "Blue Braes" in 1833.² The red scaur, which is now the home of a colony of Jackdaws, can be seen from a distance in the direction of Chirnside, and as it is of considerable height and precipitous, it was one of the most suitable places on the banks of the Whitadder for the eyrie of the Falcon. The rock under which the nest was placed has now fallen down, and the Peregrine has not bred there for the last sixty years.³

Lady John Scott-Spottiswoode of Spottiswoode has been so good as to inform me that, in former times, a "Blue Hunting Hawk" used to rear its young at Corbie's Heugh—a crag over the Bruntiburn—on Raecleugh Farm;⁴ and Mr. Peter Scott, Lauder, whose father was for many years

¹ *Hist. Ber. Nat. Club*, vol. xi. p. 242.

² Information from Mrs. Fairbairn on the 17th of October 1887.

³ Mr. William Patterson, late of North Berwick Abbey Farm, who, when he was a boy, lived near Duns, has informed me that his father told him that the Laird of Hutton Hall estate, on which the Falcon's nest at the "Blue Braes" was situated, had a pair of trained Falcons for hawking, and getting tired of keeping them, gave them their liberty. They remained in the neighbourhood of Hutton Hall and nested in the red scaur. This occurred about the middle of last century, and was said to have been the origin of the Falcon's nest at the "Blue Braes."

⁴ Letter from Mr. P. Stormonth Darling, Kelso, her ladyship's factor, dated the 5th of March 1886.

head gamekeeper to the Earl of Lauderdale, states that, about fifty years ago, the Peregrine nested annually on a precipice three or four miles up the Longcroft Water, in the parish of Lauder.

Although it does not now breed in any of the inland districts of the county, it occasionally makes its appearance in localities at a distance from the coast. A male frequented the tall trees by the side of the Tweed near Paxton House for a short time in the summer of 1871, and a female was killed near Leitholm, on the 8th of May 1875, by a man who was shooting Cushats, the Falcon having swooped down at a stuffed Wood Pigeon which he had placed on the ground as a decoy.¹ Dr. Stuart of Chirnside records that, on the 14th of January 1880, a Peregrine was captured by a gamekeeper at Edington, who, observing a Cushat newly killed near the place where young Pheasants were usually reared, set a trap by the side of the dead bird and secured the Falcon, which was in immature plumage.² In July 1881 a specimen was trapped near Quixwood.

The Peregrine Falcon is generally to be found on the sea-coast of the county at all seasons of the year, but it is probable that the young migrate southwards in autumn along with other passing birds of this species, which then leave the northern regions of Europe for the south with the vast flocks of migrants on which they prey, and return in spring, at both of which periods the Peregrine is seen on migration at the lighthouses on the coasts of England and Scotland.³

It chooses for its nesting place a crevice or shelf in some lofty and inaccessible cliff on the sea-coast, and has eggs in

¹ *Hist. Ber. Nat. Club*, vol. ix. pp. 18, 19.

² *Ibid.* vol. ix. p. 387.

³ *Reports on the Migration of Birds*, 1879-86.

April or about the beginning of May. It appears often to change the site of its breeding quarters from one favourite part of the sea-board to another, at irregular intervals, but sometimes continues to occupy the same eyrie for a number of years in succession. The eggs, which are generally deposited on the bare earth,¹ are three or sometimes four in number, and are of a dull yellow, thickly mottled and blotched with dark reddish brown. The young, which are at first covered with white down, are usually ready to be taken for taming about the second week in June, and towards the end of that month they may be seen sitting about the rocks in the neighbourhood of the nest. After leaving their eyrie, and until their first moult, the general colour of the upper parts of the young is brownish ash, the edge of each feather being rufous. The under parts are dirty white, with dark longitudinal streaks. In the adult birds of both sexes the upper parts are bluish slate colour barred with a darker tint—hence the local name of “Blue Hawk”—and the under parts rufous white, with dark brown transverse bars. The irides are dark hazel brown. The female, which is much larger and more powerful than the male, was, in the palmy days of hawking, known as “The Falcon,” whilst the male was called the “Tercel-gentle.”²

The flight of the Peregrine is very rapid, and resembles

¹ Mr. Peter Cowe has informed me that when he climbed to the Falcon's eyrie at Fast Castle in 1860, he saw very little appearance of a nest in the crevice of the cliff where the young birds were; and Mr. John Wilson, Chapelhill, says that when he was engaged with Mr. W. Cowe taking the young Falcons in their eyrie there in June 1866, he observed scarcely any nesting materials around them. In the case of a Peregrine's eyrie on an inland precipice in Inverness-shire which I personally examined in May 1866, the eggs were merely deposited in a little hollow scraped in the earthen floor of the crevice in the rock.

² It is said to have derived the name of “Tercel” from being about one-third smaller than “The Falcon,” but some authorities state that of the three young birds usually found in the nest of the Peregrine, two are females, and the third a male, which, on this account, is called the “Tercel.” See Harting's *Ornithology of Shakespeare*, p. 52.

that of the Rock Dove. It searches over the open country or along the sea-shore for prey, which it takes by suddenly swooping down with a perpendicular or slanting descent, or by direct pursuit; but the Falcon always endeavours to keep above the quarry until a favourable opportunity of seizing it occurs.

On the sea-coast it feeds chiefly upon sea-fowl and their young, and also on Rock Doves. In inland districts, game and Wood Pigeons form its principal quarry.

The following places in the county appear to have derived their names from eyries of this Falcon:—Hawksheugh, a cliff a short distance to the north of Bleakheugh, on the coast, about a mile north of Burnmouth; Hawksheugh or Castle-holes Heugh, near Fast Castle; and Hawksheugh, a precipice on the coast near Cockburnspath. It is probable that Hawkslaw,¹ a farm in the parish of Coldstream, and Huxton, a small farm near the Grange Wood in Coldingham parish, have derived their names from the same source. A part of Hallydown estate was known as Hawkslaw in 1764.²

¹ Called Hawkisland in a charter by Oliver Cromwell of the Lordship and Barony of Swinton, &c., dated the 26th of November 1656. See *The Swintons of that Ilk and their Cadets*, by Archibald Campbell-Swinton of Kimmerghame, July 1883.

² Mr. Hardy's *M.S. Notes*.



FALCONRY IN BERWICKSHIRE.

*Next will I sing the valiant Falcon's fame.
Aërial fights where no confederate brute
Joins in the bloody fray; but bird with bird
Jousts in mid air.*

SOMERVILLE, *Field Sports*.

BEFORE the introduction of the fowling-piece, and for centuries afterwards, until guns were so much improved that the art of shooting birds on the wing was acquired by sportsmen, hawking was one of the chief field sports in Scotland. It was a favourite amusement of many of our kings, noblemen, and others, who could afford the great expense which attended it,¹ and ladies delighted to accompany the falconers to the field.

It is a very ancient sport, having been followed in the East more than 2000 years ago; in England it appears to have been practised as early as the eighth century, and in the celebrated Bayeux Tapestry Harold is represented with a Hawk upon his hand.

After the Norman Conquest it seems to have advanced rapidly, and in the succeeding centuries the rank of an individual was indicated by the kind of Hawk carried on the wrist—thus, the Gyr Falcon was carried by the king,² the Peregrine by an earl, while to ladies belonged the Merlin.

¹ The expense connected with falconry is mentioned in an Act of the Scottish Parliament the 1st of November 1600:—"For sa-meikle as by common consuetude of all countries, special prohibition is made to all sorts of persons to slay Wyld-foull, Hair, or Vennison, except sik as by their revenues may bear the charges and burdings of the Hawkes, Houndes, and Dogges, requisite in sik pastymes," &c.

² The gentle Faucon that with his fete distrelneth
The king's hand.

CHAUCER, *The Assemble of Foules*, 1561.

The Ladye by the altar stood,
 Of sable velvet her array,
 And on her head a crimson hood,
 With pearls embroidered and entwined,
 Guarded with gold, with ermine lined;
 A Merlin sat upon her wrist,
 Held by a leash of silken twist.¹

One of the earliest historical references to falconry in Scotland occurs in the *Liber S. Marie de Melros*, where we find it recorded that, in the reign of William the Lion, when Robert of Avenel gave to the Church of St. Mary of Melrose the territory of Eskdale, he reserved, along with the game, the eyries of Hawks—"accipitrum et spervetiorum nidos."² From the *Exchequer Rolls of Scotland* it appears that in 1263 Alexander III. had a falconer at Forres.³ The old Earls of Dunbar, the powerful descendants of Cospatrick, at one time had a residence at Earlstoun. "At the east end of the village there was once a stronghold designated the Earls' Tower, and on what is now termed the Hawk Kaim, the hawking house of the earls is believed to have stood."⁴ During the War of Independence, Patrick, the 4th Earl of March and Dunbar, strenuously supported Edward I., and he and that great English king were on the most friendly terms. On one point they were thoroughly in unison—their mutual fondness for the noble pastime of hawking. This transpires among the *Documents relative to the History of Scotland*, published under the direction of the

¹ *The Lay of the Last Minstrel*, canto vi. 5. Sir Walter Scott in his notes says: "A Merlin or Sparrow-Hawk was actually carried by ladies of rank, as a Falcon was, in time of peace, the constant attendant of a knight or baron. Godscroft relates that when Mary of Lorraine was Regent, she pressed the Earl of Angus to admit a royal garrison into his castle of Tantallon. To this he returned no direct answer; but, as if apostrophising a Goshawk, which sat on his wrist, and which he was feeding during the queen's speech, he exclaimed, 'The devil's in this greedy glede; she will never be full.'"—Hume's *History of the House of Douglas*, 1743, vol. ii. p. 181.

² *Liber S. Marie de Melros*, vol. i. p. 39: *Bannatyne Club*.

³ *Exchequer Rolls of Scotland*, 1264-1269, pp. 7-15.

⁴ "Earlstoun," by James Tait, Falconhall, Kelso.—*Hist. Ber. Nat. Club*, vol. v. p. 263.

Lord Clerk Register, edited by the Rev. Joseph Stevenson;¹ and as the same Hawks which were used at Dunbar, the principal seat of the earl, would doubtless be taken to Earlston in the hawking season, the following entries have a certain local reference.

First of all, the earl visits the king in England, and on that occasion presents him with a Goshawk (*Astur*) on departing, and leaves behind him his falconer, whom the king afterwards allows to return home with a Falcon that the king had borrowed when staying in the castle of Dunbar, or, at least, had used when resident there:—

“EARL PATRICK.”

1296-7.		£	s.	d.
To the Lord Patrick, Earl of March, on returning to his own parts, of the gift of the king, as his personal expenses of his journey home, by the king's own hands at Ipswich, on the first day of January .	xx	—	—	

“A CERTAIN FALCONER OF EARL PATRICK.”

To Elias Spot, falconer of Earl Patrick of Dunbar, who remained with the king in attendance on John de Bickenore, with a certain Goshawk which the same earl had presented to the king during the season of Goshawks, licenced by the king to return to his said lord with a certain Falcon which the said king had in the Castle of Dunbar, in the foresaid year, of the gift of the said king, by his own hands, at Plumpton, the last day of April	i	—	—
---	---	---	---

To the same, of the gift of the same king, to defray his expenses in returning as foresaid is, to Earl Patrick, vizt:—From Plumpton into Scotland, for xiiij days, and for feeding and liming [luring?] his said Falcon, for the same time, by his own hands, in the same place, in the same day	—	xvj	iiij
--	---	-----	------

To the same, for his expenses for vij days, coming from London to the king, at the mandate of the king himself, on the xxij day of April for the last reckoning, receiving by the day xijd, and for the expenses of two horses and a boy of his staying for vij days at the court before his departure towards Scottish parts as foresaid is, the last day of April for

¹ Vol. ii. pp. 136, 137.

1296-7.

£ s. d.

the latest reckoning, receiving by the day vij. 0, by
his own hands, in the same place, the first day of
May, of the gift of the king¹ — xj iiijd 0

From an ancient Rental of Coldingham, drawn up after the battle of Falkirk, which took place on the 22nd of July 1298, we find that there were at Coldingham at that period two eyries of Falcons which were not saleable.² On the 25th of October of that year Edward I. of England granted to Walter de Money all the eyries of "Falcons gentilz" in his demesne lands of Scotland, for his life, for the yearly payment of "deux piers bien affaitez."³ In 1329, shortly before the death of King Robert the Bruce, there appear in the Rolls payments for repairing and surrounding with a fence the house for his Hawks at his manor of Cardross.⁴ Later in the same century Falcons were brought to David II. from John of the Isles.⁵ James III. seems to have been devoted to falconry, for in his reign falconers were specially sent to Orkney for Hawks;⁶ and in his seventh Parliament, which was "halden at Edinburgh, the ninth daie of May, the zeire of God, ane thousand, foure hundreth, seventie foure zeires," he statutes and ordains—"That in time cumming na manner of persons take ane uther man's hounds nor haulkes, maid or wilde, out of nestes, nor eggs out of nestes, within ane uther mannis ground, but licence of the Lord, under paine of ten poundes. And in likewise that na egges be tane out of the Pertrickes nor Wilde-duik-nests,

¹ I am indebted to Mr. Hardy for the above interesting extracts about Earl Patrick.

² *The Correspondence, Inventories, Account Rolls, and Law Proceedings of the Priory of Coldingham: Surtees Society*, 1841.

³ *Calendar of Documents relating to Scotland*, vol. ii., 1272-1307, p. 261.

⁴ *Accounts of the Lord High Treasurer of Scotland*, vol. i., 1473-98, Preface, pp. cxxlviii., cxxlix.

⁵ *Exchequer Rolls of Scotland*, vol. i., 1264-1379, p. 511.

⁶ *Ibid.* vol. viii. p. 276.

under the paine of fourtie shillings.”¹ The numerous entries in the *Accounts of the Lord High Treasurer of Scotland* of expenses connected with falconry during the reign of James IV. show that “the champion of the dames” was passionately fond of that sport, and we find one to the effect that “on monnunda the iiij da Januar” 1489, the king “raide to Lauder to the halkin,”² the extensive common there being well suited for that purpose. On the 19th of November 1496 he appears to have visited Home with his falconers,³ where he remained for ten days, and would doubtless enjoy good sport with Lord Home and other noblemen of the Merse, for they would be able to show him not only abundance of the ordinary kinds of game, such as Partridges, Black-game, and Grouse, but likewise Herons and Bitterns in the extensive marshes and bogs which then covered the surface of the county in every direction. “In pursuing the sport the falconers rode on horseback, for the sake of following the rapid movements of the Hawks, and were accompanied by dogs⁴ for the purpose of ‘serving’ the Hawks or raising the quarry. This was sometimes done by persons who accompanied them on foot. Such were the ‘laddis that ran with the king at the halking,’ and the ‘childer that chasit dukis in the dubbis and set thaim up to the halkis.’”⁵

¹ *The Laws and Acts of Parliament made by the Kings and Queen of Scotland*. Collected by Sir Thomas Murray of Glendook: Edinburgh, 1681, p. 64.

² *Accounts of the Lord High Treasurer of Scotland*, vol. i., 1473-98, p. 127.

³ *Ibid.* p. 306.

⁴ “It was usual on excursions of the kind to be accompanied by a water-dog, because the Hawk and its prey sometimes both fell in the water; and in their struggles the Wild-fowl, from its greater power when on the surface of that element, frequently imperilled the safety of the Hawk by plunging and diving. The fowler, meanwhile watching his bird in case of danger, would send the dog to the rescue, which was so trained that it never attempted to injure the Hawk, but seized the Mallard, or whatever fowl it might be, and brought it to its master.”—Folkard, *The Wild Fowler*, p. 12.

⁵ *Accounts of the Lord High Treasurer of Scotland*, vol. i., 1473-98, Preface, p. ccliii.

A trained Falcon was of great value, and was a fitting present for a prince to give or receive. On the 21st of September 1488 James IV. gave £180 to the "Erle of Angus for a Halk;"¹ and large sums were paid for the expenses of falconers going in the beginning of May to "the Northland for Halkis."²

In a royal *inspeximus* granted by the same king at Edinburgh, on the 24th of February 1490, of a charter in favour of the Prioress of the Cistercian Abbey of Coldstream, of a ploughgate of land in the town of Lanele, in the sheriffdom of Berwick, granted at "Caldstreme," on the 24th of June 1489, by John Liddell of "Lanele," the *reddendo* is fixed at a *pair of hawking gloves*, or twelve pennies.³ In this charter hawkings, huntings, and fishings are specially conveyed,⁴ as was usual in deeds of the kind at that period.

About this time it seems to have been the habit of gentlemen to carry their Hawks constantly with them, and even to take them to church. Alexander Barclay, who lived in the time of James V., thus alludes to this unseemly custom:—

Into the church then comes another sotte,
Without devotion, jetting up and downe
Or to be seene, and to shoue his garded cote;
Another on his fiste a Sparhawke or Fawcone.

One time the Hawkes bells jangleth hye,
Another time they flutter with their winges;
And now the houndes barking strikes the skye,
Now sounde their feete, and now the chanyes ringes,
They clap with their handes: by suche maner thinges
They make of the church for their Hawkes a mewe,
And canel for their doges, which they shall after rewe.⁵

Mary Queen of Scots, like her ancestors, was fond of

¹ *Accounts of the Lord High Treasurer of Scotland*, vol. i., 1473-98, p. 96.

² *Ibid.* pp. 177, 200, 275.

³ *Chartulary of the Cistercian Abbey of Coldstream*, by the Rev. Charles Rodgers, 1879, Preface, p. xix.

⁴ *Ibid.* p. 51.

⁵ Sibbald, *Chron. Scot. Poet.*, vol. ii. pp. 437, 438.

hawking, and it is in her reign that we first hear of the gun being used in Scotland to kill wild-fowl, "quhair-throw, the Noblemen of the Realme, can get na pastime of halking and hunting like as has bene in times by-past." The destruction to sport, "be occasion foresaid," seems to have been considered so serious, that on the 29th of May 1551 the Scottish Parliament passed the following Act—"Anent them that schuttis with gunnis at Deare and Wilde-fowle":—"The samin daye, for-sa-meikle as it was devised, statute, and ordained of before, that nane of Our Soveraine Ladies Leiges, sulde take upon hande to schutte with Halfe-hag, Culvering, or Pistolet, at Deare, Rae, Wilde-beasts, or Wilde-fowles, under the paine of death: Notwithstanding Our Soveraine Ladies Leiges daylie and continuallie in-contrair the tenour of the Actes maid thereupon, incurrand the paines contened in the samin, schuttis with the Halfe-hag, Culvering, and Pistolette, at the saidis Wilde-beastes and Wilde-fowles, quhair-throw the Noblemen of the Realme, can get na pastime of halking an hunting, like as has bene had in times by-past, bee reason that all sik Wilde-beastes and Wilde-fowles ar exiled and banished, be occasion foresaid, etc: It is ordained that nane of Our Sov. Ladies Leiges, of quhat-sumever degree hee be of, take upon hande to schutte with Halfe-hag, Colvering, or Pistolet under the paine of death and confiscation of all their gudes. The taker sall have the escheit of the persones gudes hee apprehendis and sall be rewarded utherwaies, as accordis for his laboures."¹

On the 20th of June 1555 another Act was passed "Anent the slaying of wilde-beasts, wilde-fowles, halking and hunting," whereby it was enacted that "na man take in hand to ryde or gang in their nichbouris corne in halking or hunting, fra the Feast of Pasche unto the

¹ *The Laws and Acts of Parliament made by the Kings and Queen of Scotland.* Collected by Sir Thomas Murray of Glendook: Edinburgh, 1681, p. 142.

time that the samin be schorne, and that na man ryde or gang upon quheate na time of the zeir, and that na Partrick be taken unto the Feaste of Michael-mes. Ten poundes for the first fault, twentie poundes the nixt, and the thrid fault escheitting of their guds moveable."¹ A third Act was passed at the same date "anentis stealing of Halkes," and it was extended to "the fowlers lyand at wait with their nettes."² Hawking must have been a favourite sport of King James VI., for we find him in his first Parliament, on the 15th of December 1567, passing a severe Act to the effect "that quhat-sum-ever person or personis, of quhat Estaite, degree or conditioun that ever they be of, schuttis in ony times cumming with Culvering, Cros-bow or Handbow at Dae, Rae, Hart, Hunde, Hair, Cunning, Dow, Herron, or foule of river within this realm, sall foirfault and tyne their haill moveable gudis," and for the next fault in the case of "ane vagabound not havand gudis," to "cut of his richt hand."³ During this king's reign no fewer than ten Acts for the preservation of game, and against "schutting with gunnes at wylde-fowles," were passed between 1567 and 1621, including one on the 4th of August of the last-mentioned year which bore "That no man Hunt nor Halk at any time hereafter, who hath not a Plough of land in Heritage under the paine of ane hundredth pounds;"⁴ another of the same date being "Anent the harrying of Haulke Nests, and hunting in Snow."⁵

In the reign of James VI., Sir George Home of Wedderburn, who was born about 1550, and succeeded to the family estate in 1574, seems to have been very fond of hawking. Godscroft, in his *MS. History of the Homes of*

¹ *The Laws and Acts of Parliament made by the Kings and Queen of Scotland.* Collected by Sir Thomas Murray of Glendook: Edinburgh, 1681, p. 157.

² *Ibid.* p. 158. ³ *Ibid.* pp. 186, 187. ⁴ *Ibid.* p. 479. ⁵ *Ibid.* p. 479.

Wedderburn, says of him: "He was very handsome and well-proportioned, and of great strength, and swift of foot. He sang after the manner of the Court, and likewise psalms to his own playing on the harp. He was a keen hunter and delighted in hawking. He was so much given to that sport that he built a hunting lodge called Handaxe Wood, in the Lammermuir Hills, in which he often spent the night. He had Hawks called Merlins and Falcons, and afterwards another kind called Tercells,¹ which he delighted in even in his old age. He caught both Partridges and Muir-fowl."²

Falconry appears to have been a common sport in Berwickshire towards the end of the seventeenth century, and Mr. Campbell-Swinton of Kimmerghame relates in his *Men of the Merse* how a party of Merse lairds about this time went "to the setting at Kettleshiel, where the dogs set several times; but it was either an old fowl who rose before the net was ready, or young fowls that were scattered, so that there was none caught by the net but ane old han; but a hawk of Cavers³ took severals, and some were marked where they sat down and were taken."

About the beginning of the eighteenth century guns⁴ had been so much improved that sportsmen began to shoot game on the wing, and this seems to have led to the abandonment of hawking, a pastime which had delighted successive generations from the days of William the Lion.

Towards the close of the eighteenth century a consider-

¹ Male Goshawks (*Astur palumbarius*). The female Goshawk was known as the Goshawk, and the male, which is smaller than the female, as the Tercel. The female Peregrine was known as the Falcon, and the male, which is considerably smaller, as the Tercel-gentle.—Harting's *Ornithology of Shakespeare*, p. 53.

² I am indebted to Colonel Milne Home of Wedderburn for the use of the *M.S. History of the Homes of Wedderburn*, from which the above is extracted.

³ Carre of Cavers, who was also Laird of Nisbet.—*Men of the Merse*, pp. 59, 60.

⁴ They were formerly such miserable machines that in the middle of the fifteenth century it took a quarter of an hour to charge and fire one.—Hallam's *Middle Ages*, vol. i. p. 342.

able effort was made to revive hawking in England, and about 1780 it had again become a common sport in Scotland.¹ Mr. Baird, a younger brother of Sir David Baird of Newbyth, in East-Lothian, kept Falcons in the early part of the present century, and he sometimes got his Hawks from their eyries on the coast of Berwickshire. Lady John Scott-Spottiswoode of Spottiswoode informs me that amongst her very earliest recollections are the occasional visits of Mr. Baird to Spottiswoode, with his Hawks, where he flew them at Grouse on the moors.²

The gun is now used to kill game of all kinds, and with such skill that driven Grouse and Partridges are shot with precision, even when flying at their utmost speed.

Time is like a fashionable host,
That slightly shakes his parting guest by the hand ;
And with his arms outstretched as he would fly,
Grasps in the comer : welcome ever smiles,
And farewell goes out sighing.

SHAKESPEARE, *Troilus and Cressida*.

¹ *Falconry in the British Isles*, by Francis H. Salvin and W. Broderick, 1855.

² Information in a letter from Mr. P. Stormonth Darling, Kelso, dated the 10th of April 1886.



THE HOBBY.

Falco subbuteo.

*Like Larks when they the tyrant Hobby spy,
Some, wonder-struck, stand fix'd, some fly.*

COWLEY.

THE Hobby, which may be described as a Peregrine in miniature, very seldom visits Berwickshire, and then apparently only on migration, there being no record of its nest having been found in the county.

Sir Walter Elliot of Wolfelee mentions that when the Berwickshire Naturalists' Club visited Lauder on the 24th of June 1869, they saw in the museum of a local collector—Mr. Walter Simson, shepherd, Thirlestane Castle—a specimen of the Hobby which had been killed in that neighbourhood;¹ and Mr. John Ferguson records that two examples were shot in the vicinity of Duns in 1874, one of them being got at Kimmerghame.²

The Hobby possesses considerable powers of flight, and was formerly used in falconry to take Larks and other small birds.

¹ *Hist. Ber. Nat. Club*, vol. vi. p. 18.

² *Ibid.* vol. vii. p. 284.



THE MERLIN.

STONE FALCON, ROCK HAWK, SMALL BLUE HAWK.

Falco aesalon.

*Saving there came a little gray Hawke,
A Merlin him they call,
Which untill the grounde did strike the grype,
That dead he downe did fall.*

PERCY, *Sir Aldingar.*

THIS beautiful little Falcon is occasionally seen throughout the lower parts of the county in the autumn and winter months, and its nest is sometimes found during summer in the rocky deans of the Lammermuirs.

At the second anniversary meeting of the Berwickshire Naturalists' Club, which took place at Duns on the 18th of September 1833, the Rev. Andrew Baird of Cockburnspath mentioned in his presidential address that a Merlin had been shot at Blanerne, on the Whitadder;¹ and Dr. Johnston of Berwick, writing on the 24th of April 1847, says: "To-day Mr. William Dunlop brought me a specimen of the male Merlin which he had shot on the moor above Mayfield on the 22nd inst. On the previous day he saw the bird strike down a Partridge."² In the spring of 1872 a young male was killed in the Crow Dean Wood at Paxton; and in February of the following year a male in full plumage was shot in the adjoining plantation of Finchy.³ According to Mr. Andrew Kelly, it is by no means rare in the Lauderdale district. A young female was trapped by the game-

¹ *Hist. Ber. Nat. Club.*, vol. i. p. 14.² *Ibid.*, vol. ii. p. 220.³ *Ibid.*, vol. vii. p. 379.

keeper of Quixwood, at a Partridge which it had killed, in October 1878;¹ and Mr. Hardy records that an example occurred at Knock Hill, four miles from Duns, in the spring of 1879.² Mr. W. Smith, gamekeeper, Duns Castle, informs me that about 1880 he shot a Merlin near Greenlaw, and another at Murraylawrigg. In 1882 a specimen was killed at the "Cockit Hat" plantation on Lamberton Moor, where this bird is said to be frequently seen.³ Mr. Hogg has informed me that it is very destructive to the Partridges at Quixwood after the pairing time in spring.

The Merlin was in great repute with falconers in former times on account of its courage and the rapidity of its flight, as well as its capability of being readily trained. Godscroft, in his *MS. History of the Homes of Wedderburn*, written in 1611, mentions that Sir George Home, who lived in the time of James VI. of Scotland, had Hawks called Merlins, with which he caught both Partridges and Muir-fowl.⁴

It was the favourite Hawk of ladies in the palmy days of falconry, and was carried on the wrist. It is trained at the present day for the purpose of being flown at Larks, when it shows excellent sport.

A local writer on falconry says: "I once witnessed a most interesting flight between two Merlins in a wild state and a Snipe. As I was crossing Lamberton Moor, accompanied by a gentleman of Berwick, we happened to see two of these birds mounting almost perpendicularly in the air within a few paces of us. Our first impression was that they were amusing themselves by endeavouring to soar above each other, but on watching their movements for a short time we soon discovered the object of their pursuit

¹ Mr. Hogg of Quixwood showed me this specimen on the 18th of October 1882.

² *Hist. Ber. Nat. Club*, vol viii. p. 532.

³ Information from Mr. James Purves, gamekeeper, Mordington House.

⁴ See article on "Falconry in Berwickshire," pp. 17, 18, *supra*.

only a short distance above them. One of the Hawks appeared from this time to gain rapidly upon the Snipe, whilst the other appeared to make but little progress. At length, and when the Snipe and foremost Hawk had almost disappeared in the sky, the latter, having apparently gained the ascendancy, made a rapid stoop, but the former, by a sudden change in its course, eluded the stroke, and, having thrown its antagonist, made now a descent like a falling star. At this moment the Hawk that had kept below, no doubt waiting for this event, darted like lightning across the sky towards it, which, however, the Snipe, by another dexterous shift, escaped also. Still, all was in vain on the part of the pursued, for before it got many yards the other Hawk shot down upon it and received it in its talons."¹

The flight of the Merlin when on the outlook for prey is generally at no great height above the ground, and in autumn it may be sometimes seen sweeping along our hedge-rows, where

On the haw-clustered thorns, a motley flock
Of birds of various plume and various note,
Discordant chirp.²

The prey of this Falcon usually consists of the smaller kinds of birds, such as Larks, Yellow-Hammers, Chaffinches, and Thrushes, but it likewise attacks Snipes, Plovers, Partridges, and Pigeons. It also feeds upon the larger insects and beetles, the wing-cases of which are seen in its castings.³

A tame Merlin which I kept in 1867-68, and which was taken from a nest in Glen Urquhart, Inverness-shire, in the summer of the former year, used to spread its wings and tail around small birds given to it as food, after seizing them with its claws.

¹ *Treatise upon Falconry*, by James Cockburn Belany, Berwick-on-Tweed, 1841.

² Grahame, *The Rural Calendar*, November.

³ Seebohm, *History of British Birds*, vol. 1. p. 87.

This species usually places its nest on the ground amongst heather, on the sloping side of some rocky ravine. In May 1865 Mr. William Cowe showed me a spot of this kind on the farm of Dowlaw,

In a glen
Down which a little stream had furrowed deep,

and told me that he had found the eggs there in the previous summer. Mr. Kelly mentions that it breeds on the rugged, heathery braes at Broadshawrig;¹ and the Rev. George Cook, Longformacus, informs me that he lately saw an egg which had been found on the moor above Byrecleugh. Very few materials are used in the construction of the nest, the eggs, which are four or five in number, and reddish brown in colour, like those of the Kestrel, generally resting on a little dried grass or a few pieces of heather.

A ravine near the Meikle Law, in the parish of Longformacus, is called the Merlin Grain.

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 146.



THE KESTREL.

WINDHOVER, STONEGALL, STEINGALL, STANNEL, RED HAWK.

*Falco tinnunculus.***The Keelie, The Keelie Hawk.***Oft hovering o'er the barn-yard is she seen
In early spring.*GRAHAME, *Birds of Scotland.**And with what wing the Stanniel checks at it!*SHAKESPEARE, *Twelfth Night.*

THE Kestrel is more frequently seen in the county during spring and summer¹ than any other rapacious bird, with the exception of the Sparrow-Hawk, from which it may be easily distinguished by its habit of hovering in the air from time to time when searching for prey. Unfortunately, it is often observed nailed up on gamekeepers' vermin rails, although it is one of our most harmless birds of prey, as far as game is concerned, for its food consists chiefly of mice. It occasionally seizes young Pheasants, however, when they are being reared, and I have seen it attack a young Hare. It also feeds upon small birds; but they do not seem to be much afraid of

¹ This species has been observed on migration at the lighthouses on the coasts of England and Scotland, and it is probable that most of our Berwickshire Kestrels pass southwards at the beginning of winter, although some of them remain on the sea-coast of the county during that season. Mr. Hardy mentions in his *M.S. Notes* that he saw two at Penmanshiel on the 17th of January 1860. He also records (*Hist. Ber. Nat. Club*, vol. vii. p. 283) that he observed one near Oldcambus on the 23rd of December 1874 during the continuance of a heavy snowstorm; and (*ibid.* vol. ix. p. 125) that a specimen was seen at Oldcambus on the 31st of January 1879, much snow being on the ground at the time.

it, for, on the 12th of January 1888, I noticed a male Kestrel sitting on an ash-tree on the farm of Girrick, in the parish of Nenthorn, while several Greenfinches and a Yellow-Hammer were hopping about on the branches within a few feet of its perch. Frogs and beetles also form a part of its food.

It frequents the precipitous rocks on the sea-coast of Berwickshire, where it breeds, some of its favourite nesting places being near Siccar Point, Fast Castle, Blakey, and the Coal Point at Lamberton. It likewise resorts to inland cliffs on the Whitadder and Blackadder, such as the Raven's Knowe near Tibbie Fowler's Glen, and the scaur at Blackcastle Rings on Greenlaw Moor, where the Fangrist joins the Blackadder.¹ Buildings² are sometimes frequented by this Hawk, and in the wooded parts of the county it frequently takes possession of the deserted nest of a Magpie, Crow, or Wood Pigeon, in a spruce or Scotch fir, laying four or five eggs of a reddish-brown colour.

Its cry, "keelie, keelie, keelie," may be often heard in the breeding season near its haunts.

The Kestrel was formerly used in falconry, but was not much valued for this purpose, and was consequently assigned to persons of inferior rank.³

¹ When I visited Blackcastle Rings with Mr. Loney, Marchmont, on the 14th of July 1886, he informed me that he had occasionally observed the Kestrel's nest there.

² Mr. Peter Scott, Lauder, tells me that about twenty-five years ago the Kestrel used to nest regularly every season in the drainage holes of the bridge near the Saw Mill at Thirlestane Castle.

³ Mr. Harting, in his *Ornithology of Shakespeare*, p. 74, says: "The origin of the word 'Kestrel' is somewhat uncertain. By some it is derived from 'coystril,' a knave or peasant, from being the hawk formerly used by persons of inferior rank, as we learn from Dame Juliana Berners in her *Boke of St. Albans*. This opinion is strengthened by the reading 'coystril' in *Twelfth Night* (act i. sc. 3) and 'coistrel' in *Pericles* (act iv. sc. 6)."

THE OSPREY.

FISH HAWK, FISHING EAGLE, BALD BUZZARD.

Pandion haliaëtus.

*The sailing Osprey high is seen to soar,
With broad unmoving wing, and circling slow,
Marks each loose straggler in the deep below;
Sweeps down like lightning, plunges with a roar,
And bears his struggling victim to the shore.*

ALEXANDER WILSON.

THIS interesting bird occasionally visits the sea-coast and rivers of Berwickshire during the time of its migration northwards in spring, and southwards in autumn.

Sir Walter Elliot says that it seems to appear periodically on the Tweed, and, quoting from Sir William Jardine, relates that two Ospreys were killed on Lord Home's property in 1835.¹ According to the *Berwick Advertiser* of the 30th of May 1831, one was obtained on the Blackadder in that year.² A specimen was shot many years ago in autumn on the Whitadder, near Ninewells Old Bridge, by Mr. John Blackadder, East Blanterne, who states that he stalked it while it was perched on a tree by the side of the river, which was in heavy flood at the time.³ Mr. Peter Hastie, Milne Graden East Mains, has informed me that one day in September 1864 he saw two birds of this species sitting on the rocks opposite Cockburn Mill, his attention having been called to them by the loud quacking of the Ducks which

¹ *Hist. Ber. Nat. Club*, vol. vi. p. 320.

² Dr. Johnston's *M.S. Notes*.

³ Information from Mr. John Blackadder on the 5th of August 1886.

were swimming in the stream and seemed to be greatly alarmed. He fired a shot at the Ospreys, but did not kill either of them, and they flew away along the Cockburn Braes. Shortly afterwards he heard that one of them had been so severely wounded by Mr. Andrew Bell, Cockburn, that it fell to the ground, but, recovering again, took wing in the direction of the Retreat, where it was found by a boy on the following day lying dead by the side of the Whitadder, and given to Mr. Bertram.¹ The occurrence of the subject of our notice on the Leader, near the Old Craw Ha' in 1867, and in the vicinity of Newmills Bridge a few years later, is recorded by Mr. Kelly.² The gamekeeper at Mordington relates that on a Sunday afternoon in September 1871 he saw a large bird, which was apparently unable to fly, floating down the Eye, which was in flood at the time, and the current taking it into the "lead" at Netherbyres Mill, Mr. Bell helped him to lay hold of it. It was found to have a trout nine inches long in its claws, and did not, on being pursued, relax its grasp of the fish. It seemed to have been wounded in the thigh by a gunshot. He took it to Ayton Castle, where Mr. Mitchell-Innes gave directions that it should be kept at the kennels and supplied with fish; but as food of that kind could not be got in a fresh state, no boats being at sea at the time, and as it would not eat rabbits' livers, which were offered as a substitute, it died.³ From further particulars given to me by the gamekeeper at Ayton Castle,⁴ the bird was evidently an Osprey. The late Mr. Alexander Leitch, Fairneside, mentioned to me some

¹ I saw this specimen in Mr. Bertram's possession at the Retreat in September 1883. He informed me that it measured five feet eight inches from tip to tip of the extended wings.

² *Hist. Ber. Nat. Club*, vol. vii. p. 520.

³ Information from Mr. James Purves, gamekeeper, Mordington, on the 28th of December 1885.

⁴ Mr. Hugh Fraser, now gamekeeper at Kelloe.

years ago that a bird of this species was seen frequenting the high rocks on the sea-coast near Burnmouth about the same time as the above incident occurred.

Mr Campbell-Noble tells me that two examples were observed haunting the rocks on the coast opposite Coldingham Shore in October 1886.¹

The Osprey feeds upon fish, which it takes by plunging into the water from a considerable height in the air and seizing them in its talons, or by swooping down and bearing them off in its claws when near the surface.²

In former times its eyrie was to be found on many of the remote lakes in the Highlands, but now it is seen in very few localities.

It is a migratory bird, leaving the northerly part of its range in autumn and wintering in the south of Europe and north of Africa.

¹ Information from Mr. Campbell-Noble, Coldingham, on the 13th of December 1886.

² A fish when seized by an Osprey is always carried lengthways in the bird's talons.—Seeböhm, *History of British Birds*, vol. i. p. 59.



THE COMMON CORMORANT.

BLACK CORMORANT, GREAT CORMORANT, WHITE-HEADED
CORMORANT, WHITE SPOT CORMORANT, GREAT
SCART OR SCARVE, COAL GOOSE.

Phalacrocorax carbo.

The Black, or Watch, or Staff Cormorant, The Scart.¹

*Even as the matron at her nightly task,
With pensive labour draws the flaxen thread,
The wasted taper and the crackling flame
Foretell the blast. But chief the plummy race,
The tenants of the sky, its changes speak.
Retiring from the downs, where all day long
They pick'd their scanty fare, a blackening train
Of clamorous Rooks thick-urge their weary flight,
And seek the closing shelter of the grove;
Assiduous, in his bower, the wailing Owl
Plies his sad song. The Cormorant on high
Wheels from the deep, and screams along the land.*

THOMSON, *Winter.*

ALTHOUGH the Common Cormorant does not breed on the Berwickshire coast,² it is found in numbers off the shore in the autumn, winter, and spring months. It appears to have certain favourite resorts, such as the Scart Rock,³ near Siccar Point, where it may be often seen resting and preening its feathers, a habit which is thus referred to by old Gawin Douglas :—

¹ It is also called by the Firth of Forth fishermen "Letter o' Marque," from the white patch on its thigh.—*Sporting Days*, by J. Colquhoun, p. 16.

² It, however, breeds at the Farne Islands, which are within a few miles of Berwickshire.—*Birds of Northumberland and Durham*, by J. Hancock, p. 131.

³ Mr. Hardy says that there is another Scart Rock near the Green Stane, famous amongst the fishermen for the great takes of herring near it in the olden time. The Green Stane is situate about a mile west from Dowlaw.

And in the calm or loune widdir is sene,
 Aboue the fludis hie, ane fare plane grene,
 Ane standing-place quhar Skartis with thare bekkis,
 For gane the son gladly thaym prunyeis and bekis.

Mr. Hardy has noticed that when the assemblages of Cormorants on Craig Taw, a black rock off Siccar Point, are larger than usual, say from twenty to thirty birds, they betoken wet, stormy weather.¹

The screaming of sea birds and their approach to the shore seem to have been looked upon from very ancient times as signs of a gathering storm, for we find Virgil in his *Georgics* alluding to these propensities in the following descriptive lines:—

Jam sibi tum curvis male temperat unda carinis;
 Quum medio celeres revolant ex equore mergi,
 Clamoremque ferunt ad littora.

In a recent and more prosaic age we have Bailie Jarvie saying nearly the same thing, but in other words: "Thae women at Aberfoil are like the scarts or sea-maws at the Cumries, there's aye foul weather follows their skirling."²

The Cormorant is very wary and difficult to stalk. Its flight is generally low over the surface of the water, with rapid beats of the wings, and is often continued for a considerable distance in a straight line. It feeds almost wholly on fish, and swims with surprising speed, while it pursues its finny prey under water with great agility and pertinacity, displaying such skill in their capture that it has from time immemorial been tamed in China and Japan and trained to catch fish. Mr. J. E. Harting, in his *Ornithology of Shakespeare*, says that James I. kept trained Cormorants for many years, and was accustomed to travel about the country with them, fishing wherever he went. He mentions that on

¹ "1874, October 16th.—Twenty-three Cormorants at Siccar. I have noticed that these assemblages betoken bad weather."—*Hist. Ber. Nat. Club*, vol. vii. p. 281.

² Sir Walter Scott, *Rob Roy*.

the 7th of May 1610, the king was at Thetford, in Norfolk, hunting, hawking, and fishing with Cormorants; also that James had a regular establishment for his Cormorants on the river at Westminster, and created a new office, "Master of the Royal Cormorants."¹

The voracity of this bird is proverbial. A specimen obtained near Paxton in January 1877 had in its stomach a bull trout (*Salmo eriox*) seventeen inches in length, along with the remains of other fish.² It occasionally comes up the Tweed from the sea in the winter and spring months, an example in immature plumage having been shot while sitting on the top of a tall tree by the side of the river at Paxton in the winter of 1871. The Rev. Thomas Mills, who wrote the report on the parish of Ladykirk in the *Old Statistical Account of Scotland*, 1793, mentions that "Goosanders, Wigeons, and Cormorants resort to the Tweed in severe winters, and sometimes Grebes and Speckled Divers."³ It has apparently given its name to Scart Heugh on the Tweed, near the Old Camp at Milne Graden.

There is no difference in the colour of the plumage of the adult male and female. In their nuptial dress they have a large white patch on each thigh. The tail consists of fourteen feathers.

¹ *The Ornithology of Shakespeare*, by J. E. Harting, 1871, pp. 261, 262.

² *Hist. Ber. Nat. Club*, vol. viii. p. 184.

³ *The Statistical Account of Scotland*, by Sir John Sinclair, Bart., 1793, vol. viii. p. 74.



THE SHAG OR GREEN CORMORANT.

CRESTED CORMORANT, SCART, SCARF, TUFTED SKART.

Phalacrocorax graculus.

The Scart.

*Others there are that make their home
Where the white billows roar and foam
Around the overhanging rock ;
Fearless they skim the angry wave,
Or, sheltered in their sea-beat cave,
The tempest's fury mock.*

HEMANS, *Birds.*

THE Green Cormorant is found on the coast of Berwickshire at all seasons of the year, and breeds at the Brander Cove, a lofty shelving ridge of rocks which runs out into the sea about a mile to the east of Fast Castle. Here my friend Mr. W. Evans saw a colony of ten Green Cormorants, and put one off a nest which contained three eggs on the 15th of May 1887. I visited the spot in a boat on the 30th of June following, when, in addition to an old bird sitting on a nest in a crevice of the rock about thirty feet above the water, I noticed another with two young on an adjoining ledge. They were not shy, but sat quietly and allowed me to examine them with my binocular from the boat, which was close to the bottom of the rock. The Brander Cove has been long known as a favourite nesting place of this species, Mr. Hardy having noted it as such in 1855, along with Caldron Cove, Harelaw Cove, and Byreloch Heugh. He adds that about the same time Mr. Wilson of Coldingham informed him that he had seen the nest of the Shag on the shelves at the sides of Caldron Cove as well as

in the dark recesses at the top. It was breeding at the Brander Cove on the 16th of July 1880.¹ The nest is generally a somewhat bulky structure, principally composed of sea-weeds and grass, a favourite site for it being a ledge at the side of a cave. The eggs, which are usually three or four in number, are pale blue, encrusted with chalky white.

Selby, in his account of birds observed at St. Abb's Head on the 18th of July 1832, says: "As we returned seaward in the boat several Green Cormorants were seen perched upon the pinnacles of the smaller isolated rocks, surveying with keen and watchful eyes our progress, and always too much upon the alert to permit us to approach within gunshot."² Mr. Archibald Hepburn, in his Notes on birds found at St. Abb's Head on the 20th of June 1850, mentions that "a few pairs of the Green Cormorant haunt the coast."³

In its habits the Shag resembles the Common Cormorant, and is more or less gregarious. About the neighbourhood of St. Abb's Head it may be often seen perched on some rocky point or shelf, resting and preening its feathers, or winging its way rapidly out to sea, keeping low over the surface of the water. It is fond of frequenting caves, to which it retreats during the wild storms of winter. The food consists almost entirely of fish. The Shag is considerably less than the Cormorant, while the plumage of the male and female is alike in colour. It has twelve feathers in the tail, whereas the Common Cormorant has fourteen.

¹ Mr. Hardy's *M.S. Notes*.

² *Hist. Ber. Nat. Club*, vol. i. p. 19,

³ *Ibid.* vol. iii. p. 74.



THE GANNET, OR SOLAN GOOSE.

GAN, HERRING GANT, BASS GOOSE, CHANNEL GOOSE,
SPECTACLED GOOSE.

Sula bassana.

The Solan Goose.

*Wild around their rifted brows, with frequent cry,
As of lament, the Gulls and Gannets fly.*

SIR WALTER SCOTT.

ON account of the vicinity of the Bass, the Gannet is seen in considerable numbers on the coast of Berwickshire from April to September, and is generally observed winging its way to or from that well-known breeding station, or fishing off the shore. The earliest date in spring at which its appearance on the coast has been recorded by Mr. Hardy is the 30th of March 1881. It is occasionally found in the interior of the county after tempestuous weather. About the middle of January 1877 a bird of this species was captured alive and in good condition at Duns Castle Lake,¹ and Mr. Charles Watson, Duns, informed me that another was caught near Chapel in October 1882. Mr. W. Leckie states that three examples were observed in Spottiswoode bogs some years ago, having no doubt been driven there by severe weather at sea, and that one of them, which was wounded by Mr. W. Buckholm, shepherd to Lady John Scott-Spottiswoode of Spottiswoode, was put into a pond there, where it died. It was afterwards preserved by Mr. W. Renton.

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 196.

The Gannet leaves the Bass in autumn, and does not return until spring.¹

Its flight is very powerful and long sustained, and it sometimes travels immense distances to feed. It is interesting to watch a party of Gannets fishing, for the birds descend headlong from various heights in the air, and plunge into the sea with such force as to leave the surface covered with foam at the spots where they disappear under the water. In a few moments they emerge, and, after sitting for some seconds on the water, mount on the wing again and renew their search. Their skill in capturing fish had been noticed by Holland, for he thus alludes to it in his *Houlat* :—

And als in the advent,
The Soland stewart was sent ;
For he could fra the firmament
Fang² the fische deid.

The salmon-fishers on the coast say that when Gannets are observed frequently plunging into the sea for fish near the shore, a good take may be expected in the nets.

Although at the present day the Solan Goose is by no means reckoned a dainty dish for the table, yet it appears to have been considered so by Berwickshire lairds long ago, for in *The Men of the Merse* we find Lord Crossrig inviting George Home of Kimmerghame "to a Solan Goose" in March 1699.³ It was esteemed as an article of food in the Middle Ages.⁴

The grease of this bird appears to have been very much valued in the olden times, for in the General Register House,

¹ It returns to the Bass early in February, and lingers there till October, although most of the birds leave the rock when the young are taken in August.—*Hist. Ber. Nat. Club*, vol. vii. p. 17.

² Capture.—*Jamieson, Scot. Dict.*

³ *The Men of the Merse*, by Archibald Campbell-Swinton Esq. of Kimmerghame, 1858, p. 61.

⁴ *Accounts of the Lord High Treasurer of Scotland*, vol. i., 1473-98, Preface, ccv.

Edinburgh, there is a "commission by Pope Alexander vi. to the Prior and Archdeacon of St. Andrews, to investigate a claim by the prioress of North Berwick against Robert Lauder of the Bass, and rector of the parish of the Bass, for certain barrels of grease of geese, dated 10th May, 1493."¹ The following interesting "Excerpts from the Books of John, Duke of Lauderdale, respecting the price of Solan Geese, from 1674 to 1678," were communicated to the *History of the Berwickshire Naturalists' Club*² by Mr. Robert Romanes of Harryburn, Lauder:—

"THE BASS.—John, Earl, afterwards Duke, of Lauderdale, was in 1671, March 3rd, Captain of the Bass.

„ August 21st, Keeper of the Bass.

„ September 7th, Governor of the Bass.

1674. "By pryce of Sollen-geese of the Bass, 1674. The accomptant charges himself with the pryce of 1118 Sollen-Geese, sold for 1 lb. 8s. 4d. each score, p. contract accordingly, dated 10th June, 1674, £79 3s. 10d. sterling."

"To the climber of the Bass in full of his fee, waige, and allowance for the year and season 1674, and for some other small necessaries and charges that year, p. discharge upon the back of the contract accordingly, £11 12s. 2d. sterling."

1675. "By pryce of 1060 Sollen-Geese, as the product of the Bass the season 1675, sold for 1 lb. 9s. 2d. sterling each score, p. contract accordingly, dated 11th May, 1675, £77 5s. 10d."

"To Charles Maitland in the Bass for his expense when he went to London with Sollen-Geese, p. his Gra. Order and his Receipt, dated 19th October, 1675, £20 0s. 0d."

1676. "By pryce of 1150 Sollen-Geese as the product of the Bass for 1676, sold as above, p. contract 24 May, 1676, £83 17s. 1d."

1677. "By pryce of 985 Sollen-Geese sold at 1 lb. 9s. 2d. each score, for the season 1677, p. contract accordingly, £71 16s. 5½d."

1678. "For the Sollen-Geese in the Bass for year and season 1678, Charles Maitland is settled with, and here is the agreement made with him thereanent:—

'At Edinburgh, the 10th day of May, 1678, it is agreed upon and consented to betwixt Sr. William Sharp of Stonyhill on the one part, and Charles Maitland, son to Robert Maitland, keeper of the Bass, on the other part, That is to say the said Sr. William Sharp settis and lettis to the said Charles Maitland the whole Sollen-Geese of the Bass for the season 1678, for the sum of three score fifteen pounds sterl., to be payed to the said Sr. William

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 88.

² *Ibid.* vol. vii. pp. 90-92.

Sharp, his heires, and exrs. free of all charges whatsoever incumbent to the delivery of the said Sollen-Geese, and the said Charles Maitland binds him and his heires and exrs. to content and pay to the said Sr. William Sharp and his foresaids, the said sum of seventy-fye pound sterling, the one half at the date of their presents and the other half upon the twenty nyynth day of September next to come in this instant year 1678, with the sum of ane hundred pounds Scots of failzie, to be payed by the partie failziear to the party willing to observe the premises. In witness yrof both parties have subscribed their presents with their hands tyme and place aforesaid before these witnesses, John Robertson, writer in Edr., and David Callender, writer hereof.

'Charles Maitland is also to give to me in this season two dozen good Sollen-Geese free.'



THE COMMON HERON.

GREY HERON, CRESTED HERON, HERONSHAW, HURON, FRANK,
CRANE, CRAIGIE HERON, LANG-NECKIT HAARAN.

Ardea cinerea.

The Hurant, Huron, or Heronsheugh.

*Lo! at his siege, the Hern
Upon the bank of some small purling brook
Observant stands to take his scaly prize,
Himself another's game; for, mark, behind
The wily falc'ner creeps; his grazing horse
Conceals the treach'rous foe, and on his fist
Th' unhooded Falcon sits; with eager eye
She meditates her prey, and in her wild
Conceit already plumes the dying bird.*

SOMERVILLE.

IN olden times this interesting and picturesque bird, which is frequently seen in every district of the county, was so much prized for the "marvellous and delectable" sport which it yielded to the falconer, that an Act was passed by the Scottish Parliament in 1493 for preserving Herons.¹ Mr. Thomas Dickson, in his *Accounts of the Lord High*

¹ James IV. Anno 1493.—"Anent the distroying of Heron sewis."—*Acts of the Parliaments of Scotland*, vol. ii. p. 235. This Act was renewed in 1567 against all such as shoot with "Culveringis, Crosbow, or Handbow ony time at Dae, Rae, Hart, Hynd, Hair, Cunning, Dow, Herron, or foule of river," the penalties being that they "sall foirfault and tyne their haill moveabil gudis," and "gif the committer of the cryme be ane vagabound not havand gudis, that the judge, quhom befoir he is convict, keip and hauld him in prison for the space of fourtie dayis. And that for the first fault. And the nixt fault, to cut of his richt hand."—*The Laws and Acts of Parliament of Scotland*, by Sir Thomas Murray of Glendook, 1681, pp. 186, 187.

Treasurer of Scotland, says that the Heron and the Bittern were the highest quarry at which Falcons were flown, and when struck by the Hawk, the former was "either released to furnish fresh sport, or kept to be used in perfecting the training of other Falcons. It was for this purpose—'to mak tranis to the halkis'—that 'quyk' or live Herons were frequently brought to the king,"¹ as shown by the following entries in the *Accounts*:—

1496. "Item, the last day of Julij, giffin to the man that brocht twa quyk herounis to the King to mak tranys to halkis, . . . ix s."²
 1497. "Item, that samyn day (the last day of May) gevin be the Kingis command to ane man of the Lard of Dawikkis, that brocht quyk herounis to the King, . . . xvij s."³

The kings and nobility of Scotland, like their compeers in England,⁴ appear to have followed the sport of Heron hawking with great ardour, and as an instance of this it may be mentioned that Archibald Douglas, 7th Earl of Angus, on seeing a Heron rise from a marsh at the beginning of the battle of Ancrum Moor,⁵ is said to have exclaimed, "Oh! that I had my white Goshawk here, that we might all yoke at once."⁶ Ladies often went out with the falconers to the Heron hawking and took an active part in the sport.⁷ It must indeed have

¹ *Accounts of the Lord High Treasurer of Scotland, 1473-1498*, Preface, p. cclii.

² *Ibid.* p. 287.

³ *Ibid.* p. 338.

⁴ Not only were Herons protected by Parliament in England, but penalties were incurred by taking their eggs. The fine was 8d. for every egg. See 3 and 4 Ed. vi. c. 7, and 25 Henry viii. c. 2.—*The Ornithology of Shakespeare*: Harting, pp. 222, 223.

⁵ This moor, which lies 1½ miles north-west of the village of Ancrum, was the scene of one of the last great conflicts in the international war between Scotland and England. In 1554 an English army 5000 strong, under Sir Ralph Evers and Sir Bryan Latoun, overran and wasted the Scottish Border northward to Melrose. Returning with their booty, they were overtaken at Ancrum Moor and utterly routed by a Scottish force under the Earl of Angus and Scott of Buccleuch.—*Ordnance Gazetteer of Scotland*, vol. i. p. 49.

⁶ *Dryburgh Abbey: its Monks and its Lords*, second edition, 1860, p. 24.

⁷ *Strutt's Sports and Pastimes*.

been a gallant sight when "the champion of the dames," accompanied by many of the nobility and ladies of his court and the falconers on horseback, went a-hawking; and we know from the *Lord High Treasurer's Accounts* that he sometimes visited Berwickshire for this purpose, one occasion being "on Monnunda, the iiij da Januar (1489), quhen he raide to Lauder to the halkin."¹

The Heron was formerly esteemed as an article of food² and held a high place at the tables of the great, where it appeared at the marriage and other principal feasts.³ An entry in the *Northumberland Household Book* in the time of Henry VIII. reads that "it is thought in likewyse that hearonsewys be bought for my lorde's owne mees, so they be at xijd. a pece." Mr. James Smail, in his interesting paper on "Hérons and Border Heronries,"⁴ says that even when plump and dressed and roasted to perfection, the flavour of the Heron is so fishy as to be quite unpalatable, "but the young birds taken from the nest and properly stewed are really good."

Its beautiful plumes appear to have been used to ornament the caps of the highest in the land, and Sir Walter Scott, referring to this in his description of the meeting of Lord Marmion and Sir David Lindesay of the

¹ *Accounts of the Lord High Treasurer of Scotland*, 1473-1498, p. 127.

² *Ibid.* Preface, p. ccv.

³ The following directions for roasting the Heron appear in *Le Vrai Cuisinier François*, Bruxelles, 1699, a copy of which is in the possession of Miss Dickenson of Norham:—"Plumez-le, et le vuidez; ensuite vous chercherez six cimeres qui sont sur son corps, et un autre faisant le septième" qui est au-dedans; troussiez les jambes le long des cuisses, faites-les blanchir sur le feu, et le piqués, enveloppez le col avec du papier beurré, puis le faites rôtir, et étant cuit, servez." The Heron is mentioned in the book as being in season "depuis la S. Remy (1st October) jusques en Carême" (Lent).

⁴ *Hist. Ber. Nat. Club*, vol. x. p. 331.

* Rolland, in his *Faune Populaire de la France*, 1879, says, "Le peuple prétend que le Héron a sept vésicules de fiel."

Mount in "Saltoun's Wood," says of the "Lord Lion King at Arms," that

His cap of maintenance was graced
With the proud heron-plume.

Folkard mentions that "among our ancient customs, was one of swearing an oath upon the dead body of a Heron, and whereby many a gallant knight has, in years long passed, plighted his troth to his 'ladye faire,' as the most solemn and honourable manner of assuring her of his sincerity."¹

It is said in some parts of the county that when Herons are seen flying up the course of the Tweed in numbers it betokens stormy weather. This may be on account of the bird's habit of leaving discoloured waters and proceeding to smaller and clearer streams during floods. The association of the lofty flight of the Heron with approaching stormy weather is thus referred to by Virgil in his *Georgics* :—

notasque paludes
Deserit atque altam supra volat ardea nubem.

And Thomson, in his description of an approaching storm in winter, says :—

Loud shrieks the soaring Hern, and with wild wing
The circling sea-fowl cleave the flaky clouds.

The Heron generally builds on lofty trees in woods, and commonly in colonies after the manner of the Rook; the nest, which is formed of sticks and lined with twigs and dry grass, being of a large size. It is an early breeder, and the eggs, which are three or four in number and of a uniform bluish-green colour, are usually laid towards the end of March.²

¹ *The Wild Fowler*, Folkard, second edition, 1864, p. 194.

² According to Mr. George Bolam's *M.S. Notes* he found eggs in the nests of the Herons at the Pistol Plantation Heronry on the 1st of April 1881. Dr. Stuart records that Mr. A. H. Evans saw young birds in the nests at the above Heronry on the 21st of April 1879.—*Hist. Ber. Nat. Club*, vol. ix. p. 135.

The following are lists of the Heronries which are found in Berwickshire at present (1887), as well as of those which existed in the county in former times, but are now abandoned; and I take this opportunity of thanking my correspondents for the information regarding these which they have so kindly supplied:—

HERONRIES EXISTING IN BERWICKSHIRE IN 1887.

PARISH.	SITUATION OF HERONRY AND APPROXIMATE NUMBER OF NESTS.	NAME AND ADDRESS OF REPORTER.
Buncle.	Buncle Wood.—2 or 3 nests in old Scotch fir-trees.	John Blackadder, East Blanterne, Chirnside.
Duns.	Castle Wood, on Duns Castle Estate.—About 40 nests in Scotch fir-trees. A Heronry has existed in this wood from time immemorial, but its exact locality has been changed to different parts of the wood at least three times, owing to the destruction of the trees by high winds.	John Ferguson, Duns.
Lauder.	Ollister Dub; West Mains Brae; Boiling Park; and old trees between Luggy and Wester Park—all in and about the Thirlestane Castle Policies.—From 2 to 5 nests in each.	Robert Romanes of Harryburn, Lauder.
Whitsome.	Pistol Plantation; chiefly on tall Scotch fir-trees south from forester's house. — About 50 nests scattered through the plantation. (Mr. Hardy records the discovery of this Heronry by Dr. Stuart in 1875.— <i>History of the Berwickshire Naturalists' Club</i> , vol. vii. p. 516.)	Charles Stuart, M.D., Chirn- side.
Mertoun.	Mertoun House Policy; high beech-trees.—About 35 nests.	John Thomson, Maxton, St. Boswells.
Coldstream.	Hirsel.	
Eccles.	Lithtillum Loch.	

**HERONRIES WHICH FORMERLY EXISTED IN BERWICKSHIRE,
BUT ARE NOW ABANDONED.**

PARISH.	SITUATION OF HERONY AND APPROXIMATE NUMBER OF NESTS.	NAME AND ADDRESS OF REPORTER.
Longformacus.	At the bottom of the March Wood, between Felicleugh and Ellemford, near the junction of the Dye and Whitadder.	Rev. George Cook, The Manse, Longformacus, Duns.
Polwarth.	Twenty-three years ago there were from 10 to 12 nests on the highest chestnut-trees at Marchmont, but during the making of the Berwickshire railway the engines, which were constantly running along the line at night, apparently frightened the Herons away, for they left their nests at that time and have not returned. (Mr. Hardy, in his <i>M.S. Notes</i> , says there used to be a Herony at Marchmont, where the birds made a great noise. They were protected by Sir W. Purves Campbell.)	Peter Loney, Marchmont, Duns.
Westruther.	A small Herony, consisting of from 8 to 12 nests, formerly existed in the Circle Plantation, which stood about a hundred yards to the east of Gateside School. About twenty years ago a great gale blew down the high spruce firs upon which the nests were placed, and this destroyed the Herony. For a few years afterwards a number of Herons built on the trees at Crumles Bridge, near Bruntaburn, but boys interfering with their nests caused them to abandon that situation. The Herons always chose trees having round tops, and made very large circular nests.	Walter Lockie, Gateside School, Spottiswoode, Westruther, Lauder.
Foulden.	A few Herons took up their abode at Foulden about 1830, on trees a short distance to the south of the Mansion House, but did not continue long there.	John Wilson of Welnage, Duns, May 4th, 1886.

THE COMMON HERON.

45

PARISH.	SITUATION OF HERONRY AND APPROXIMATE NUMBER OF NESTS.	NAME AND ADDRESS OF REPORTER.
Edrom.	In 1825, when I was a boy at school in Duns, there was a Heronry of about 12 nests at Nesbit, all clustered about one spot, and several nests on one tree—great nests they were, double the size of Rooks' nests. We used to see the Herons' legs sticking out over the edges of the nests when the old birds were hatching. The trees on which the Herons built stood to the south and west of Nesbit House.	John Wilson of Wehnage, Duns, July 25th, 1884.
Cockburnspath.	In Dunglass Dean, besides the tall trees near the Belvidere on the East-Lothian side, where the Herons built when I was a boy, it is reported they afterwards built near the Saltheugh, on the Berwickshire side. They have deserted both places long since. Three years ago, on a flat spot among dangerously steep rocks near Siccac Point, a Heron's nest was found. The young ones had been deserted after being nearly fully grown. The nest was made of large sticks, and had many fish-bones about it.	James Hardy, Oldcambus, Cockburnspath. — <i>MS. Notes</i> , dated August 8th, 1877.
Hutton.	There used to be 2 or 3 Herons' nests on some old trees having their tops covered with ivy near Clarabad Damhead about twenty-five years since. The trees were blown down some time ago. There is an old Heronry Wood at Paxton, which formerly consisted of lofty spruce and silver fir-trees, growing in a dean near the Tweed, immediately to the west of Paxton House. The most of the tall silver firs have been blown down, and only a few giants now remain, one of which is about 110 feet in height. It is said that Herons at one time nested on the tall silver firs—hence the name of the wood. About 1869 several young Herons were confined in a wire-netted enclosure below the trees for about a year and a half for the purpose of inducing them to stay and build their nests on the remaining high trees, but on getting their liberty they flew away and did not return.	James Hardy, Oldcambus, Cockburnspath, in <i>Hist. Ber. Nat. Club</i> (1875), vol. iii. p. 516. W. Compton-Lundie of Spital, Spital House, Borwick-on-Tweed, May 3rd, 1887. The Author.

The Heron frequents the Tweed, Whitadder, Blackadder, Leader, Eye, Dye, Eden, and other streams in the county, where it may be sometimes observed standing motionless in the water watching for its prey. As, however, it is very wary, it is more often noticed rising from the river with its slow, steady flight, and its long legs stretched out beyond its tail. It likewise visits the rocky sea-coasts of the county, including the neighbourhood of Oldcambus, at all seasons of the year, but chiefly from March to August, in search of food. "Here," writes Mr. Hardy, "the birds sleep when the tide does not suit for fishing, one by one, or by pairs, in the chinks and hollows of the great rocks at Rough-head and Swallow Craig. When they fly, their large grey wings are very conspicuous on the black winter shores. If the tide is going out, they each select their own rock, and are elegant and watchful, their shadows being reflected in the receding waters. They remain still as long as a person walks on the top of the sea banks, but fly off if a stand be made."¹ The scream of a Heron, which it often utters when rising from a river side or marsh, never fails to alarm all the wild-fowl within hearing: "the Herrons gaif an vyild skreech as the Kijl had bene in fyir,² quhilk gart the quhaipis³ for fleyitnes⁴ fle far fra hame."⁵

When Herons are passing singly or in small numbers high overhead in the air on a prolonged journey, their cry often attracts attention, and they may then be observed in the full grandeur of their flight. Rooks sometimes mob them on these occasions, and fly after them with much persistence.

¹ Mr. Hardy's *MS. Notes*, dated the 13th of February 1872.

² "To cry as if the Kill was on fire"—a common phrase to express making a great noise.—Jamieson, *Scot. Dict.*

³ Curlews.

⁴ Fear.

⁵ *The Complaynt of Scotland*, 1560.

The food of this voracious bird¹ consists of fish (of which it consumes an immense amount), small animals, such as rats and mice, young water birds, frogs, newts, molluscs, crustaceans, worms, and insects. Mr. Brotherston, Kelso, mentions having examined one which had upwards of twenty newts in its stomach.² Mr. Ferguson, Duns, informed me on the 25th of May 1887 that during the spring of that year the Herons nesting in the Heronry at Duns Castle carried off the greater number of the young Coots in the lake there to feed their young. The game-keeper repeatedly observed them swooping down close to the water and picking up the young with their bills. The first brood of Coots escaped, as they had grown up before the young Herons were hatched.

It is well known that the Heron, when wounded, is a dangerous bird to approach, on account of its habit of striking at the eye with its long-pointed bill. An instance of this propensity is thus related in the *Kelso Chronicle* for August 1852: "One day last week, as two little boys from the village of Dodmill, near Spottiswoode, were strolling over Blythe Moor, one of them caught a Heron, with which he eagerly ran to his companion to show him his prize. He had no sooner, however, placed the bird on the ground than it drove its bill into one of the other boy's eyes, which it put quite out. The surgeon who examined the wound said it was a matter of surprise that the bill of the bird did not pierce the poor little fellow's brain."


Two pools in the Dye are named after this bird—the Heron's Hole, a short distance above Longformacus at a sharp turn of the river; and the Heron Scaur, on the north side of the same stream, about a mile above Byrecleugh.

¹ Although the Heron is very ravenous, it is light for its size. An old male in full plumage which I shot on the Langton Burn, near Wedderburn Castle, on the 29th of December 1886, weighed only 5½ lbs.

² *Hist. Ber. Nat. Club*, vol. vii. p. 502.

Mr. John Thomson has favoured me with the following interesting account of the Heronry at Mertoun :—

“Considering its size and habits, the Heron may be termed plentiful in the south-western district of Berwickshire. At all hours of the day, and every day, it may be observed winging its heavy flight to or from its feeding places. Yet on some days the naturalist may walk mile after mile on Tweedside, even close past a Heronry, without seeing a single bird. This is especially the case when the Tweed is in high flood. On these occasions it seems to prefer the tributary streams, ditches, and pools, to the swift-running river and its discoloured waters. In the summer time it is nearly always on the look out for food. On several occasions, when fishing for trout at night, I have disturbed a Heron from his favourite stream, while it was so dark that, had it not been for his scream, I would have been unaware of his presence. The screaming of the bird on these occasions is rather odd, as it seldom screeches when disturbed in the day time. More than once I have seen Herons fishing by moonlight, and noticed that they sounded their alarm note. It is a remarkably sage-looking and silent bird, though when near the nest it is often heard giving warning of its approach to its mate. One of the largest Heronries on the Borders is at Mertoun. The nests are built on the high beeches on an eminence in the western part of the policies. The Heronry is situated on a peninsula, and on three sides is only about three hundred yards from the Tweed. The beeches are noble trees, large in the trunk and particularly fine in their foliage. The nests are placed in secure positions on the slender boughs, which in many cases seem to be too small to sustain them. Lord Polwarth is particularly careful that the Heronry shall not be molested in any way, and as the nests are perfectly inaccessible, the birds are always able to rear their young in peace. Yet the



Merton, A. Scott. 1894.

number of nests never increases in any appreciable degree, generally remaining at about thirty-five. It is not now known how long the Herons have occupied this wood conjointly with an extensive colony of Rooks. The beeches seem to be about two hundred years old, and it is probable that the Heronry has existed for at least a century. One year the Herons and Rooks had a tough battle. The Rooks apparently wished to take possession of the nests of the former, and fought hard to attain their object. In the end the Herons were able to maintain the *status quo ante*, and the surplus Rooks betook themselves to other trees in the park. Only in one season during the memory of persons living have the Herons failed to nest at Mertoun. This was about 1840. In the spring foresters were busily engaged thinning, and the birds betook themselves to the old wood at Blue Houses, near Dryburgh, where they nested and reared their young. They showed their decided partiality for Mertoun by returning next year, where they have ever since remained. In early summer from twenty to thirty of these birds may be seen sunning themselves in the grass enclosure near their nests, forming a spectacle as beautiful as it is perhaps unique in this part of the country.

From careful and continued observation I have come to the conclusion that in certain cases particular Herons take up and hold without challenge a favourite fishing stream. The right of the individual to his "private water" seems to be fully recognised by other birds of the same species, which I have never seen fishing upon it even in the regular owner's absence, though I have noticed them on the opposite margin, a hundred yards or so lower down. This privilege seems to be conceded to old male birds. In one case, at least, I have been able distinctly to identify the bird which exercised his liberty without challenge. My friend the Rev. Alexander Stewart, LL.D., F.S.A., Ballachulish, in one of his

"Nether-Lochaber" papers, supports my experience (*Inverness Courier*, February 5th, 1886). Mr. Stewart says: "We have repeatedly seen instances of individual Herons enjoying such a monopoly as Mr. Thomson describes, and have little to say about it, except that the Heron, in such a case, is always a male, and usually a fine specimen, large and full-crested, of his long-legged race. We know a Heron in the full and free enjoyment of such a monopoly in our own parish at the present moment." Since the above was written I have obtained abundant proof of the correctness of the foregoing observations. About twenty years ago an old Heron was every day to be seen fishing in the stream on the Tweed opposite Mertoun House. This patriarch, according to the old servants of the Mertoun family, had held that stream as his peculiar possession for about forty years. There could be no mistake regarding his identity, as he was known wherever he was seen. This favourite bird, which in his day was one of the recognised "lions" of Mertoun, is thus referred to by the Hon. and Rev. Robert Liddell in his *Lay of the Last Angler*:¹—


- "I'll venture to pourtray one feature more
 In sketching beauteous Mertoun's situation.
 Notice that lonely fisher near the shore
 (Below 'Stile-foot' he takes his usual station).
 "Don't be afraid that he will interfere
 With your day's sport, because he's not a caster,
 Though in his own peculiar way, 'tis clear
 That he's a finished and successful master.
 "See! how he stalks along the pebbly strand,
 With keen eye watching each sub-aqueous motion,
 Wading knee-deep for hours he will stand,
 Yet as to taking cold, he scorns the notion.
 "He needs no rod, nor line, nor fishing-book,
 Although he makes his living on the water;
 He catches all his fish without a hook,
 But when 'he's gotten haud' he gives no quarter.

¹ Kelso: J. & J. H. Rutherford, 1884, pp. 74-76.

"It is an ancient Heron—I believe,
Forty years old at least—a dear relation,
Who's much at Mertoun, says he can perceive
Of its identity much indication.

"Its haunts and habits always are the same—
What lots of fish ere this he has digested.
And the old poacher's wonderfully tame,
Because he never is at all molested.

"Still, he's a wary bird, and thinks aright,
'The better part of valour is discretion ;'
So if you come too near, he takes to flight,
With pompous gravity beyond expression."



THE NIGHT HERON.

THE GREY NIGHT HERON, THE NIGHT RAVEN.

Nycticorax griseus.

*The Heron came from the Witch-pule tree,
The Houlet frae Deadwood-howe ;
The auld grey Corbie hoverit aboone,
While tears downe his cheeks did flowe.*

THE GLOAMYNE BUCHTE.

A SPECIMEN of this very rare bird was shot while sitting on the top of a tall oak-tree at the Hirsel, by the Earl of Home, on the 25th of May 1822. It was a male, and was presented to the Museum of the University of Edinburgh by his Lordship. A female was wounded by Lord Home on the same day, but it fell amongst a bed of reeds and could not be found, though a very diligent search was made for it.¹ The Night Heron appears to have occurred only seven times in Scotland.² It is not so large as the common species, and breeds in several parts of Europe.

¹ *Newcastle Magazine* for July 1822, and Dr. Johnston's *M.S. Notes*.

² Yarrell's *British Birds*, fourth edition, vol. iv. (1884-85), p. 196.



THE COMMON BITTERN.

BULL O' THE BOG, BUTTER-BUMP, BITTER-BINN, BOG-BUMPER, BOG-
BLUTTER, BOG-JUMPER, BOG-DRUM, MIRE-BUMPER, MIRE
DRUM, MOSS-BUMMER, BUMPY-COSS, BUMBLE

Botaurus stellaris.

The Bull o' the Bog, The Mire Drum.

*No more the screaming Bittern bellowing harsh,
To its dark bottom shakes the shuddering marsh.*

LEYDEN, *Scenes of Infancy.*

UNTIL the early years of the present century, when Billie Mire was drained, that extensive and almost impassable morass was a favourite haunt of innumerable wild-fowl, and above their various weird cries at night the loud boom or bellow of the Bittern could be heard in spring coming from the great reed beds which surrounded the deep black pools of the bog—the bird on this account being known by the country people in the neighbourhood as the Bull o' the Bog or the Mire Drum.¹

As Billie Mire was the principal resort of the Bittern in Berwickshire, as well as of several other birds which are now rarely or never seen in the county, amongst which may be mentioned the Hen Harrier, it may not be considered out of place to give here an account of that interesting and his-

¹ It is probable that the weird and unearthly cry of the Bittern at night gave rise to the superstition regarding the "Bogle of Billy Myre" and "Jock o' the Mire," which Dr. Henderson says "so long haunted its black peat-hags, grey saugh bushes, and ancient causeway." See *Popular Rhymes of Berwickshire*, p. 8.

torical bog,¹ which is said to have extended in ancient times from the Eye in the neighbourhood of Ayton on the east, to the Whitadder near Chirnside on the west, a distance of about five miles.

Along the northern boundary of the parish of Chirnside, and dividing it from Coldingham, lies a narrow valley, which widens towards the west, where it separates the former parish from Buncle. The bottom of this valley, for nearly its whole length of about four miles, is singularly flat, being, for the most part, about 200 feet above the level of the sea; but there is a slight declivity towards the west from a point about half a mile to the east of Causewaybank Farm House, and a gentle slope to the east from the same spot. The watershed which feeds the valley is very extensive, comprising the lands of Blackburn, Causewaybank, and Oldcastles on the south; Berrybank, Ferneycastle, Stone-shiel, Auchencrow Mains, Billie Mains, Lintlaw, Slighouses, Marygold, Mayfield, Warlawbank, Greenburn, Greenhead, and Fairlaw on the north. These lands vary in altitude from 300 feet—the height of the Piper's-knowe² at Causewaybank—to 800 feet near the source of the Fosterland Burn, to the west of Warlawbank. Flowing into the

¹ Billie Mire was the meeting place of English and Scotch Commissioners with regard to treaties between the two kingdoms on the 25th of August 1380 and the 27th of January 1384. It was passable by horses only at two places over causeways formed by plunging large stones into the bog. The course of one of these causeways is indicated by a place on the southern side of the morass called Causewaybank, and the remains of the other were still discernible in 1836, about eighteen feet in width, and eight or ten in depth, on the line of road between Chirnside and Auchencrow. On the expiration of a truce the causeways were uniformly demolished as far as would obstruct the passage from the south side of the Mire.—Carr's *History of Coldingham Priory*, pp. 81, 82.

² Dr. Henderson of Chirnside, writing in 1846, says, in his MS. Notes on Billie Mire: "Upon its banks are several inconsiderable elevations, consisting chiefly of sand and gravel. Among those on the south side, near the farm of Causewaybank, the Pyper Knowe is the most remarkable. A few years ago this knoll was completely covered with a luxuriant crop of broom, which might have vied in length and beauty with that of the far-famed Cowden Knowes. This place was a favourite resort of the fairies of old."

valley from the northern watershed are several small rivulets known as the Auchencrow Burn, Fosterland Burn, Draeden Burn, and Lintlaw Burn. Auchencrow Burn has its source near Shillum Dykes, and after draining part of the lands of Coldlands, Sunnyside, Fairlaw, Stoneshiel, Ferneycastle, and Greenhead, passes Auchencrow village and Auchencrow Mains, and thence enters Billie Mire Burn or Cast, which now occupies the bottom of the valley, about half a mile to the east of Billie Mains. Fosterland Burn—which is said to have derived its name from the foresters of the ancient Priory of Coldingham having property on its banks—rises in boggy ground on the heights to the west of Warlawbank, and, after being joined by Greenburn and other lesser runnels, passes close under the ruins of Billie Castle and adds its waters to Billie Mire Burn, about a quarter of a mile to the east of Billie Mains. Draeden Burn, a name which, says Mr. Carr, in his *History of Coldingham Priory*, “an etymologist can have little difficulty in tracing to the same root as the word ‘Druid,’” has its origin in a plantation situated a short distance to the east of Slighouses, and, being augmented by the waters of several small springs, proceeds eastwards, and, crossing the public road from Lintlaw to Billie Mains not far from the spot upon which formerly stood Little Billie, the birthplace of the late Dr. Henderson of Chirnside, passes near the Pech Stane, and falls into Billie Mire Burn about a quarter of a mile to the south-east of Billie Mains. A large circular cairn, which was removed about fifty years ago, stood near the Pech Stane above mentioned, on the farm of Little Billie. These relics of ancient times are referred to in the following fragment :—

Grialy Droedan sat alane
By the cairn and Pech Stane;
Billy, wi' a seg sae stout,
Cries “I'll turn grialy Droedan out !”

Droeden leuch, and stalk'd awa,
And vanish'd in a babbanqua'.¹

Lintlaw Burn is said to have had its origin in Preston Cleuch, a rocky ravine to the west of Buncle Church, which is supposed to be the ancient "crahochtre" mentioned in old charters as part of the boundary of Coldinghamshire, where there is a fine perennial spring.² Its chief sources now appear to be in the neighbourhood of Buncle Wood, and, being increased by many small sykes and rills, it runs eastwards a little below Slighouses,³ where it receives the Marygold Burn, and, continuing its course, enters Billie Mire Burn about half a mile to the north of East Blanerne. Not far from its mouth, on a little haugh, formerly stood Billie Mill, which was taken down in December 1845, the site being still marked by one or two old trees. The waters from all these rivulets being united in Billie Mire Burn or Cast flow southwards and join the Whitadder a short distance below East Blanerne.

Until the beginning of this century the whole extent of the valley from Causewaybank on the east,⁴ to about half a mile beyond Billie Mains on the west, formed one long, continuous, and very deep quagmire, which received the

¹ Billie Mire. See *Popular Rhymes of Berwickshire*, by Dr. Henderson of Chirnside, pp. 8, 9; also Carr's *History of Coldingham Priory*, pp. 11, 12.

² The water from this spring now supplies Bonkyl Lodge, being conveyed thither by gravitation in a pipe.

³ Formerly the property of Dr. James Hutton, one of the founders of geology, who settled here in 1754, and devoted himself to agricultural pursuits.

⁴ Judging from the account given of Billie Mire in Carr's *History of Coldingham Priory*, where it is said to have been six miles in length, and from the extent of the deposit of alluvium shown on its site in Sheet No. 34 of the Geological Survey of Scotland, this bog would appear in ancient times to have reached to within about half a mile of the point where the railway crosses the valley from East Reston to Prendergast, or about a mile to the east of Causewaybank. Probably the part between Causewaybank and the eastern end of the alluvial deposit, shown on the Geological Survey Sheet, may have been drained about the middle of last century, when agricultural improvements of all kinds were begun in Berwickshire. This part would be easily drained on account of the slope of the ground enabling the water to run off freely by the Horn Burn.

waters of the various rivulets, and the drainage of the watershed above mentioned. The superfluous waters of this great bog, which varied from one hundred to two hundred yards in width, were drained off towards the west by a stream known as Billie Burn, which joins the Whitadder near Chirnside Mill, and to the east by the Horn Burn, which flows into the Eye, in the vicinity of Ayton. During summer a great part of the surface of the Mire was thickly covered with immense beds of tall and luxuriant reeds,¹ bulrushes, flags, and other aquatic plants of many kinds, which grew on the shallows, whilst here and there the deep black pools were fringed with low grey willow trees—

Where countless reeds once clothed yon narrow vale,
 Their feathery heads wild streaming in the gale,
 There lay the Myre, with moss-pools dark and deep,
 Round whose black margin foul toads loved to creep :
 The wild grey willows waving there you'd see,
 Their silvery blossoms opening to the bee ;
 There red marah-cinquefoil and the buck-bean grew,
 And hoary cannach waving in the view ;
 The yellow marigold long flourished there,
 And purple orchis—Flora's offerings fair.

Scenes of Boyhood, DR. HENDERSON.²

¹ Mr. John Wilson of Welnagie told me on the 7th of August 1884, that he remembered that, when he was a boy, Billie Mire was comparatively undrained—he was born in 1810—and that it used to be overgrown with tall reeds, which looked like a field of wheat.

² In some MS. Notes on Billie Mire by the late Dr. Henderson of Chirnside, for the use of which I am indebted to his son, Mr. R. Henderson, chemist, Chirnside, I find the Doctor, writing about 1835, says: "A few years ago the Mire was thickly covered with the *Arundo phragmitis* (Common Bog-reed), *Angelica sylvestris* (Wild Angelica), several species of *Carex* (Sedge), *Calltha palustris* (Marsh marigold), *Hydrocotyle vulgaris* (Common White-rot), *Comarum palustre* (Marsh Cinquefoil), *Enanthe crocata* (Hemlock Water-dropwort), *Menyanthes trifoliata* (Bog-Bean), *Sium nodiflorum* (Procumbent Water Parsnip), *Viola palustris* (Marsh Violet), *Veronica beccabunga* (Brooklime), *Nasturtium officinale* (Water Cress), *Cardamine pratensis* (Cuckoo-flower), several species of *Eriophorum*, *Scirpus*, and *Salix*, *Iris pseudacorus* (Yellow Iris), *Typha latifolia* (Black-headed Reed), several species of *Juncus*, *Potamogeton*, *Senecio aquaticus* (Marsh Ragwort), *Myosotis palustris* (Forget-me-not), and many other marsh plants. He adds that before the Mire was drained there was also found in it in considerable abundance the medical leech (*Hirudo officinalis*).

Vast numbers of Wild Ducks and water-fowl of many kinds found a plentiful supply of food in the pools and marshes of the Mire, and shelter as well as safe breeding quarters in its almost impenetrable reed beds. On the swamps the Black-headed Gulls (*Larus ridibundus*) bred in colonies, and enlivened the scene by hovering in noisy circling flocks over their nests, their large spotted eggs being much prized by the herd boys who loitered on the neighbouring banks in charge of the stock which grazed in the drier parts of the bog. In the mornings and evenings the Hen Harrier (*Circus cyaneus*) could be seen passing slowly over the rushes, and quartering the wet meadow land like a well-trained setter, in search of prey to carry to its nest of hungry young in the thickest part of some neighbouring reed bed. As evening advanced many sounds fell upon the ear—the peculiar humming of the Snipe as the bird descended on tremulous pinions from soaring at an immense height to its home amongst the tussocky grass and rushes; the continual “Crek, crek, crek,” of numerous Landrails (*Crex pratensis*) along the grassy edges of the marsh; and the chattering song of the Sedge Warbler (*Acrocephalus schœnobœnus*) amongst the low thick clumps of alder and grey willow bushes; whilst, later on, at night-fall, the loud “Quack, quack,” of the Wild Duck, the harsh scream of the Heron, and the boom of the Bittern resounded through the air. In winter, after floods of rain, and when heavy snow melted, the whole Mire often presented the appearance of a far-extending loch, and thousands of wild-fowl were then seen frequenting its waters. Such was the state of Billie Mire down to the end of last century.

The accompanying plan shows the western part of the Mire, stretching from the march between the lands of Blanerne and Billie to the road between Auchencrow and Berwick, as it was in 1759; and the eastern part, extending

from the above road to a short distance beyond Causeway-bank, as it was in 1816. For the use of the plan of the western part I am indebted to Colonel Milne-Home of Wedderburn, and for that of the eastern portion I have to thank Mr. John Blackadder, Blanerne, who has likewise kindly favoured me with some notes regarding the drainage of the Mire. This, it appears, was done by deepening the western outlet of the superfluous waters of the Mire, and cutting a deep cast or ditch along the centre of the valley to lead the water to the western outlet. Mr. Blackadder, in his notes, says: "Sir William Hall of Whitehall, about the year 1780 or 1785, when the Duke of Bridgewater's canals were working in Lancashire, had a survey made for a canal from Eyemouth to Duns, to pass through Billie Mire, Billie Burn, and the ravine south of Elfole, and terminate near the present Manse. The cast was cut in the year 1801 or 1802. John Wait and Thomas Wilkie, Chirnside, were the contractors. Several people in Chirnside remember the whole of the Mire on the east of the Mire Bridge being covered with water, one cart only being able to pass at a time where the present bridge is built. The edges of the swamp were covered with rushes and black-headed reeds or canes, which were cut by the people of the adjoining villages for thatching their houses. After the cast was made, Mr. George Logan, tenant of Auchencrow Mains, drained his side of the bog, and for several summers employed his men and horses before harvest to cut the present Mire Brae road, carting the earth which came from the cutting—some thousands of loads—and spreading it on the moss to firm it. During the drainage operations he discovered upwards of twenty querns or hand corn-mills, supposed to be some of those left by General Leslie's army when it crossed the Mire near the site of the causeway stones, which are yet to be seen at this point. It would seem that the

cast which was made in 1801 or 1802 removed only a part of the water from the Mire, which therefore remained much in its natural state, and that the inhabitants of the neighbouring farms still occasionally heard

The Bittern sound his drum,
Booming from the sedgy shallow,
Scott, Lady of the Lake,

for Mr. William White, Lennel Hill Farm, has informed me that he remembers hearing the Mire Drum in the Mire when he was a boy living with his father at Causewaybank between 1815 and 1825. He went to reside at Causewaybank in the former year, and lived there for upwards of sixty years. He says that the Mire was then much in its natural state, and that it was not effectually drained until about 1830 or 1835.¹

Mr. John Blackadder states that the late Mr. David Aitchison, Oldcastles, told him that his (Mr. Blackadder's) father, about the beginning of this century, shot the last Mire Drum that was seen in Billie Mire, and that it was killed towards the east end of the bog, near Blackburn; also that the late Mr. Archibald Hood, Sunnyside, who often went out to shoot in company with the late Mr. Blackadder, gave a corroborative account of the incident.

Mr. Wilson of Welnage informed me on the 4th of May 1886, that an old man named Jamie Slight, who used to live at Nethermain, near Chirnside, told him that he had frequently shot the Bittern at Billie Mire before it was

¹ During the drainage operations the roots of oak and other trees were discovered. The farm steward at Causewaybank informed me when I visited the site of Billie Mire with Mr. John Blackadder on the 28th of April 1886, that when Mr. White, the tenant of Causewaybank, had occasion to bury horses or other animals which died on the farm, graves were dug for them in the soft soil of the Mire, and at the depth of five or six feet pieces of bog oak were found, also hazel nuts. He said that some years ago a considerable quantity of bog oak was discovered, and that a gentleman in the neighbourhood got it for the purpose of having a table made with it.

drained; also that John Davidson, an aged farm servant at Oldcastles, who had been brought up there, had mentioned to him that in his youth he had often heard the Bull o' the Bog bellowing at night in the vicinity.

Mr. Thomas Hewit, Auchencrow, stated to me on the 23rd of June 1886, that in his younger days he had frequently heard old people speak of hearing the Bull o' the Bog in the neighbouring Mire; and Mr. John Ferguson, Duns, relates that he has got similar accounts from villagers at Chirnside. A male Bittern was shot at the Hirsle in 1817, and another in the following year;¹ and a specimen was killed at Redheugh, in the parish of Cockburnspath, by Mr. Johnston, on the 6th of December 1834.² Mr. Kelly, Lauder, writing in 1875, says: "I have ascertained from Mr. Simson that Huntleywood Moss was once (1810) a favourite haunt of the Bittern, or 'Bull o' the Bog;' and for thirty years later occasional birds have been gotten, but it is now quite deserted."³ The last example seen in the neighbourhood of Mellerstain, according to Mr. John Thomson (writing in 1886), was "shot on Minchie Moss about forty years ago." Mr. John Aitchison, plasterer, Duns, informed me on the 20th of May 1886, that a Bittern was shot by John Hogg, gamekeeper, Preston, about 1851, on the estate of Cumledge, near the Knebs Rocks, on some rough ground by the side of the Whitadder, not far from the place where the old Waulk Mill stood. It was killed in the "back end" of the year, and was "stuffed" by Mr. Henderson, cabinetmaker, Duns. It was seen in his hands by Mr. Aitchison, Mr. W. Duns, builder, Mr. W. Marshall, blacksmith, and Mr. Thomas Cockburn, baker, all

¹ These specimens are in the Hawick Museum, where I saw them on the 27th of August 1890. The labels upon them state that the birds were preserved by "John Wilson, College Preserver of Birds and Quadrupeds to the Museum in the University of Edinburgh."

² *Hist. Ber. Nat. Club*, vol. i. p. 66.

³ *Ibid.* vol. vii. p. 305.

of Duns. In October 1882 Mr. Andrew Brotherston, bird-stuffer, Kelso, informed me that a Bittern was seen and heard at Lithtillum or Ferneyrig Bog, about 1874, by Mr. W. Paterson, gamekeeper to Sir John Marjoribanks of Lees, Bart.

There can be little doubt that in ancient times, long before the days of agricultural improvement and drainage, while as yet the Merse was covered with bogs and morasses which are now drained, the Bittern was found in every district of the county;¹ and it may be well supposed that King James IV., who frequently resorted to Bathgate Bog² to fly his Falcons at the Bittern there, would not fail to take an opportunity of trying their mettle at this noble quarry in some of the Berwickshire marshes, when he visited Lauder³ and Hume Castle⁴ with his falconers.

The bird was in olden times esteemed as a luxury for the table, and ranked with the Heron.⁵ It was formerly comparatively plentiful in the fen districts of England, where it bred. It still visits many parts of that country, and occasionally Scotland, on migration during the winter months, especially in severe seasons. The latest recorded instance of its nest being found in Great Britain was at Upton, in Norfolk, on the 30th of March 1868.⁶

The Bittern is very shy and retiring in its habits, hiding in thick reed beds during the day, and generally leaving these only by night or when accidentally disturbed. Seeböhm says: "Its flight is slow, steady, and silent, and,

¹ See *The Haigs of Bemersyde*, by John Russell, Advocate, 1881.

² See *Accounts of the Lord High Treasurer of Scotland*, 1473-1498, Preface, p. cclii.

³ The King "raide to Lauder to the halkan" on the 4th of January 1489.—*Ibid.* p. 127.

⁴ The King went to Hume Castle, apparently on a hawking expedition, with Hannay and Alexander Law, falconers, on the 19th of November 1496, and remained there ten days.—*Ibid.* p. 306.

⁵ *Birds of Norfolk*, Stevenson, vol. ii. p. 173.

⁶ Yarrell's *British Birds*, fourth edition, vol. iv. (1884-85), p. 209.

like its allies the Herons, its legs stretch out behind in a line with the beak, the head being drawn up between the shoulders whilst flying. It is far more nocturnal in its habits than any of the Herons, and the boom or love song of the male is heard at all hours of the night during the breeding season, and never in the day. It is a weird, unearthly noise, not to be dignified by the name of note, and may be heard at a considerable distance. The bird is so shy that the noise is instantly stopped on the slightest alarm. Some writers have likened it to the bellowing of a bull; others think it resembles the neighing of a horse; whilst more imaginative ornithologists trace in it a resemblance to their ideal of demoniac laughter. It consists of two parts—one supposed to be produced as the bird inhales, and the other as it exhales its breath. Naumann attempts to express it on paper by the syllable *ti-prumb*, repeated slowly several times. The call-note, which is common to both sexes, is a hoarse croak like the *ca-wak* of the Night Heron, or cry of a Raven, and is sometimes heard when the birds are on migration; but the 'boom' is only heard from the reeds, and as it is uttered the bird is said to stand with its neck stretched out and its beak pointing upwards."¹

¹ Seebohm, *British Birds*, vol. II. (1884), p. 504.



THE WHITE STORK.

Ciconia alba.

*Where the Rhine loses its majestic force
In Belgian plains, won from the raging deep
By diligence amazing and the strong
Unconquering hand of Liberty,
The Stork Assembly meets, for many a day
Consulting deep and various ere they take
Their arduous voyage through the liquid sky.*

THOMSON, *Autumn.*

A FINE specimen of this very rare bird was shot in a field on the farm of Blackpotts, near Coldingham, in 1848, and was for many years in the collection of Mr. William Patterson, Abbey Farm, North Berwick, where I have frequently seen it.

The White Stork occasionally visits the British Islands during the spring and autumn migrations, but has seldom occurred in Scotland. It winters in Africa, and in summer breeds in most of the countries of Europe, where its arrival in spring is looked upon with great pleasure by the inhabitants. It migrates by day, and at a great height. Seebohm says that its flight differs somewhat from that of the Heron, the neck being stretched out instead of being folded up until the head comes between the shoulders; and that, though the legs are stretched out behind, and the neck and bill extended in front, they are not in a straight line as in that bird, but both legs and neck are slightly drooped, so as to form a distinct curve.

The Stork feeds chiefly on frogs and fish, but lizards, snakes, small animals, young birds, and insects, are all

devoured by it. Its supposed antipathy to snakes is thus referred to by an ancient Scottish poet :—

The Cygonie that foul so whyte
Quhilk at the serpents hes despyte
Come granen to the ground.¹

¹ Burel's *Pilg.*, Watson's Coll., ii. 27 — From Jamieson's *Scot. Dict.*



THE BEAN GOOSE.

WILD GOOSE, SMALL GREY GOOSE, NARROW-BILLED GREY GOOSE.

*Anser segetum.**The Wild Goose.*

THE PINK-FOOTED GOOSE.

WILD GOOSE, SHORT-BILLED GREY GOOSE.

*Anser brachyrhynchus.**The Wild Goose.**And Wyld Geis eik claking by nychtis tyde,
Attour the cicte fleand hard I glyde.*GAWIN DOUGLAS, *A Description of Wynter.**"A straw for your wandering spirits," said Adam Woodcock, "I mind them no
more than an Erne cares for a string of Wild Geese."*SIR WALTER SCOTT, *The Abbot.*

IMMENSE flocks of Wild Geese frequent Berwickshire during the autumn and spring months, consisting of the Bean Goose, with its Pink-footed congener;¹ and as the relative number of the two kinds is a matter of conjecture, owing to the similarity of their plumage—whilst their habits are

¹ Seebohm says: "The Pink-footed Goose can scarcely be regarded as more than a local race, or an island form of the Bean Goose. With the exception of the fact that its notes are said to be sharper in tone and more rapidly repeated than those of the Bean Goose, it is not known to differ from that bird in any of its habits."—*British Birds*, vol. iii. (1885), pp. 498, 499.

alike—it has been considered advisable to include them both in this article.¹

The arrival of the Wild Geese in autumn is looked upon by the country people as a kind of land-mark in the calendar, being a subject of popular observation; and when they come before their usual period it is said to be a sign of an early winter. They are generally seen for the first time in the season passing high overhead in a wedge-shaped flock,² the attention of the people in the neighbourhood being usually attracted to them by the well-known "Honck, honck," of the birds; and, when they are descried, they are usually seen in stately and marshalled flight three or four hundred feet high in the air.

Amongst many records of their arrival in the county in autumn from 1800 to 1886, kindly given to me by Mr. Hardy, Oldcambus, the earliest is dated the 1st of October 1884, when they came to the Broad Bog, near Penmanshiel, just as harvest ended, and continued there in great numbers; the average date of their first appearance in autumn is the 26th of October, when they are generally observed flying from the north-west to the south-east.

They have certain favourite resorts, which are usually on bare, open, moory ground, such as in the locality last mentioned, or the Hule Moss in the parish of Greenlaw. They also frequent large open fields where they can have a good view of the approach of an enemy. When a flock

¹ The Earl of Haddington mentioned to me in a letter in 1887 that, in his experience, the most of the Wild Geese seen in Berwickshire are Bean Geese. Mr. Gray, writing of this species in the *History of the Berwickshire Naturalists' Club*, vol. vii. p. 465, says: "This bird seems to have been very scarce in the winters of 1874-75, the Pink-footed Goose having apparently taken its place. Unusual numbers of the latter bird have been seen and killed in Berwickshire and East-Lothian, and even in Stirlingshire, where it has hitherto been a complete stranger."

² It is supposed that by flying in the shape of a wedge, or a straight line, they cut the air with greater ease individually than if they flew in a confused flock, and that the leader drops behind when fatigued, his place being taken by another bird.

has selected a spot on which to alight, the Geese may be seen circling slowly round and round, first at a considerable height, and then gradually getting lower and lower until they reach the ground, when they all stand motionless for some time, with erect head and neck, watching attentively. If nothing suspicious is noticed, they commence feeding, one of their number, however, always acting as a sentinel to warn the others of any appearance of danger. When the sentinel gives the note of alarm the Geese run up to him, and, uttering their loud grating cries, take to flight, at first without any order, though after gaining some height they assume their usual wedge shape.

There is no better sport with the gun in this country than stalking Wild Geese, the sportsman having to exercise all his powers to get within range of these wary and almost unapproachable birds. Sometimes he has to crawl on his hands and knees for long distances, behind hedges and dykes, and often along wet ditches; but these difficulties are all forgotten when his hopes are crowned with success.¹

Unwearied patience, persevering toil,
Alone can crown the fowler's eager hopes,
Whate'er the season or whate'er the sport.

VINCENT, *Fowling*.

The late Earl of Wemyss was well known in Berwickshire as a keen and successful stalker of Wild Geese, and many anecdotes are related of his skill. One day, about twenty-five years ago, when fox-hunting near Reston, he was informed that some Wild Geese were frequenting the farm of Heughhead, then occupied by Mr. Joseph Allan, and although his Lordship's residence, Lennel, was about sixteen

¹ John Ker, 3rd Duke of Roxburghe—the Bibliomania Duke—"lay for hours together, though snow fell at the time, beside some lonely spring in the Cheviot Hills, where he expected the precarious chance of shooting a Wild Goose when the dawning should break."—*Chamb. Scot. Biog. Diet.*, iii. p. 309.

miles distant, he returned to Heughhead early on the following morning with his gun, and after a difficult stalk succeeded in shooting two Geese out of a flock on Draeden Field.¹ He sometimes used a stalking pony to get up to the watchful birds, keeping it walking in front, between him and them, to conceal his approach.² Stalking Wild Geese requires all the strength and ardour of youth on the part of the sportsman, and yet we find from the following letter, written by Mr. Alexander Brown, gamekeeper, Gosford Lodge, that in 1871 Lord Wemyss, then in his seventy-sixth year, was still enjoying that exciting sport:—"Gosford Lodge, Longniddry, October 9th, 1886. I can quite well remember the occasion of my dear old master shooting the Wild Goose of which you speak. It was in the Bog Field on Little Swinton Farm, about 7 o'clock on the morning of the 15th of March 1871. There was a large flock, and his Lordship got within forty yards of them. On the following Saturday he shot other two Geese on Simprim Mains, not far from Ladykirk Lodge, about 11 o'clock in the forenoon. His Lordship was riding a dun pony. It was the last year we were at Lennel."³

Great flocks of Wild Geese frequented the farm of Fenton-barns, near Drem, East-Lothian, in the autumn, winter, and spring months of 1867-68. They began to come there about the end of November and left in the beginning of April. The grass lands, as well as those sown with wheat after potatoes, were their principal resorts; but they had certain favourite fields upon which they alighted and fed, and seemed to prefer those which were either quite flat or had rising ground in the centre, from which they could

¹ For this information I am indebted to Mr. James Bertram, the present tenant of Heughhead Farm.

² Mr. James Hardy's *MS. Notes*, 1842.

³ This letter was written to Mr. John Miller, Ladykirk West Lodge, now forester to Colonel Milne-Horne of Wedderburn, at the Grange, near Coldingham.

easily observe the approach of an enemy. They very seldom ventured near any of the hedges, but generally kept about the middle of the field at a considerable distance from the fences or ditches, and were exceedingly vigilant and wary. Although I tried very often to creep up to them when they were feeding, I never succeeded in doing so, the birds always discovering me before I got near enough to use my gun with effect. The only way of getting within range of them which I found successful was by marking a flock from a distance with a telescope and then concealing myself behind a thick part of the hedge of one of the adjoining fields in the line of flight usually taken by the Geese when rising from the particular ground on which they were sitting. Before going to my place of concealment I used to instruct a boy in what direction to put them up, and, if he managed well, they sometimes came straight over my head within shot. In that way I had the satisfaction of bringing down a Goose occasionally with my gun. They sometimes sat all night in the fields when there was moonlight, but generally resorted to Gullane Sands in the evenings and returned to their feeding grounds in the mornings, shortly after sunrise. In Berwickshire Geese appear occasionally to remain on the open moors at night.

When they are seen winging their way from the north-west to the south-east it is probable that they are proceeding to Fenham Slakes in Northumberland, and when flying high to the north-west, Gullane Sands in East-Lothian may be their destination. They continuously frequent many localities in the county during the autumn months, and stay throughout the winter, when the weather is open, the latest recorded date at which they have been observed being the 22nd of May 1886, when Mr. Clay, Kerchesters, saw a flock of twenty flying over "Gibbs' Cross" field on the farm of

Wedderlie about 7 P.M., and heard a Cuckoo at the same time. He considered this to be unusually late for Wild Geese in that neighbourhood. During spring they are very fond of visiting ground newly sown with oats, which they greedily devour.¹ They likewise do considerable damage to young grass, and render the pasturage foul with their droppings.² They are sometimes trapped on the fields which they frequent³ by ordinary rabbit traps being set and carefully covered with fine soil on the ground where they feed, but when any are caught the flock does not usually return to the same spot for a season.⁴

As the haunts of Wild Geese in Berwickshire are gradually getting fewer in number, and many localities which were frequented by them in former times are now forsaken, the following list of farms and fields in each parish of the county which are still visited by them may not be without interest, and may prove useful for future reference. The information contained in the schedule has been supplied by the correspondents whose names are given below, and whom I take this opportunity of thanking for their kindness in responding to my enquiries.

¹ "March 20th, 1858.—One of the outer fields on Penmanshiel, surrounded by moor, was once an extensive bog, its name being the Braid Bog. Finished sowing it to-day. It was then frequented by Wild Geese, which at night ate the corn not fully harrowed in."—J. Hardy's *MS. Notes*.

² "October 5th, 1837.—One Goose will eat as much as a sheep, besides what it will defile. Sheep will not graze after them."—J. Hardy's *MS. Notes*.

³ Mr. Joseph Caverhill, Abbey St. Bathans, informed me on the 18th of January 1837, that Wild Geese had been sometimes trapped on Godscroft Woodheads by Mr. James Hunter. He told me at the same time that, in the autumn of 1836, Mr. William Allan made a successful double shot at Wild Geese on the farm of Bow-shiel, bringing down a Goose with each barrel of his gun; and that in the spring of that year Mr. David Purves, gamekeeper, Butterdean, killed two Geese in the same way on Harelawside. Mr. Caverhill likewise mentioned that Mr. John Moffat, Bankhead, killed seven Geese on Fannanside, near Godscroft, in the autumn of 1835.

⁴ A female Wild Goose was caught in a trap at Penmanshiel Moor in October 1842. The Geese never went near the spot where it was trapped during the remainder of the season.—J. Hardy's *MS. Notes*.

72 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Abbey St. Bathans.	Quixwood.	Broomhill & Yellow Craigs, two large fields adjoining each other.	They do not alight in spring, but are seen passing over from the south in April. From 12 to 30 in a flock.	In October. They have alighted only once in the last 15 years—about 5 years ago. Are seen passing over from north to south. About 30 to 100 in a flock.	John Hogg of Quixwood, Grants-house, 31st Oct. 1886.
	Abbey St. Bathans.	Abbey St. Bathans Moor.	They do not alight in spring.	The first week of October. They stay about a week, coming from north and departing southwards. 30 to 70 in a flock.	James Shiell, gamekeeper, Abbey St. Bathans, Grants-house, 12th Oct. 1886.
	Barnside.			In the beginning of October. Generally come from north, going southwards. 10 to 30 in a flock.	James J. Rankine, Barnside, Grants-house, 7th Oct. 1886.
	Whiteburn.	On all the fields of the farm.	Usually come in March. Not often seen after first week of April, generally travelling north.	They come from middle of October to middle of November, generally travelling southwards.	George Cockburn, Whiteburn, 4th Oct. 1886.
	Godscroft.	On fields that are sown with oats.	From middle of March to middle of April.	They very seldom come in autumn.	William Hunter, Godscroft, 29th Sept. 1886.
	Shannobank.			Flock seen alighting on this farm 6 or 8 years ago.	Thomas Cockburn, steward, Whitsome Newton, 16th March 1886.
Ayton.	Cocklaw.		Two Wild Geese were seen on a field on Cocklaw in March 1882.		James Purves, gamekeeper, Mordington, 12th April 1884.
Bunkle.	Preston.	Damhead.		A flock of 18 was seen on Damhead Field on 13th Oct. 1886. Seen in autumn.	John Barrie, gamekeeper, Preston, Duns, 13th Oct. 1886.
	Blanerne East.	Herd's Acres, 32 acre field, on hill top.	Beginning of March. Often see large flocks flying north in spring. Wild Geese have been seen on farm several times during last 15 years.		John Blackadder, East Blanerne, Chirnside.

THE BEAN GOOSE AND PINK-FOOTED GOOSE. 73

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Bunkle—continued.	Lintlaw.	Bogieside.		Large flock settled in field called Bogieside on 14th Oct. 1886.	Robert Bruce, gamekeeper, Blanterne, Chirnside, 25th Oct. 1886.
	Mayfield.	About 52 years ago they used to frequent all the fields on the farm, but none have been seen on it for 25 years.	They used to come in March and April.		W. Dunlop, Mayfield, 13th Oct. 1886.
Channelkirk.	Glengelt.			Sometimes alight on Glengelt fields, but not so often now as formerly. They visit the farm in October and November.	Thomas M. Skirving, Glengelt, Channelkirk.
	Overhowden.	Road Field, Croft Field, and Hill Field.	In March; cease coming about end of April. Come from south, go north. Flocks large.	In October; cease coming about end of November. Come from north, go south. Flocks small.	Robert Sharp, Overhowden, 12th Oct. 1886.
	Bowerhouse.			Flock of 6 alighted on farm on 6th Oct. 1886. They came from the east. Wild Geese have always frequented the farm.	John Fleming, Jun., Bowerhouse, 8th Oct. 1886.
	Hartside.	Fields sown with corn.	Come in March and April generally.	Not seen in autumn.	John Bertram, Hartside, 1st Oct. 1886.
Chirnside.	Edington Maina.		About 1845 a flock alighted on the farm on a knoll in the field in front of farm house, three of which were shot by Mr. Wilson's brother.		John Wilson, Weinage, Duns, 14th May 1886.
Cockburnspath.	Beclaw.		In April. From south to north.	In October. From north to south.	John Darling, Beclaw, Cockburnspath, 21st Oct. 1886.
	Edmendside.	Camps.			

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Cockburnspath—continued.	Penmanshiel—continued.		weeks, resorting to each alternately. They are damaging the grass.—29th April 1879. 8th Feb. 1880.—Small returning flock seen on 27th March; a great flock on moors behind Penmanshiel and Howpark, where they continued eating much grass until the 24th April following. 7th March 1881.—Came in great numbers to moors at Penmanshiel, and continued until 31st March. 8th Oct. 1886.—Wild Geese at Penmanshiel Broad Bog. 18th Nov.—They have damaged a great deal of corn on the moor exposed during October, owing to the bad weather of that month. They alighted on the stubble and pulled the sheaves to pieces. They sit in the middle of the field during the day.		
Coldingham.	Rentonbarns. Mont Albane.	Fifty Acre and Greenwood Fields. North Hill and Moor Hill.	Come when fields are sown with corn, and remain for a week or ten days in the vicinity. About April, and frequent newly sown oat fields and young grass. Last seen on farm in spring 1883.	Not seen on farm in autumn.	Alexander C. Hastie, Rentonbarns, 18th Oct. 1886. R. J. Scott, Mont Albane, Renton, 7th Oct. 1886.

76 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Coldingham— <i>continued.</i>	North Fala-knows.	Easter and Wester Lamb Lees.	In April. Flocks smaller in spring than in autumn.	About end of October and beginning of November. From 7 to 25 in a flock.	John Wood, North Fala-knows, Coldingham, 8th Oct. 1886.
	Cairncross.	Ladypark.	Flock seen on Ladypark 26th and 27th Jan. 1887.		John Miller, forester, Grange, Coldingham, 31st Jan. 1887.
	Auchencrow Mains.	Liddleshill.	They do not visit the farm in spring.	In November. About 90 in a flock.	Thomas Calder, Auchencrow Mains, 4th Oct. 1886.
	Crosslaw.		Occasionally seen on back fields.		Thomas Cockburn, steward, Whitsome Newton, 16th March 1886.
Coldstream.	Milne Graden West Mains.	Easter-Mondy Knowes.	Occasionally alight in March and April. Last seen about 11 or 12 years ago.	Not seen on farm in autumn.	John Miller, Milne Graden, Coldstream, 12th Oct. 1886.
	Lees.	Lees Haugh.	They sometimes alight in March on Lees Haugh, and swim on Learmouth Stream on the Tweed. There are usually from 3 to 20 in a flock. Rarely alight.		Thomas Hood, factor, Lees, Coldstream, 23rd Oct. 1886.
	Hawkslaw.				James A. Somervall, Hawkslaw, Coldstream, 2nd Oct. 1886.
	Skaithmuir.	Big Ingram, Butterlaw Hill, and Brown's Butts, &c.	They fly over the fields, but do not alight in spring. Small flocks.	They visit the farm from middle to end of October, seldom later. From south-east to north-west. Pretty large flocks. In some years they do not visit the farm.	J. Shaw, Skaithmuir, 4th Oct. 1886.
	Hatchetnise.	Wild Geese used to visit the farm regularly about 30 years ago. They sometimes alighted on Lith-tillum. 3 were shot on the farm.			J. Fulton, Hatchetnise, 7th Oct. 1886.

THE BEAN GOOSE AND PINK-FOOTED GOOSE. 77

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Cran-shaws.	Rawburn.	On all the cultivated fields on the farm when in young grass or oat stubble. The two fields most frequented are Crow-hill and Old Plantation Field.	They usually appear in spring, about the middle of March, and though they occasionally alight they do not stay long. In spring they come from the south and go north. The flocks are not so large in spring as in autumn—usually about 30. Wild Geese have always visited Rawburn Farm occasionally, but they have been more numerous of late years, owing to more land being cultivated now than formerly—the attraction apparently being the young grass fields.	In autumn they come from the 20th of October to the middle of November, and, if not molested, usually stay about two weeks. They come from the north and go south. Usually about 50 in a flock.	H. Hewat Caw, Rawburn, 6th Oct. 1886.
	Cran-shaws.	Sometimes, although seldom, they alight on the Whitadder Braes.	They come in April, flying from south to north.	In October, flying from north to south. Flocks large, often about 100 in a flock.	John S. Bertram, Cran-shaws, 2nd Oct. 1886.
Eccles.	Printonian.	Langbank, Bowmaker Hill.	At seed-time.	They do not visit the farm in autumn.	George Rutherford, Printonian, 6th Oct. 1886.
	Lochton.	Occasionally seen on farm. 3 shot in 1866.			Peter Cowe, Lochton, Coldstream, 7th Aug. 1886.
Edrom.	Green-knowe.	Allice-field. Occasionally alight on farm, but not often.		Small flocks sometimes come. A flock of 7 frequented Allice-field in 1882 for 5 days.	Mark Cosser, Greenknowe, 16th Oct. 1886.
	Cairnsmill.	Easter Ridley, Sand Pit Field, Haugh.		One shot on the 20th October 1884.	John Thomson, gamekeeper, Kimmerrhame, 3rd Nov. 1886. G. Nisbet, gamekeeper, Nesbit House, Duns, 12th Oct. 1886.

78 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Edrom— continued.	Kimmer- ghame Mains.	Bog Field.		3 seen on Bog Field in autumn of 1883.	John Gray, Bellahiel, 7th Oct. 1886.
Duns.	Kidahiel- haugh.	Pilgrim's Acre.	During seed-time in spring, and continue for two or three weeks. Seldom alight in spring.	Have not seen them on farm in autumn.	Thomas Johnston, Kidahielhaugh, Duns, 6th Oct. 1886.
	Hardens.	Harclaw Field in Duns Parish.		Come about first week in October, and give up coming about end of same month.	John H. Laurie, Hardens, Duns, 15th Oct. 1886.
Fogo.	Printonlan.	Sieverig, Calfwad, Wester Muir.	If open spring, from middle of February to first week in April. They always come from north-west, and return in same direction. About 30 to 60 in a flock.	From middle of October to the end of same month. From 15 to 35 in a flock.	William Thompson, gamekeeper, Charterhall, 11th Oct. 1886.
	Fogorig.	Biselawrig, Stagpark, Bowshot, Trainmine.			
	Ryselaw.	Long Hill and West Shot Dykes.	Stay a short time in spring. Flocks smaller in spring than in autumn. They come from south-east and go north-west.	Visit the farm for a short time in autumn. They come from the north-west and go south-east. Flocks larger in autumn than in spring.	James Anderson, steward, Ryselaw, 9th Oct. 1886.
	Sisterpath.	Chesters, East and West Wormrigg, both 50 acre fields; sometimes alight on adjoining fields.	They do not feed in spring on farm, but are seen passing over. One was shot on Wester Fawrig on 2nd April 5 or 6 years ago. They have not returned to that field since then.	They come after harvest, and give up coming when corn gets scarce. They come from the ponds on Kyleahill Moor (this is also known as the Hule Moss), and return there. Two were shot on East Wormrigg Field in November 1883. There have not been so many since that year. About 40 passed over Sisterpath on the 25th Sept. 1886—the first flock this season.	Thomas Torrance, Sisterpath, 2nd Oct. 1886.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Foulken.	Foulken New Mains.	Mill Pond.		On 14th November 1878 a flock alighted on the Mill Pond. James Purves, gamekeeper at Foulken, shot one of them.	G. Millican, Foulken New Mains, 6th Nov. 1886.
	Foulken West Mains.	Damhead Field.	Seen passing high overhead in spring, from middle of March to middle of April, going north.	Seen only once in last 20 years. About 10th November, 15 years ago, two alighted on Damhead Field when sown with wheat. Large flocks pass high overhead in end of October and November, going south.	H. Hewat Craw, Foulken West Mains, 5th Oct. 1886.
Gordon.	Rumbleton Law.	Lilrig and Hill.	Come in March and until about the 20th April. If put up, they fly to Greenlaw-dean and Hallyburton.	Come in October, and remain until snow-storm occurs.	John Jamieson, gamekeeper to Lord Haddington, in Gordon District, 9th Oct. 1886.
	Fallside.			Only once seen on farm during a gale in autumn.	Alex. White, Fallside, 3th Oct. 1886.
	Middlethird.	Betty Field, Todrig Bank and Moor.	About 20th Feb. to 10th March. From 10 to 50 in a flock.	They have not been known to alight in autumn.	Middlethird.
	Rumbleton, Rumbleton Law, Hexpath.		If the winter be open, the Geese come about the middle of November, and do not leave until April. In general they come from a northern direction, and leave in the same way, both in spring and autumn. As many as 200 sometimes in a flock. About 20 years ago they frequented some lower down fields on Mellerstain Estate.		James M'Pherson, gamekeeper, Mellerstain, 15th Oct. 1886.

80 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Greenlaw.	Bedshiel.	On most of the fields.		They come in autumn and when the winter is mild; they seldom leave until spring.	Edward Lithgow, Bedshiel, 20th Oct. 1886.
	Old Greenlaw.		For the last 24 years have only been seen on farm once or twice.		William Duncan, Old Greenlaw, 19th Oct. 1886.
	Angelrow.	Shed Park.	They visit the farm during winter and spring, and are sometimes seen on the Mill Pond, which is in the Shed Park. They appear to come from the north, and leave in the same direction. They come from February to April.		James Burton, Angelrow, 11th Oct. 1886.
	Greenlawdean, Hallyburton, and neighbourhood.			They come in October, and continue coming as late as December. They come from north-east, and go south in flocks of 20 to 100. As many as 700 have been seen in a flock on Greenlawdean.	W. Smith, gamekeeper, Duns Castle, Duns, 11th Oct. 1886.
	Greenlaw Moor.	The Hule Moss, a sheet of water extending to about 17 acres.	If the winter be mild, a considerable number remain all the season about the Hule Moss, leaving when frost sets in, and returning immediately after the water is open. All depart about the 20th April.	They usually arrive about the 1st of October. Their stay depends on the weather; when frost sets in they leave, and return again when the weather becomes mild. They come from the north, and usually go southward. They arrive in flocks, not exceeding 50 or 60 birds, until they accumulate to nearly 1000 in number.	Thos. Smith, gamekeeper, Marchmont, 15th Oct. 1886.
Hutton.	Broad-meadows.	Gordon Law.		A flock was seen 30 years ago sitting on the Gordon Law Field.	D. Howick, Hutton Mains.

THE BEAN GOOSE AND PINK-FOOTED GOOSE. 81

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Hutton — continued.	Hutton Mains, West Fishwick.	Big Muir Field.		A flock was seen on Big Moor Field about 15 years ago; and on a field of West Fishwick, next Winfield, about 10 years ago.	Gamekeeper, Broadmeadows, 12th Oct. 1886.
	Spital Mains, Clarahead.			Wild Geese used sometimes to alight on Spital Mains and Clarahead Farms, but have not done so for many years. Two were shot some years ago by Mr. Stow-Compton-Lundie on Spital Mains.	W. Compton-Lundie of Spital, Spital House, Oct. 1886.
	Paxton South Mains, Sunwick.	Toll Field.		A small flock alighted on the Toll Field a few years ago. Wild Geese used to visit the fields about the moor long ago.	John Nesbit, Paxton South Mains, 8th Oct. 1886.
Ladykirk.			"In spring Wild Geese frequent the country."—Rev. Thos. Mills, Minister of Ladykirk, in <i>Old Stat. Acc. of Scot.</i> (1793), vol. viii. p. 74.		
Langton.	Langton Lees.	Stubble fields and young grass.	Very seldom come in spring.	Occasionally visit farm in autumn.	Thomas Torrance, Langton Lees, 23rd Oct. 1886.
	Woodend.	On high fields near Damhead.	Visit farm in Feb. and March. Come from south-west, go north-east.	Come to farm in September and October. Flocks number from 6 to 50.	J. S. Braah, Woodend, 15th Oct. 1886.
	Cholcelee.	North Hill, Birks, when these fields are in young grass.	March and beginning of April. Come from south and go north.	September and October. Come from north and go south. Flocks large.	Alexander Penny, Cholcelee, 13th Oct. 1886; and George Mercer, 8th Oct. 1886.

82 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Lauder.	Blythe.	Higher fields on the farm.	Occasionally visit farm in spring. They come from the south, but do not stay long. They appear to feed on the farm during the day, and leave for the moor on Hallyburton Farm in the evening. I do not think that they come so often to the farm as they did some time ago.		Geo. M'Dougal, Blythe, 30th Oct. 1886.
	Thirlestane.	The Brae Field, and other fields.	Come in April, and occasionally in May. They come from south-east, and go south by east.	In autumn they come from north and go south-east. They do not visit the farm now as frequently as they did 16 years ago.	Robt. Bruce, Thirlestane, 12th Oct. 1886.
Legerwood.	Boon, and Cribba.	Cribba-bank, and Candle-maker Fields.	They are not observed to visit farm in spring.	They occasionally frequent farm in autumn. A flock here at present, and been so for past 10 days. Wild Geese often visit Corsbie Farm.	Robert Shirra Gibb, M.B., C.M., Boon, 25th Oct. 1886.
	Corsbie.				
	Legerwood.	Candle-maker Field.		When I went to Legerwood in 1841, Wild Geese alighted in a field called Candlemaker, and for some years afterwards (always in the month of April), on their way north. In coming back in autumn they passed overhead without alighting. After the large field—90 acres—was divided and the plantation grew up, the Geese gave up alighting on the farm. They never visit the farm now. It is 35 years since they frequented it.	John Logan, Legerwood, 9th Oct. 1886.

THE BEAN GOOSE AND PINK-FOOTED GOOSE. 83

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Longformacus.	Ellemford.	Girthgate Hill; Teindhill.	The Geese do not visit Ellemford Farm now, but pass over it in large numbers in autumn. The last time I saw them sitting on the farm was in April 1865, on a newly-sown field called Girthgate. There would be about 200 in the flock. They used to alight also on the Teindhill field, in which the old manse of Ellemford stood.		W. Elliot, Ellemford, 30th Oct. 1886.
	Felicleugh.	Moorylaw.	Occasionally visit high-lying fields in spring about seed-time.	Autumn, after the harvest. Have seen them frequent farm for 3 weeks at a time.	J. Johnston, Felicleugh, 18th Jan. 1886.
	Retreat.	Cairnfield, Shepherd's House Field, Duddieslea.	Used to come to farm in spring and autumn some years ago. Occasionally in spring. In flocks of from 10 to 30. Seen in autumn flying about the hills, and feeding on Rawburn young grass lands.		P. Hastie, Milne Graden, 10th Sept. 1884.
	Longformacus.		A flock of 6 or 8 alighted a few years ago on the Dye, near the Heron's Hole.		James Bertram, Retreat, 8th Oct. 1886. Colonel Brown of Longformacus, Oct. 1886.
Mordington.	Lamberton.	Brotherstone and Millburn—two knolly fields close to the coast. Camp Field.	Have not been noticed on the farm in spring.	They occasionally visit the farm in September or October.	Rev. George Cook, The Manse, Longformacus, Oct. 1886.
	Mordington Maina.	Big Moor, Jock's Park.	On 1st Jan. 1884 a flock of 20 alighted on the Camp Field. They seldom alight. Saw two in March 1883 on the Big Moor Field.		James Mein, Lamberton, 28th Oct. 1886. James Purves, gamekeeper, Mordington, 12th April 1884. James Purves, gamekeeper, Mordington, 11th Oct. 1886.

84 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Oldham-stocks (detached)	Butterdean.	Camps, Gowt, Longbank.	Come in middle of March, and leave about end of April. They visit Butterdean Farm.	Arrive in October and leave in November.	Thomas M'Kinlay, Butterdean, 8th Nov. 1886.
Swinton.	Little Swinton.	Bog Field used to be formerly visited; now the Geese alight on the field in front of the farm-house.	Mostly arrive in March. One was shot by the late Lord Wemyss on 16th March 1871. They usually come from the south-east, and in leaving fly north-west.	They also visit the farm in autumn.	John Miller, Milne Graden, 12th Oct. 1886.
	Do.			Seven very large Wild Geese were seen sitting within 100 yards of Little Swinton stackyard on 6th Oct. 1886.	Thomas Calder, Swinton Hill, 9th Oct. 1886.
	Swinton Hill.	Nisbet Hill, West and East Low Fields along the march with Simprim.	March and April. They give up coming about the end of the latter month.	October and November. The late Mr. James H. Calder shot one on Nisbet Hill Field about the middle of November 1860. Lord Wemyss used to come to shoot the Wild Geese long ago with a white stalking pony.	Thomas Calder, Swinton Hill, 9th Oct. 1886.
	Simprim Malna.		Frequent farm in spring. The late Lord Wemyss shot 2 on this farm on 22nd March 1871.		John Miller, Milne Graden, 12th Oct. 1886.
	Greenriggs.	Flat fields at the side of the Leet.	Over 30 years ago, when the flat land on Greenriggs Farm was in grass and un-drained, Wild Geese used to alight there, and were stalked occasionally by the late Earl of Wemyss.		Mark Cossar, Greenknowe, 16th Oct. 1886.

THE BEAN GOOSE AND PINK-FOOTED GOOSE. 85

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
West-ruther.	West-ruther Mains.		Occasionally, but not often. Have observed them alight on the farm only three times.		James Gibson, Westruther Mains, West-ruther, 30th Oct. 1886.
	Cammer Laws.	Pond Field, Wood Park, Backrig Park.	They come about the end of March, and give up coming about the end of April. They are very fond of grass that has been sown down without a crop. The flocks are usually smaller in spring than in autumn.	They arrive about the middle of October, and leave about the end of November, but occasionally stay later. The average number in a flock varies from 40 to 60, but as many as 150 have been seen.	Robert Lyal, Cammer Laws, 9th Oct. 1886.
	Hindside-hill.		About 8 years ago two were shot on this farm near the village of Houndslow by a Spottiswoode gamekeeper.		John Young, gamekeeper, Spottiswoode, 11th Oct. 1889.
			They used to come in spring to Easter Langrigs Field, where there was a pond.		R. Renton, Spottiswoode, 26th Aug. 1886.
	Wedderlie.	Outer House, Edgar Hill, Gibb's Cross.	Come in March if weather be good, and generally in April. Flocks large - up to 60 birds. The Geese visit the farm only when the fields mentioned are in young grass. 83 Geese were seen sitting on Gibb's Cross Field on 3rd March 1885.	Occasionally come in autumn during October. Flocks small.	W. Anderson, shepherd, Wedderlie, 1st Oct. 1886.
		Hally-burtons.	About 18 years ago they used sometimes to frequent the flat mossy ground to the west of Wedderlie House.		Matthew Craig, steward, Wedderlie, Aug. 1886.
	Harelaw.		Come in spring to the mossy grass fields of the farm.	Also visit the farm in autumn.	Farm steward at Harelaw, West-ruther, 24th April 1885.


86 THE BEAN GOOSE AND PINK-FOOTED GOOSE.

Parish.	Farm.	Fields on which the Wild Geese alight.	Date when they come in Spring, with Remarks.	Date when they come in Autumn, with Remarks.	Name and Address of Correspondent.
Whitsome.	Winfield.	Gordon Law and White Field.	They visit the farm, but not regularly every year now as they did from 25 to 46 years ago. They come in March and April, their visits depending upon the weather. They arrive from the south-east, and leave in a north-westerly direction.	They do not come regularly, but sometimes visit the farm in October and November. They have been known to stay a week at a time, feeding on the young grass fields. Arrive from the north-west, and leave in a south-easterly direction. The flocks are larger in autumn than in spring.	John Clay, Winfield, 10th Oct. 1886.
	Whitsome-hill.	Rippleton.	Very rarely visit this farm.		James Craw, Whitsomehill, 14th Oct. 1886.
	Leetside.	Catchhill and Merry-lees Fields.	Visit the farm sometimes, but not so often as they did formerly.	Occasionally alight in autumn, but not often.	David Herriot, Leetside, 11th Oct. 1886.
	Whitsome Laws.		Very seldom visit this farm. Have seen them only twice on it during last 20 years.		Thomas Torrance, Whitsome Laws, 23rd Oct. 1886.

The Hule Moss—a picturesque sheet of water on a lonely part of Greenlaw Moor, between Marchmont and Dogden Moss, and extending to nearly seventeen acres—is a favourite resort of Wild Geese.¹

A correspondent who is well acquainted with their habits informs me that they usually come to this haunt in October and November, though he has seen them there as early as the middle of September and as late as December. In spring they frequent the Moss from February to the

¹ See Sheet xxi. 4, 54, Ordnance Survey Map of Parish of Greenlaw. The extent of the water is 16·869 acres.



John Platteau 1847
Rocky Mts. Wyoming and Southern Kansas in distance

middle of April. They generally arrive in the dusk of the evening, and alight about the middle of the lake, where they remain for some time, afterwards swimming ashore to rest on the heather until the morning, when they depart to feed on the stubble fields. When alighting they sweep down with a sloping flight into the water, and on windy nights they are seen flying low over the moor.

Mr. Loney relates that about fifteen or sixteen years ago a gamekeeper at Marchmont shot seven Wild Geese at the Moss in one night, when it was so dark that he could not see where the birds fell. On going in search of them next morning he found five lying in the water and two on the heather at its edge. He says that the Geese come regularly every year to the Moss in spring and autumn.

Greenlaw Moor is extensive, and comparatively flat; and, as the sheet of water called the Hule Moss has no banks surrounding it, the Geese can float on its surface in safety, the approach of an enemy even at a distance being easily observed. I visited the Hule Moss with Mr. Loney and Mr. John Blair, artist, on the evening of the 14th of July 1886, when the accompanying sketch was made by Mr. Blair. The Moss then presented a beautiful and interesting appearance, with its clear water rippling in the breeze, and gleaming from afar in the light of the setting sun. From its southern edge, looking towards the north, were seen the two Dirringtons, Great and Little, towering towards the sky, in connection with which the following popular rhyme relating to the weather is sometimes heard:—

When Dirrington puts on its hood,
And Cockburn Law its cowl,
A' the herds o' Lammermuir
Ken that it will be foul.

Behind the Dirringtons, and in the direction of Wedderlie, could be observed the Twinlaw Cairns, around which the

beautiful ballad of "The Battle of Twinlaw"¹ has thrown a halo of romance like the soft purple light of the evening which then coloured the landscape. Far away in the distance to the south-west the Eildons rose above the horizon, bringing recollections of "the wondrous Michael Scott" and

The words that cleft Eildon Hills in three,
And bridled the Tweed with a curb of stone.²

Mr. Hardy says that boys in the county believe that the Wild Geese in their flight can form all the letters of the alphabet.³ They sometimes call to the Geese—

Tring a' tring o' Wild Geese
Black Jock forenent.

Another rhyme heard among children in Berwickshire is—

Wild Geese! Wild Geese! how far will ye flee,
To Herrington and Berrington and owre the Red Sea?
Where do ye sit? Down the water-fit.
Where do ye stand? On the dry land.

When heavy snow is falling in large flakes the Berwickshire boys say that

The folk o' the East are plucking their Geese,
And sending their feathers to me, O!⁴

The Wild Goose appears to have been much used for the table in Scotland in olden times, for we find the Scottish Parliament in 1551 fixing the price of the "Wild Guse of the great kind" at "twa shillings."⁵

The Bean Goose has yellow legs and the middle portion

¹ *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 73.

² *Lay of the Last Minstrel*, canto ii. 13.

³ In the neighbourhood of Saltoun, in East-Lothian, I have heard boys thirty years ago calling to the flocks of Wild Geese, as they passed high overhead in the air, "Make A, make O," and so on.


⁴ A similar rhyme is heard in East-Lothian—

"The folk o' the East are plucking their Geese,
And sending their feathers to our toon."

⁵ *Laws and Acts of Parliament of Scotland*, by Sir Thomas Murray of Glendook: Edinburgh, 1681, p. 145.

of the bill orange, whilst in the pink-footed variety these parts are flesh-coloured. In both birds the "nail" at the tip with the base of the bill is nearly black.

Although it is probable that the Grey-lag Goose (*Anser cinereus*) visits Berwickshire at the same season as the other species, yet there appears to be no record of its occurrence in the county. It differs from the subjects of our notice by having the lower back of a lavender grey, some of the feathers of the under parts blackish brown, and the bill flesh-coloured, without any black on the "nail" or at the base, where there is a narrow margin of white feathers.



THE WHITE-FRONTED GOOSE.

LAUGHING GOOSE, BALD GOOSE, WHITE-FACED GOOSE.

*Anser albifrons.***Wild Goose.***Winter's not gone yet if the Wild Geese fly that way.*SHAKESPEARE, *King Lear*.*I have a wie lairdschip down in the Merse,
The nyeteenth pairt of a Gusse's gerse,
And I wo' na cum every day to wow.*

SCOTTISH BALLAD.

THE White-fronted Goose is very like its Bean and Pink-footed congeners in size, general colour, and appearance, but it may be easily distinguished from them by the white feathers on the forehead and round the base of the bill, and the black bars on the lower part of its breast. It frequents bogs and marshes more than they do, and is not considered to be so difficult to stalk.

This species probably visits the county in small numbers in autumn and spring, but the only authentic record of its occurrence in Berwickshire, which I have been able to obtain, is that of an example shot in the Sandpit Field, on the farm of Greenknowe, by the gamekeeper of Kimmerghame estate, on the 1st of February 1884, who informed me that it was alone when he killed it. It was identified by Mr. George Bolam, Berwick-on-Tweed, shortly afterwards.

THE BRENT GOOSE.

THE BLACK-FACED BERNICLE GOOSE, BRAND GOOSE, BLACK-
HEADED BARNACLE, RING-NECKED BARNACLE, CLATTER
GOOSE, HORRA GOOSE, WARE GOOSE, BLACK GOOSE,

Bernicla brenta.

Wild Goose.

*From the frozen North, where Winter's hand,
With sway despotic and untam'd, locks up
The shrinking world; o'er the wide ocean borne
On vigorous wing, pour forth the feather'd tribes
Diverse and strange.*

REV. JOHN VINCENT, *Fowling.*


THE Brent Goose is a winter visitor, and is the smallest of the various species of Wild Geese which are found on our shores. It is occasionally seen off the coast of Berwickshire during the winter months, but it seldom visits the interior of the county, the only instance of its occurrence in the Merse with which I am acquainted being that of an immature specimen in the possession of Mr. Allan of Peelwalls, which was shot on Billie Mains Mill Pond about thirty years ago. Immense flocks frequent Fenham Flats, near Holy Island, in Northumberland, from autumn until spring, where numbers are frequently killed, as they are excellent birds for the table.

This species feeds chiefly upon marine plants¹ and insects.

¹ Mr. Andrew Brotherston, bird-stuffer, Kelso, records that in the early part of February 1879 he had two Brent Geese sent to him for preservation, and their stomachs were filled with grass-wrack (*Zostera marina*). He adds that they had probably been feeding on the slakes between Fenham and Holy Island, where this plant occurs in great abundance, and where so many Brents were killed at the time above mentioned that they were selling at one shilling each.—*Hist. Ber. Nat. Club*, vol. viii. p. 587.

The ancient Scottish name of the Brent Goose was the Rood, Rude, or Rute Goose, and we find Queen Mary, in her fifth Parliament (1st of February 1551) fixing the price of this bird at "auchteen pennies."

The Brent Goose can at once be distinguished from the Bernacle Goose by its black head and the white patch on the side of the neck. Young birds of the year have not the white patch.



THE BERNACLE GOOSE.

THE WHITE-FACED BERNICLE GOOSE, CLAIKIS, CLAKIS, CLAIK
GOOSE, BARNACLE, WHITE-CHEEKED BARNACLE,
LAND BARNACLE.

Bernicla leucopsis.

Wild Goose.

*All Water-foullis war swemand thair gude speid;
Alse out of growand treis thair saw I breid,
Fowlis that hingand be thair nebbis grew.*

GAWIN DOUGLAS,¹ *The Palace of Honour.*

THIS winter visitor, which can be easily distinguished from the Brent Goose by its white forehead and cheeks, is occasionally seen off the coast of the county. It seldom visits the inland parts of Berwickshire, but stragglers have been sometimes shot at a distance from the sea. Mr. Lockie informs me that one visited Dod Mill Pond in the autumn of 1883, and remained there for about two months. It became somewhat tame, and used to follow the farmyard ducks, but disappeared when the pond became frozen over in winter. Mr. John Wilson, Chapelhill, Cockburnspath, writes that a flock of ten Bernacle Geese visited Chapelhill Farm in January 1876, when he shot two of them.


It is a very noisy bird, and both when feeding and on the wing keeps up a continual cackling sound. Its food consists chiefly of grass and bents.

¹ Gawin Douglas, who was born in 1475, was Rector of the parish of Prestonkirk, in East-Lothian, 1496, and in 1509 Dean of the Collegiate Church of St. Giles, Edinburgh. He was made Bishop of Dunkeld 1516, and died of the plague in London 1522.

In olden times it was believed that this Goose was generated from the Barnacle (*Lepas anatifera*), and Hector Boece, our oldest historian, gives a curious account of

The Scottish Barnacle, if I might choose,
That of a worme doth waxe a winged goose.

Its price was fixed by the Scottish Parliament in the time of Queen Mary (1551) at "auchteen pennies." It is an excellent bird for the table.



THE CANADA GOOSE.

THE CRAVAT GOOSE.

Bernicla canadensis.

They flock together in consent, like so many Wild Geese.

SHAKESPEARE, *Henry IV.*

THIS large and handsome Goose has occasionally occurred in Berwickshire. Five specimens were shot at Dowlaw mill pond by Mr. William Cowe on the 14th of May 1867,¹ and one or two have been killed on the Leader, near Lauder.² Dr. Stuart of Chirnside records that Mr. Millican, Foulden New Mains, saw a flock feeding in his mill pond there on the 16th of July 1882. Supposing them to be tame birds, he incautiously approached them, when they took wing and flew over in the direction of Blackburn.³ As this species is kept on a large pond at Gosford, in East-Lothian, with other water-fowl, and it rears its young there, it is probable that the examples seen in this county have come thence.

This bird is about forty-one inches in length, and may be known by its black head and neck, while a white patch extending from under the chin to behind the ears has given it the name of the Cravat Goose.

¹ *Hist. Ber. Nat. Club*, vol. vi. p. 435.

² *Ibid.* vol. vi. p. 18, and vol. viii. p. 147.

³ *Ibid.* vol. x. p. 573.



THE WHOOPER.

ELK, WHISTLING SWAN, WILD SWAN.

Cygnus musicus.

The Wild Swan.

'Twere sweet to mark the setting day
On Bourhope's lonely top decay ;

Thence view the lake,¹ with sullen roar,
Heave her broad billows to the shore ;
And mark the Wild Swans mount the gale,
Spread wide through mist their snowy sail,
And ever stoop again, to lave
Their bosoms on the surging wave.

SIR WALTER SCOTT, *Marmion*.

THE earliest record of an appearance of the Wild Swan in the county occurs in a diary kept by Captain Bell, of the Berwickshire Militia, who, about the beginning of this century, resided at Linthill, near Eyemouth. The entry in the diary is as follows:—"October 23rd, 1800.—Saw three Wild Swans—not flying high. Got in the last of my corn crop—oats—weather fine."

Writing in August 1834, the Rev. J. S. Goldie, minister of Coldstream, says that Wild Swans have been shot in that parish;² and in January 1835 the Rev. John Turnbull, minister of Eyemouth, mentions that "a few months ago several Swans made their appearance in the bay of Eye-

¹ St. Mary's Loch.

² *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 206.

mouth, one of which was shot."¹ Mr. Hardy, Oldcambus, relates that about 1843 three were seen, one of which was captured at Heughhead, and another near Press. Mr. Wilson of Welnage has informed me that a specimen was killed on the Whitadder, near Cumledge, about thirty years ago. The late Mr. Wilson of Cumledge got the bird stuffed, and kept it for many years. During the very severe winter of 1879-80 several Wild Swans frequented the Tweed between Paxton and Berwick, some of which were obtained, one of them (a very large male) being in my collection. According to Mr. Millican, Foulden New Mains, four others visited his mill pond in winter a few years ago, and remained about six weeks. When disturbed, they rose, and after flying a mile or two round in a circle, returned to the pond. He saw them rise from the water one morning, and, after mounting high in the air by circling round and round, make straight off towards the sea at Lamberton, whence they did not return.

The Wild Swan does not breed in any part of Scotland, but visits this country on the autumn and spring migrations, its numbers depending upon the severity of the season. It frequents the sea-coast of Berwickshire, but is sometimes seen on the rivers and inland ponds of the county.

The whole length from the point of the bill to the end of the tail is five feet, and the weight about twenty-four pounds. The front of the bill is black, and the posterior part yellow.

The general colour of the young birds is greyish brown.

In the list of prices of game fixed by the Scottish Parliament in the reign of Queen Mary (1551), the Swan is entered at five shillings.

A curious old custom in connection with the Swan is


¹ *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 322.

alluded to by Dunbar in his "Prayer that the King war
John Thomsoun's Man":¹ —

I wald gif all that ever I have
To that conditioun, sa God me saif,
That he had vowit to the Swan,²
Ane yeir to be Johne Thomsoun's man.

¹ The phrase was proverbial for a person who was ruled by his wife.

² "'That ye had vowit to the Swan.' The stanza containing this line is quoted from the *Mait. MS.* by Mr. Tyrwhytt in his excellent Glossary to Chaucer, who there adduces a singular instance of this vow from Matthew of Westminster. When Edward I. was setting out on his last expedition to Scotland (1306), a festival was held at which 'allati sunt in pompatica gloria duo cygni, vel olores, ante regem, phalerati retibus aureis, vel fistulis deauratis, desiderabile spectaculum intuentibus. Quibus visis rex votum vovit Deo cœli et cygnis se proficisci in Scotiam.' In the days of chivalry it was customary for the knights to make vows to God over a roasted Swan, Peacock, Heron, or other bird, and these vows were held to be inviolable. The bird was afterwards carried to the table."—Sibbald's *Chron. of Scot. Poetry*, vol. i. p. 323.



BEWICK'S SWAN.

Cygnus Bewicki.

The Wild Swan.

*Sum swallis swan, some swallis dwik,
And I stand fastand in a nuik.*

DUNBAR.

BEWICK'S SWAN, which is about one-third smaller than the Whooper, and, like that bird, visits Scotland on migration, is occasionally seen off the coast of Berwickshire during the winter months. Mr. Hardy, Oldcambus, writing on the 12th of November 1886, mentions that a specimen of this Swan was brought to him from Redheugh on that day, and adds that it had been cast ashore, probably by the storm which took place on the 5th and 6th of the same month.¹

The length of Bewick's Swan is about four feet, and the base of the beak is orange yellow. In yèung birds the plumage is greyish brown.

¹ Mr. Hardy's *MS. Notes*.



THE COMMON SHELD-DUCK.

SHIELDRAKE, SHELDRAKE, SKELGOOSE, SKEELING GOOSE,
BURROW-DUCK, ST. GEORGE'S DUCK, SLY GOOSE, STOCK-
ANNET, BARGANDER, BARDRAKE, BAY-DUCK.

Tadorna cornuta.

The Sheldrake.

*The sleeping Shell-Ducks at the sound arise,
And utter loud their inharmonious cries ;
Fluttering, they move their weedy beds among,
Or instant diving hide their plumeless young.*

CRABBE.

THIS beautiful bird, which is a permanent resident in Scotland, is seldom seen in Berwickshire, as the coast is too precipitous for its habits. Small flocks, however, have been occasionally observed on the Tweed in the neighbourhood of Paxton during severe weather about the end of winter, when they were invariably very wild and shy.

Mr. Charles Watson, Duns, has informed me that a specimen of this bird was shot at Chirnside on the 27th of April 1878; and Mr. Peter Cowe states that an example was killed on a pond at Lochton in 1884.

The Shell-Duck nests in burrows on sandy links by the sea-shore, one of its breeding places being between Holy Island and Bamborough on the Northumberland coast.¹

It may be easily distinguished by a broad band of rich chestnut which extends from the lower part of the white breast over the back at the base of the neck.

¹ *Birds of Northumberland and Durham*, by J. Hancock, p. 150.

THE MALLARD,¹ OR WILD DUCK.

MIRE DUCK, MOSS DUCK, MUIR DUCK, GREY DUCK.

Anas boscas.

The Wild Duck.

*High o'er the restless deep, above the reach
Of gunner's hope, vast flights of Wild Duck stretch
Far as the eye can glance on either side,
In a broad space and level line they glide,
All in the wedge-like figures from the North,
Day after day flights after flights go forth.*

CRABBE.

IN former times the Wild Duck was much more plentiful in Berwickshire than it is at present, for agricultural drainage² and improvements have removed nearly all the bogs and morasses which it loved to haunt, amongst which may be mentioned Billie Mire, where, until the early part of this century, it was seen in hundreds. As few people at the present day have any idea of the great alterations which have taken place over the surface of the county since the middle of last century, it is interesting to hear what Mr. John Wilson says of its state about that time: "As our grandfathers saw it," says that gentleman, "the whole country, with the most trifling exceptions, was unenclosed,

¹ Both Mr. Howard Saunders, in vol. iv. of the revised and enlarged edition of Yarrell's *British Birds*, p. 358, and Mr. Seebohm, in his *British Birds*, vol. iii. p. 559, use Mallard as the English name of the Common Wild Duck. It is derived from the French word "Malart," which signifies the male of the Wild Duck.

² Writing in 1842, under dates July 2nd and 9th, Mr. Hardy says: "On a visit to west of Berwickshire and Lauderdale, the Wild Duck is becoming rarer and rarer on account of drainage."—*MS. Notes*.

there was scarcely such a thing as a plantation of trees; there was no artificial drainage, and the hollow parts were full of bogs, marshes, and stagnant pools.”¹ The late Dr. Henderson of Chirnside, an ardent lover of nature,² lamenting the changes which were taking place in his day, remarks that “burnies, too, maun a’ rin anither gate now frae what Nature intended; lochs, too, are a’ drained, Wild Ducks hae nae well-ees now to waddle in; ane can hardly get a bit dub for a channel-stane rink.”³

Notwithstanding these changes, however, the Mallard is still seen, although in comparatively small numbers, in every district of the county, where it haunts the rivers, streams, lakes, and ponds, many frequenting certain favourite retreats, such as Duns Castle Lake,⁴ the Hirsell Lake, and the lochs of Legerwood and Bemersyde. It is also found on the sea-coast from autumn until spring, as many as two hundred having been observed by Mr. Hardy in a flock at Greenhaugh on the 16th of November 1875. He remarks that—“In the night-time they resorted to the inland ponds, burns, and marshes, but in the morning returned to the sea, on that part of the coast most beset with rocks and protected by high cliffs.”⁵

Although many Wild Ducks breed in the county, there can be little doubt that the numbers of our native birds

¹ See *Report on the Agriculture of Scotland*, 1878, p. 23.

² I love the uncultured spot where Nature reveals free,
Some place left sacred to the flower and bee.

DR. HENDERSON, *Scenes of Boyhood*.

³ *Popular Rhymes of Berwickshire*, p. 83.

⁴ This lake has been long known as a resort of wild-fowl. Writing in 1792, the Rev. Robert Bowmaker, minister of Duns, says: “On the north and west [of Duns Castle] are several hundred acres of thriving planting, much of it very old. In the bosom of this plantation is a fine basin of water called the Hen Pond; it is above a mile in circumference, and in summer vast numbers of Wild Duck resort to it.”—*Old Statistical Account of Scotland*, vol. iv. p. 384.

⁵ *Hist. Ber. Nat. Club*, vol. vii. p. 486.

are augmented in autumn by migratory flocks from regions

Where the Northern Ocean in vast whirls
Boils round the naked, melancholy isles
Of further Thule,¹

to which they return in spring.

During severe weather in winter, when our lakes and ponds are frozen, Wild Ducks betake themselves to the Whitadder, Blackadder, Eye, Dye, Eden, and other streams, which keep comparatively free from ice, and also to the sea-coast. In ordinary weather at that season they are accustomed to rest on lakes, ponds, or the sea during the day-time; and at the twilight of the evening, which is known to the wild fowler as "flight-time," they fly off to the neighbouring marshes, small streams, and ditches to feed, returning in the early morning to their usual haunts for the day. In the evenings, towards the end of August and in September, great flocks often visit barley fields, where the corn is "laid," and devour large quantities of grain.² The usual food of the Wild Duck consists of seeds of various kinds, aquatic plants, worms, slugs, and insects. An example killed near Gordon in the severe winter of 1878-79, besides the roots and leaves of aquatic plants and a large number of the shells of *Pisidium pusillum*, had a quantity of *Sedum Acre* in its stomach.³

The Mallard is an early breeder, and generally has eggs in April; the nest, which is composed of dry grass and lined with down, is usually placed on the ground by the side of a

¹ Thomson, *Autumn*.

² Mr. Logan, late of Legerwood, informs me that they used to do considerable damage to his barley fields in the vicinity of the loch there, and that he has often shot numbers by waiting at the "darkening" near the "laid" spots. Mr. James Herriot says he has known large flocks visit the barley fields on Leetside Farm in the evenings, after the corn was cut. Mr. Black, Girrick, near Nenthorn, mentions that numbers frequent his barley fields and feed on the "laid" parts of the crops in the evenings just before harvest.

³ *Hist. Ber. Nat. Club*, vol. viii. p. 537.

pond, stream, or ditch, amongst rushes or other herbage, but it has been found in various abnormal situations, and even in a tree. One which I discovered by the side of the Whitadder on the 19th of April 1873 was on such a steep bank that the young would have considerable difficulty in reaching the water in safety. The eggs, which vary in number from eight to thirteen, are of a dull greenish-grey colour.

The young are not able to fly for about two months after they are hatched, and when nearly fledged are called "flappers." Mr. Blackadder, Blanerne, has informed me that flapper shooting at Billie Mire was a favourite sport of the inhabitants of Chirnside long ago, who "used to go over with their guns to the Mire in bands about the month of August, when the young Ducks were nearly ready to fly, and bring back loads of them."

The following entries with reference to flapper shooting appear in a diary kept by Captain Bell, of the Berwickshire Militia, in 1812-14 :—" 1814, *July 12th*.—Went to Blacksmill Burn and up above Dirrington Law for young Ducks. Got two young ones and two old ones. The young ones were rather small, few feathers being on the wing. *July 17th*.—Went to Swinton Mill and tried for Wild Ducks. Got four very fine ones and a Water Hen. Saw three or four more."

At the end of the breeding season a great change takes place in the colour of the Drake; he then appears in a dress like that of the Duck, though a little darker, and the quills being cast simultaneously, he is rendered incapable of flight; but by the middle of October he has again acquired his full plumage.

Wild Duck shooting is most enjoyable, and a fine old Drake in full plumage, besides being a very satisfactory mark, forms a desirable addition to the contents of a game

bag, and makes a very savoury dish for the table. The sport is frequently followed in the evening, when the Ducks fly in from the sea or from lakes to their feeding grounds, the sportsman concealing himself behind a hedge or tree in their usual line of flight, and killing them on the wing as they fly overhead. I have found that one of the most successful ways of shooting Wild Ducks is to go to their feeding places—such as marshy grounds, the sides of small streams, ditches, and the like—very early in the morning¹ before it is quite light, for they are then generally not so wary as usual, and allow the gunner to approach within range before they fly up. When severe frost occurs in winter, and snow covers the ground, Ducks are found on those parts of our rivers and small streams which keep free from ice, and if the fowler be provided with a suit of white linen to cover his clothes, and a white cap, they may be stalked with greater success than in ordinary shooting costume, for the white dress is not conspicuous when seen against a background of snow. I have frequently sat in the snow at dawn by the side of Langton Burn, near Wedderburn Castle, and shot Ducks as they came flying close past me, my white dress concealing me from their view. On the morning of the 9th of January 1879 I killed eleven Mallards in this manner in half an hour. As daylight approaches, and the sun rises on such occasions,

What pen or pencil shall presume to draw
The glowing scene—the rosy hue that paints
The glistening snow, the fiery gleams that flash
From crystal icicles, the rocks which deck,
Or hoary willow roots, and with a flood
Of brightest splendour light the river up!

¹ Mr. John Black, Girrick, Nenthorn, informs me that Wild Ducks frequent the Eden (which forms the western boundary of his farm) in great numbers. The numerous bends in the course of the stream are very favourable for stalking the Ducks, and he has killed as many as eight in a morning by walking up the side of the river and shooting them as they rose from the water at the angles of the stream. He has killed seventy in a season.

Now wand'ring by the river's winding side
 Its mazy course we trace, explore each creek,
 Islet, or shelter'd cave, the Wild Fowl's haunts.

REV. JOHN VINCENT, *Fowling*.

Several places in Berwickshire appear to have derived their names from the Wild Duck, amongst which may be mentioned Drakestruther, in Lauder parish; Drake Mire, a tract of marshy ground to the north of the Dog Bush Plantation, in Buncle parish; Wild Duck Ha', the old name of a place in Swinton parish, which, Mr. Hardy says, lay by the side of a moss near the Leet, where boys of a generation back used to gather Wild Ducks' eggs; and the Duck Ponds on the top of the moor at the highest point of the Black Hill above Dye Cottage, in Longformacus parish.¹

A popular saying sometimes heard in the county is that "Ducks and Geese drown at the wing."²

¹ Colonel Brown of Longformacus gave me this information.

² This has probably arisen from the fact that when a Duck or Goose is wounded in the wing while on the water, the feathers of the wounded wing get wet immediately, the bird having apparently lost the power of keeping them in such a position as to resist the action of the water.



THE SHOVELLER.

SPOON-BILL DUCK, BROAD BILL, SHOVEL BILL, BLUE-WINGED
SHOVELLER.

Spatula clypeata.

*The Schooler who so shakes the air with saily wings,
That even as he flies you still would think he sings.*

DRAYTON, *Polyolbion*.

THE Shoveller, which is so called from the broad expansion of its bill towards the tip, has not yet been shown to be more than a rare winter visitor to Berwickshire.

Mr. Allan of Peelwalls has informed me that a specimen in his possession was killed on Billie Mains mill pond about thirty years ago, and a male and female are said to have been shot at Legerwood Loch in the winter of 1870.¹ Mr. Hardy records that on the 25th of July 1872, Mr. Wilson, Coldingham, obtained an example from the mill pond at Fleurs near that village,² and the Rev. William Stobbs mentions that a pair were got near Gordon Moss.³ On the 25th of May 1886 Mr. James Aitchison, slater, Duns, showed me a male in fine plumage which had been obtained at the Hule Moss in the beginning of that month out of a flock of about twenty. Five Shovellers were observed on Duns Castle Lake on the 1st of December 1887 by Mr. William Smith, gamekeeper, who states that they are now seen there in small numbers nearly every winter.

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 147.

² *Ibid.* vol. vi. p. 431.

³ *Ibid.* vol. ix. p. 230.

Although this beautiful Duck is generally only a winter visitor to Scotland, it has been found breeding in various Scottish counties, including East-Lothian,¹ and also in Northumberland.

It is an excellent bird for the table. When it flies, the wings, which are moved rapidly, cause a peculiar sound, that may be heard at some distance.

¹ Yarrell's *British Birds*, fourth edition, vol. iv. p. 376.



THE PINTAIL DUCK.

PINTAIL TEAL, WINTER DUCK, SEA PHEASANT, CRACKER,
LADY-BIRD, HARLAN.

Dafila acuta.

*A flight of fowl
Scatter'd by winds and high tempestuous gusts.*

SHAKESPEARE, *Titus Andronicus*.

THIS elegant bird is occasionally seen as a winter visitor off the coast of Berwickshire, but it seldom ventures into the interior of the county.

Mr. John Weddell, Long Birgham, informs me that a specimen was shot on the Tweed there a few years ago, and Mr. William Smith, gamekeeper, tells me that a Pintail Drake has been seen on the lake at Duns Castle during the winter months for some years past. He saw it there last on the 28th of November 1889.



THE TEAL.

COMMON TEAL, GREEN-WINGED TEAL.

Querquedula crecca.

Teal Duck.

*Mourn Sooty Coots and Speckled Teals :
Ye Fisher Herons watching eels :
Ye Duck and Drake wi' airy wheels
Circling the lake.*

BURNS, *Elegy on Captain Matthew Henderson.*

THIS pretty little Duck is seen during the autumn, winter, and early spring months on most of the inland waters of the county, including streams and ponds. It is, generally speaking, a winter visitor, coming from the north in early autumn and returning there in spring, but a few remain in Berwickshire and breed during the summer in suitable spots, amongst which may be mentioned the bog on Greenlaw Common. It frequents the Langton Burn, in the neighbourhood of Wedderburn Castle in winter, while the pond at Wedderburn North Lodge was a favourite haunt before it was removed, as many as fifty having been occasionally seen there in a flock. Mr. Lockie says that it is found at Legerwood Loch and on the lake at Spottiswoode, and he mentions that it is common in the Earlstoun district, and breeds amongst reeds by the side of the Leader. Mr. Johnston, Felicleuch, near Ellemford, informs me that it resorts to the Whitadder there. According to Mr. Edington, it occurs in Lumsden Moss, and Mr. Hardy says it visits Townhead Mill Pond. When shooting with Mr. Clapham,

Broomhouse, on the 26th of November 1886, I saw several Teal rise from the Whitadder near Blanerne, and have sometimes observed them frequenting a small burn near Edrom Mains. This species is also occasionally noticed on the Tweed about Paxton and Milne Graden.

The Teal is the smallest of our Wild Ducks, and besides affording good sport with the gun, not being so wary as the Mallard, is excellent for the table. When rising from a stream it generally flies straight up into the air and requires quick shooting, as it is rapid on the wing.

In olden times it appears to have been a favourite quarry of the falconer, and we find it specially mentioned in an Act of the Scottish Parliament "against slaughter of Wild-fowles," 15th November 1600, James VI., 16, c. 23 — "Seing in tyme of peace in all tyme bygane, the saids pastymes of hunting and halking were the onely means and instruments to keepe the haille Leiges bodies fra not becoming altogether effeminat . . . they discharge any persons whatsomever, within this Realme in any wyse to sell or buy any fastan reid or fallowe Deare, Daes, Raes, Hares, Partridges, Moore-fowles, Black-cokes, Aith-hennes, Termigants, Wyld Dukes, Teilles, Atteilles, Goldings, Mortyms, Schidderems, Skaildraik, Herron, Butter, or any sik kynde of fowles, commonly used to be chased with Halkes, under the paine of ane hundreth pōunds, to be incurred alsweil by the buyer as the seller."

The nest of the Teal is usually found amongst rushes or other herbage by the side of a loch or pond, or in a bog or marsh remote from cultivation, and is composed of dead grasses and other plants, with a lining of down and feathers. The eggs are of a greenish cream colour, and vary in number from eight to fifteen. The food consists of water plants, grasses, and insects.

THE GARGANEY.

SUMMER TEAL, CRICKET TEAL, PIED WIGEON.

*Querquedula circia.**Strange fowl light upon neighbouring ponds.*SHAKESPEARE, *Cymbeline*.

THE Garganey, which is a little larger than the Teal and somewhat like it in appearance, has apparently been obtained only once in Berwickshire, a beautiful male having been shot by Mr. H. Hewat Craw on the mill pond at Foulden West Mains, on the 11th of March 1886. He has informed me that it was accompanied by another duck of the same kind, which may have been a female.

This species is a rare visitor to Scotland, but has occurred on migration in several counties. It winters in the south of Europe, and its breeding quarters extend as far north as Denmark, Sweden, and Russia.



THE WIGEON.

WHEW DUCK, PANDLE WHEW, YELLOW POLL, WHISTLER,
WHIM, BALD PATE, HALF DUCK, SMEE DUCK.

Mareca penelope.

*Who can recount what transmigrations there
Are annual made? What nations come and go?
And how the living clouds on clouds arise?
Infinite wings! till all the plume-dark air,
And rude resounding shore are one wild cry.*

THOMSON, *Autumn.*

THIS winter visitor is seen in flocks off the coast, and occasionally in small numbers on the ponds¹ and rivers in the interior of the county. It generally arrives from the north in October and leaves in March or the beginning of April.

Mr. Kelly records that a flock frequented an old water-run of the Leader, between New Mills ground and the haugh, from the beginning to the middle of October some years ago, and that the crop of one which was shot at Newbigging upper pond was full of the grass *Poa annua*.² He also mentions that the bird generally associates in Lauderdale with Mallard and Teal, from which it can easily be distinguished when flushed by the whiteness of its under parts and its more rapid flight.³ The Rev. W. Stobbs of Gordon, in some notes on the birds of that district, alludes

¹ Mr. William Smith, gamekeeper, Duns Castle, informs me that he observed fourteen Wigeon on the lake there on the 3rd of December 1889, and thirty-nine on the 11th of January 1890. He adds that considerable flocks frequent it in winter.

² *Hist. Ber. Nat. Club*, vol. vii. p. 523.

³ *Ibid.* vol. viii. p. 147.

to a specimen which was killed in Gordon Bog.¹ It has been occasionally observed on the Tweed at Paxton. Mr. Hardy relates that numbers have been obtained at the Cove Shore in winter. Small flocks of Wigeon sometimes visit the mill pond at Foulden New Mains, and Mr. Millican, the tenant of that farm, informed me on the 6th of November 1886 that some time previous to that date he had killed six out of a flock one morning. It has been occasionally observed on the Eden near Nenthorn during hard weather by Mr. Black, Girrick. Great numbers of Wigeon were formerly taken in decoy ponds, as many as 44,677 having been caught at the decoy of Steeple, in Canney Marsh, Essex, between 1714 and 1726,² and it affords more sport than any other duck to the wild-fowl shooter on the coast.


The food of this bird consists of grass, aquatic plants, and insects, and Mr. Waterton records that, unlike the Teal and Mallard, which obtain nearly the whole of their food during the night, it feeds in the day-time. It has a rapid flight and a whistling cry, and is a savoury dish for the table.

A few Wigeon nest in the shires of Ross, Sutherland, and Cromarty, and thence northwards.³

¹ *Ibid. Ber. Nat. Club*, vol. ix. p. 280.

² Yarrell's *British Birds*, fourth edition, vol. iv. p. 398.

³ Seebohm, *British Birds*, vol. iii. p. 539.



THE POCHARD.

DUN BIRD, DUNKER, POKER, RED-HEADED POKER, RED-EYED
POKER, GREAT-HEADED POKER.

Fuligula ferina.

*How silly the Wild Duck and Wigeon appear,
To be lured in decoy by the pranks of an ape!
But crafty the Pochard, which cunningly dives,
And beats under water a certain escape.*

FOLKARD.

THE Pochard is a winter visitor to the sea-coast and inland waters of Berwickshire from October until March or April, when it leaves for its breeding quarters. It is seen in considerable numbers off the shore, but only occasionally frequents the lakes, ponds, and rivers of the county, and then singly, or only in small flocks. The first notice of the Pochard in the *History of the Berwickshire Naturalists' Club* is in the presidential address of the Rev. Andrew Baird, minister of Cockburnspath, delivered at Duns on the 18th of September 1833, in which he states that at a meeting of the club held at Cockburnspath, on the 16th of April of that year, "Dr. Johnston mentioned that he had lately received from the Rev. Mr. Campbell a specimen of the Pochard Duck (*Anas ferina*, Linn.), shot near Coldingham Loch.¹

During severe winters the Pochard visits the Tweed and also the Whitadder, in the neighbourhood of Paxton. Several were killed on the former in the hard frost of

¹ *Hist. Ber. Nat. Club*, vol. i. p. 16.

1870-71, and I shot a beautiful male on the latter, near the Old Bound Road, in the end of December 1874. Mr. Kelly records that there are some specimens in local collections about Lauder which were procured in the vicinity of the Leader;¹ and Mr. Hardy mentions one which was shot on the Whitadder, above Cockburn, in January 1877.² Mr. Weddell, Long Birgham, writes to me that he has sometimes killed this duck on the Tweed in that neighbourhood; and Mr. H. H. Craw states that he has occasionally shot it on the mill pond at Foulden West Mains. The lake at Duns Castle, where wild-fowl of all kinds are carefully protected by the proprietor, W. J. Hay, Esq., is sometimes visited by the Pochard, a flock of seven having been observed there by the gamekeeper, Mr. William Smith, on the 27th of January 1887, and from twenty to thirty on the 17th of October of the same year.

Although the great majority of Pochards return to northern regions in spring, a few remain to breed in various parts of Britain, and Mr. Gray records that a nest has been found on the banks of a loch in Fifeshire.³

The subject of our notice is a wary bird, and when it enters the mouth of a decoy pipe with other wild-fowl it dives and escapes under water if any attempt be made to drive it further in along with them. For this reason it is taken on what is called a "flight pond," having nets at the sides so constructed that one of them can be raised by the fowler when the ducks are flushed, according to the direction in which they fly. A few of the leading Pochards are allowed to pass over the place where the net is concealed, and then it is suddenly raised up so as to intercept the great bulk of the flock, which strike against the net in their flight, and flutter down into a number of small pens con-

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 306.

² *Ibid.* vol. viii. p. 196.


³ *Ibid.* vol. ix. p. 386.

structed at the bottom, out of which they cannot readily escape, several hundreds being sometimes taken at once in this manner.¹

Pochards feed, when on fresh water, on aquatic plants, for which they dive, and they are then excellent for the table, being considered almost equal to the celebrated Canvas-back Duck of America. When at sea they subsist on molluscs and other marine creatures, and are not then well flavoured.

The head and upper neck of the male Pochard are rich chestnut. In the female these parts are buffish brown.

¹ See *The Wild Fowler*, by Folkard, second edition, 1864, pp. 82-94.



THE TUFTED DUCK.

BLACK DUCK, BLACK WIGEON, DOUCKER.

Fuligula cristata.

..... the feather'd tribes in close array
O'er the wide fields of ocean wing their way
When from the rage of winter they repair
To warmer suns and more indulgent air.

PITT.

THIS duck is occasionally seen off the coast, and on some of the inland waters of the county, during autumn, winter, and spring. It has been observed on the Tweed at Paxton, a male in full plumage having been shot there during the snow-storm of 1870-71.

Mr. John Aitchison, plasterer, Duns, informs me that a male was killed at Marchmont in the autumn of 1886. Mr. William Smith, gamekeeper, Duns Castle, informs me that he saw two on the lake there on the 3rd of November 1887, and four on the 10th of January 1890. Although the Tufted Duck is generally a winter visitor from northern regions and returns there in spring to breed, yet numbers remain and breed in various counties of England, including Northumberland. It has likewise been observed nesting in Perthshire,¹ and at Yetholm Loch in Roxburghshire.² It is a late breeder, incubation not taking place until May or the beginning of June.

It is an expert diver, and feeds on various aquatic plants and insects, but is not considered a good bird for the table.

¹ Yarrell's *British Birds*, fourth edition, vol. iv. p. 481.

² *Hist. Ber. Nat. Club*, vol. viii. p. 521.

THE SCAUP DUCK.¹

WHITE-FACED DUCK, SPOON-BILL DUCK, MUSSEL DUCK,
BLACK-HEADED DIVER.

Fuligula marila.

*It was the dreariest depth of winter-tide,
And on the ocean and its isles was felt
The iron sway of the North. Yea, even the fowl,
That through the polar summer months could see
A beauty in Spitsbergen's naked isles,
Or on the drifting icebergs seek a home,
Even they had fled, on southern wing, in search
Of less inclement shores.*

DELTA, *The Fowler.*

THE Scaup Duck is a winter visitor to the sea-coast, but is seldom seen on the inland waters of Berwickshire. When severe weather occurs, with snow and hard frost, it is occasionally seen on the Tweed near Paxton, where several were shot during the snow-storm of 1870-71, and again in December 1875.

It is an expert diver, and feeds principally on shell-fish and marine plants, and is not therefore a very palatable bird for the table.

The head, neck, and upper breast of the male are black, glossed with green, while the feathers round the base of the bill in the female are white.

¹ So named from its feeding amongst broken mussel and oyster shells ; called in the north "Scaup."—Swainson, *Provincial Names of British Birds*, 1885, p. 159.



THE GOLDEN-EYE.

GOLDEN - EYED GARROT, GOWDY DUCK, PIED WIGEON, WHITE-SIDE, GREY - HEADED DUCK, RATTLE - WINGS, WHISTLER, DIVING DUCK, DIVER OR DOUCKER, MORILLON.

*Fuligula clangula.**The Wigeon, The Sea Duck.**Clanging Golden-eye.*CRABBE, *Peter Grimes.*

ALTHOUGH numbers of Golden-eyes frequent the coast of Berwickshire, and a few are found on the larger rivers and inland waters¹ in the autumn, winter, and spring months, the adult male, in his beautiful black and white dress, is comparatively seldom noticed.² During the continuance of very severe weather in winter he may be occasionally observed on the Tweed, where females and immature males are then frequently seen swimming about the pools and diving in the streams.³

The Golden-eye is sometimes noticed on the Whitadder as far up as Abbey St. Bathans.⁴ Mr. Kelly says that he has not noticed it on the Leader.⁵

¹ Mr. W. Smith, gamekeeper, informs me that this duck sometimes frequents the lake at Duns Castle in winter. He saw two there on the 8th of February 1890.


² Mr. Hardy, writing on the 25th of February 1879, says: "About forty-two Golden-eyes seen in Siccar Bay—only two males in full plumage."

³ Mr. Cowe, Lochton, informed me on the 7th of August 1886 that an old male in full plumage was shot on the Tweed there in winter about 1872.

⁴ Mr. John Aitchison, plasterer, Duns, informs me that a female was shot at Ellemford on the 26th of November 1886.

⁵ *Hist. Ber. Nat. Club*, vol. vii. p. 523.

It arrives in the county from the north in autumn, and leaves in spring. It feeds on small fishes, shell-fish, and aquatic plants, which it obtains by diving, and is not an appetising dish for the table.



THE LONG-TAILED DUCK.

LONG-TAILED HARELD, NORTHERN HARELD, SHARP-TAILED DUCK,
CALLOO, COAL-AND-CANDLE-LIGHT, COL-CANDLEWICK,
COLDIE, MEALY-BIRD.

Harelda glacialis.

The Coal-and-Candle-Light Duck.

*Fowls by winter forced forsake the floods,
And wing their hasty flight to happier lands.*

DRAYTON.

THE Long-tailed Duck, which is an autumn and winter visitor, is seen in small flocks off the coast of Berwickshire, and sometimes singly or in pairs on the inland waters of the county, including the Tweed and the lake at Duns Castle. Mr. Hardy records that two were killed in the Harbour Loch, Coldingham Shore, in January 1860.¹ I shot a female on the Tweed at Finchy, near Paxton, in the end of December 1874. Mr. W. Smith, gamekeeper, Duns Castle, informs me that he noticed a Long-tailed Duck on the lake there on the 13th of January 1886.

Females and immature males are most frequently met with, the male in his beautiful adult plumage being comparatively seldom seen.

The food of this species consists chiefly of crustaceans, fish, and other marine creatures. Its flesh is coarse and unsavoury.

¹ *Hist. Ber. Nat. Club*, vol. iv. p. 211.

THE EIDER DUCK.

ST. CUTHBERT'S DUCK,¹ DUNTER GOOSE, GREAT BLACK AND
WHITE DUCK, DUSKY DUCK, CUD-DOO, CULVER DUCK.

Somateria mollissima.

The Cud-Doo, The Culbert,² The Dunter.

*With instinctive love is drest
The Eider's downy cradle, where
The mother bird her glossy breast
Devotes; and with maternal care
And plumeless bosom stems the toiling seas
That foam round the tempestuous Orcades.*

C. SMITH, *Studies of the Sea.*

DURING the autumn, winter, and spring months the Eider Duck frequents the coast of Berwickshire, usually in small numbers, though occasionally considerable flocks are observed. Mr. Hardy, Oldcambus, who, in his papers on the local migration of birds in the *History of the Berwickshire Naturalists' Club*, frequently notices the occurrence of this duck off the coast about Siccar Point from November to May, says: "They utter a noise like the cooing of a Pigeon, and the fishermen call them Cud-doo. They stay all the winter, but are seldom seen off here, and are said to breed in some of the rocks near Fast Castle. In earlier times they also nestled in a rough part of the bank near the Cove Harbour."³ Amongst many MS. notes on birds with which he

¹ So called from its nesting on the Farne Islands, once the abode of St. Cuthbert.


² This, says Mr. Hardy, is one of the coast names of the bird.

³ *Hist. Ber. Nat. Club*, vol. vii. p. 277.

has very kindly favoured me, the same gentleman mentions under date of the 25th of April 1885: "A male Eider brought by one of the salmon fishermen. It was a very fine specimen, and had been caught in one of the salmon nets. It seized everything that approached its bill, and watched its opportunity readily to inflict a wicked bite. A nest with young was found last year by the salmon-fishers on the west side of Fast Castle." On the 30th of June 1887, when passing "The Little Rooks," which are small rocky islets about half a mile to the west of Fast Castle, in a boat rowed by some of the salmon fishermen, they informed me that in the summer of 1885 several pairs of Eider Ducks nested in the vicinity, and that they had often tried to catch the ducklings, but without success. They said that they had observed a few birds of this species about that part of the coast in the first week of June 1887. A male was seen by me on the Tweed, near Paxton, in the end of December 1874, and Mr. W. Smith, gamekeeper, Duns Castle, informs me that he noticed two on the lake there on the 25th of January 1886. The Eider Duck breeds at the Farne Islands, and elsewhere on the coast of Northumberland. Its nest is generally composed of sea-weeds and dry grass, and as incubation proceeds it receives a lining of down plucked by the bird from her body. Seebohm says that "Eider-down is a highly prized article of commerce, and in some places, especially in Norway, Iceland, and Greenland, the birds are strictly protected for the profit they yield. By judiciously removing the eggs and down from the nests the birds are made to lay again, and furnish a fresh supply of the precious down. Each duck yields about four ounces of down, which, when cleaned, is worth about a sovereign a pound."¹ It requires

¹ *History of British Birds*, vol. iii. p. 620.

about a pound and a half to make a coverlet. The eggs vary in number from five to eight, and are greyish green in colour. The bird generally begins to lay about the middle of May. Its food consists chiefly of crustaceans and shell-fish.



THE COMMON SCOTER.

BLACK SCOTER, BLACK DUCK, SURF DUCK.


Edemia nigra.

On dit d'un homme sur lequel on ne peut compter: "Il ressemble à une macreuse; il n'est ni chair ni poisson."

FRENCH PROVERB.

THE Common Scoter is a winter visitor, which is seen in flocks off the coast of the county, but seldom on the inland waters. I have noticed it several times on the Tweed, at Paxton, during winter. Two specimens were observed on the lake at Duns Castle, by the gamekeeper there, on the 11th of March 1887, and the same number on the 25th of October following.

It feeds on shell-fish, which it obtains by diving, and its flesh has a strong fishy flavour; hence the French proverb quoted above. The plumage of the male is wholly black.



THE VELVET SCOTER.

WHITE-WINGED BLACK DUCK, GREAT BLACK DUCK,
DOUBLE SCOTER.

Edemia fusca.

*I gaze upon the stormy, troubled ocean,
I hear her crested waves,
Waking, as they roll with restless motion,
The echoes of her caves.*

WALTER CHISHOLM.

THIS species, which can easily be distinguished from the Common Scoter, by its larger size and the white bar across its wing, is occasionally seen off the coast of Berwickshire in the autumn, winter, and spring months, but is rarely observed in the interior of the county. Mr. Peter Cowe, Lochton, has informed me that a specimen was shot on the sea near Dow-law, in the parish of Coldingham, in 1860. A flock of ten Velvet Scoters was observed by the gamekeeper at Duns Castle, on the lake there, on the 7th of January 1886; and Mr. Hay of Duns kindly wrote to me on the 18th of April following that two were to be seen on the lake at the date of his letter.



THE GOOSANDER.

SAW BILL, DUN DIVER, JACK LAW, GREATER GOOSANDER.

Mergus merganser.

*The Gosander with them, my goodly fens do shew,
His head as ebon black, the rest as white as snow.*

DRAYTON.

THE Goosander is a visitor from the north, which is frequently seen during the winter and early spring months on the inland waters of Berwickshire, including the Tweed, Whitadder, and Leader,¹ when it is also observed on the sea-coast of the county. The adult male in full plumage, with his shining green head and rich pinkish cream-coloured breast, is one of the most beautiful of our water-fowl, but he is of much less frequent occurrence than immature birds of the same sex and females in their dull coloured coats.

This species is very destructive to fish, which it catches readily with its serrated bill. Mr. Brotherston, bird-stuffer, Kelso, writing on the effects of the severe winter of 1878-79, says: "Goosanders have been numerous and fat. Nearly every one I have dissected has been gorged with trout and parr in various stages of digestion, and measuring from three up to nine and a half inches in length."

Although the Goosander generally departs towards the end of March for its breeding quarters in the north of

¹ Mr. Kelly mentions St. Leonard's Cauld, on the Leader, as a well-known haunt of the Goosander.—*Hist. Ber. Nat. Club*, vol. vii. p. 305.

Europe, a few remain and nest in some parts of the Highlands, including the counties of Perth, Ross, Sutherland, Inverness, and Argyle. It usually makes its nest in the hollow of a tree, or under some kind of shelter. It subsists almost entirely upon fish, and its flesh is unpalatable.



THE SMEW.

PIED SMEW, SMEE DUCK, WHITE NUN, WHITE-HEADED
GOOSANDER, PIED DIVER, LOUGH DIVER,
VARE WIGEON.

Mergus albellus.

. *cautious water-fowl, from distant climes.*

WORDSWORTH.

THE Smew is a rare winter visitor to the coast of Berwickshire, and has been obtained only once in the interior of the county, a specimen in Kelso Museum having been killed at the Hirsell, near Coldstream.¹ An adult male in full plumage was shot at Eyemouth a few years previous to 1880, and is now in my possession, having been kindly presented to me by Mr. Evan Sanderson, Berwick-on-Tweed.

¹ Mr. Hardy's *M.S. Notes*.



THE RING DOVE.

WOOD PIGEON, CUSHAT, QUEST.

Columba palumbus.

Cushie, Cushie Doo.

'Twas summertide, the Cushat sang
 His am'rous roundelay,
 An' dew's like cluster'd diamonds hung
 On flow'r and leafy spray,
 The coverlet of gloamin' grey
 On everything was seen,
 When lads and lasses took their way
 To Polwart on the Green.

SONG, *Polwart on the Green.*¹

*The Cuschetts on the branches green,
 Full quietly they crowd.*²

ALEXANDER HUME.³

THE soft cooing of the Cushat is one of the many delightful sounds which are heard in our woods and groves in the spring and early summer months, and it falls soothingly on the ear whilst we listen to the rich and varied strains of the Blackbird and the Thrush. There is something peculiarly pleasing in the low melancholy note, which is suggestive of peace and rest.

Nor is her changeless plaint
 Unmusical, when with the general quire
 Of woodland harmony it softly blends.

GRAHAM.

¹ Written by John Grieve. See *Scottish Minstrel*, vol. v. p. 4.

² To coo like a dove.—Jamieson, *Scot. Dict.* "The kowsehot croudis and prykis on the ryse."—Gavin Douglas, 1513.

³ Alexander Hume, parson of Logie, was the second son of Patrick, 5th Baron of Polwarth, the lineal ancestor of the family of Marchmont. His poems were printed in 1599. He is supposed to have been born about 1550.—Sibbald's *Chron. Scot. Poetry*, iii. p. 367.

In the beautiful woods which adorn the banks of the Whitadder "the Ring Dove's deep melodious moan" can be heard to great perfection, and there, on a fine calm evening in early summer, it intermingles with the songs of many birds and the gentle murmur of the neighbouring stream.

So silent is the oessile air
That everie cry and call,
The hills and dailis and forest fair,
Againe repeats them all.

ALEXANDER HUMM.

The Cushat, like the Starling, has greatly increased in numbers within the memory of many people in the county.¹ This has probably been the result of various causes, amongst which may be suggested the widely extended cultivation of turnips and clover² since the end of last century, which supply it with food in winter and spring when little else is available, the planting of numerous fir woods for ornament and shelter throughout the county during the same period, which form a safe retreat where it can build its nest and rear its young in security, and the destruction of all kinds of birds of prey by gamekeepers.³

Numerous flocks of migrating Cushats come to Berwick-

¹ This had been observed by Mr. Hardy above forty years ago, for I find him writing under date the 12th of July 1844: "Wood Pigeons are greatly increased of late years on account of the number of young fir plantations which shelter them."—Mr. Hardy's *MS. Notes*.

² Lord Kaimes, about the year 1746, had turnip fields dressed and cattle fed with the produce at Kaimes, which were the first turnips sown in the county for the express purpose of feeding cattle. Clover and the artificial grasses were also sown in abundance at Kaimes, and at sundry other places about the year 1750. —*General View of the Agriculture of the County of Berwick*, by Alexander Low and Arthur Bruce, 1794, p. 106.

³ Although there are comparatively few Hawks to be seen in the county now, I often notice spots by the sides of woods and strips of plantation in autumn where they have plucked Cushats. The partiality of Hawks for Pigeons as a quarry seems to have attracted the notice of Horace, for in Book I. Ode xxxvii. he says, "*Accipiter velut molles columbas.*"

shire in the autumn and early winter months¹ from the northern parts of Europe, and finding food and shelter here, doubtless remain in some cases, and help to swell the ranks of our native birds. As an instance of this I may mention that, whilst many came to feed on the beech nuts in the woods at Paxton in October and November 1873, these, about the middle of the latter month, were augmented by vast numbers which passed up the valley of the Tweed from the direction of the sea at Berwick, arriving in the mornings and not being observed to return eastwards in the evenings. For about a fortnight during the same autumn hundreds continued to fly daily from the east over the Well Mire Wood, on the southern bank of the Whitadder, near the village of Paxton, and although many of them were shot, the reports of the guns did not seem to alter the line of flight taken by their successors.² Mr. John Wilson, late of Edington Mains, has informed me that thousands used to visit that farm in autumn, and that fishermen about Coldingham have occasionally seen immense numbers passing over the sea towards the Berwickshire coast.

The Cushat is strong and rapid on the wing, and when on a long journey flies high in the air. If suddenly frightened when passing overhead it sometimes makes a peculiar whistling sound with its wings, and this appears to have the effect of communicating the alarm to any others which may be in the neighbourhood. During the

¹ Between the 21st of October and the end of November 1884 there was an immense immigration of Cushats covering the East Coast between Berwick and Yarmouth. On the 29th of November 1885 a vast rush flying south-west in countless thousands was seen at the Isle of May. The noise they made was like a railway train.—*Reports on the Migration of Birds*, 1879-85.

² Another great migration of Cushats was observed at Paxton in the autumn of 1887. On the 26th of November in that year Mr. Compton-Lundie of Spital and I shot fifty-seven Pigeons in the course of a few hours as they passed over our heads towards the west. We were concealed behind a screen of fir branches set up against the west wall of the Wester Park at Paxton House, and we placed the dead birds on the grass in front of our ambush to act as decoys.

nesting season the gambols of the male as he rises and descends in his flight, or occasionally strikes the points of his wings together, is a pleasing sight, which is frequently witnessed on calm sunny evenings.

About 1859-60 this bird had increased to such an extent in the neighbouring county of East-Lothian¹ that it had to be constantly herded off the ripening wheat and barley fields by men or boys with guns. I have seen great numbers rise off patches of "laid" wheat in the vicinity of Salton, where the "Big Wood"² harboured thousands in its dark and unfrequented recesses. When feeding on growing grain the Pigeons usually come in pairs or in small flocks, and alight, in the first place, on some neighbouring hedgerow tree—such as an ash, willow, or plane—whence, after resting for a short time, they fly down to join any others which may be engaged in feeding on the adjacent parts of the field where the wheat or barley has been laid flat on the ground by heavy rain. A favourite way of shooting them used to be by making a small hut of green boughs underneath a tree frequented by the birds, and waiting in it with the gun ready to bring down the

¹ Mr. Archibald Hepburn, Whittingham Mains, East-Lothian, writing in 1847, draws attention to the fact that in the end of last century the Cusbat was a comparatively rare bird in that county. He says: "I am acquainted with a man, now sixty-five years of age, whose bird-nesting days were spent in the woods near Gifford, and he states that Wood Pigeons were then so rare that the discovery of a nest was looked upon as a great feat."—*Hist. Ber. Nat. Club*, vol. ii. p. 278.

² Sir Walter Scott mentions this wood in his description of the meeting of Lord Marmion and Sir David Lindesay of the Mount, Lord Lion King at Arms:—

The green sward way was smooth and good,
Through Humble's and through Saltoun's wood;
A forest glade, which, varying still,
Here gave a view of dale and hill,
There narrower closed, till overhead
A vaulted screen the branches made.

It appears from the *Accounts of the Lord High Treasurer of Scotland*, 1478-98, that the "Big Wood" supplied timber to make gun carriages in the time of King James IV. of Scotland: "Item, that samyn day (xxij. February 1496), gevin to Johne Mawar, zongare, to pas to Borthuik and Saltoun to vasy tymmyre for gun paraling, . . . ix. s."

Pigeons, which alighted amongst the branches overhead. It was advisable to allow the birds to settle for a short time before aim was taken, for they always looked well about them immediately after they perched, their sharp eyes quickly discovering any movement below, in which case they at once flew off in great alarm. They could also be shot on the wing as they approached or left the tree. I have sometimes killed twenty or thirty in the course of an hour or two in this manner; a quiet, sultry afternoon about the beginning of August being the most favourable time for success, as the Pigeons then came in extraordinary numbers to feed. They were obtained in the same manner in the spring months when they frequented the newly-sown fields to pick up the scattered grain, but as there were then no leaves on the trees or hedges to help to hide the shooter, his place of concealment had to be more closely constructed to screen his movements when taking aim. A few stuffed Cushats were used as decoys, and were placed on the "laid" wheat in the neighbourhood of the tree underneath which the shooter was hidden; or, in the case of newly-sown fields, within range of his retreat; and the birds which were killed were set on the ground near them, with their heads supported by small forked sticks, to make them look as if they were alive. These attracted Pigeons passing overhead so powerfully that it generally happened that they came down and alighted as soon as they saw them. I often observed that after settling beside the decoys, the visitors stood looking about them for a short time before commencing to feed; sometimes they walked up to the lures to make a closer inspection of them, and when this did not prove satisfactory they took alarm and flew away. On several occasions I have seen male Cushats attempting to pair with the stuffed decoys.

The destruction of crops by this voracious bird became

so great in Haddingtonshire shortly after 1860 that, in 1862, the United East-Lothian Agricultural Society offered a premium of one penny for each Cushat's head produced to the collector appointed for the district in which the bird was killed. This scheme was so successful that between December 1862 and June 1870 the heads of 130,440 were presented for payment.¹

An agricultural association was formed in the east of Berwickshire in 1875, and in January 1876 the members sent a memorial to the proprietors of land in the district to the effect that, considering the great damage done to the crops by the extraordinary and excessive numbers of Wood Pigeons in the county, they had resolved that means should be taken for their destruction, and for this purpose they invited the co-operation of the landowners. In 1877 the association offered a prize of £5 for the greatest number of Cushats killed, but there was no competition. In April 1878 the members decided to give a premium of one penny for each head, and one halfpenny for each egg produced to collectors appointed in various localities, with the result that during the year ending the 1st of April 1879, 2980 Wood Pigeons and 666 of their eggs were destroyed. Prizes for eggs were again offered by the association in 1885, but there was no response. In some instances men devoted their whole time, during certain seasons of the year, to the shooting of Cushats, travelling about the county from place to place, and taking up their quarters wherever they could make the heaviest bags. They sold the Pigeons which they killed at from fourpence to sixpence each, and thus made a livelihood.

The Pistol Plantation, on Blackadder Estate, which consists principally of lofty old Scotch and spruce fir-trees, is a favourite roosting place of this bird in the autumn months.

¹ Information kindly supplied by the Secretary to the Society.

Advantage is taken of this by sportsmen, who, in the evenings, stand with their guns under the trees in those parts of the wood which are most frequented by the Pigeons, and shoot them as they fly in to roost. A windy night is the most suitable for this kind of sport, when as many as seventy-two have been killed by one gun.

Besides consuming large quantities of ripening and newly-sown grain, such as wheat, barley, and oats, as well as beans, peas, and tares,¹ the Cushats likewise do much injury to young Swedish turnips in early summer by feeding on the leaves; and they also eat the "shaws"² and roots of turnips in hard weather in winter. It is believed that they do not break open the roots, their bills not being strong enough to do so, but that they feed upon those which have been already broken by hares, or by Rooks, whose sharp beaks penetrate the tough skin of the turnip with ease. They also do great damage to young grass and clover fields. A singular instance of voracity in this respect is mentioned by Mr. Hardy, who records that Mr. Wood, Foulden Bastle, shot a Wood Pigeon on his farm on the 7th of February 1872, and found in its crop upwards of 4200 clover leaves; and that in the previous year he got 3800 leaves from one which he had killed.³ During long-continued snow-storms Cushats are often put to great straits for food, and are frequently driven to visit

¹ Gray mentions, as an example of the extraordinary voracity of the Wood Pigeon, that Lord Haddington had forwarded to him the contents of the crops of four of these birds opened at different times. The first contained 144 field peas and 7 large beans; the second, 231 beech nuts; the third, 813 grains of barley; and the fourth, 874 grains of oats and 56 of barley. He likewise adds that a bird shot at Alyth, in Forfarshire, was found to have no less than 1020 grains of corn in its crop.—*Birds of the West of Scotland*, pp. 216, 217.

² Mr. Hardy, writing in 1860, says, under date January 27th: "The forester here (Penmanshiel), an Englishman, used to cook the turnip leaves found in Cushats' crops, and said they were tender and good to eat. This during snow-storms—snow a foot deep. Cushats very tame, going amongst turnips with raised-up backs and feathers dishevelled, picking out pieces of turnips."—*MS. Notes*.

³ *Hist. Ber. Nat. Olub*, vol. vi. p. 429.

gardens, where they do great damage to cabbages, broccoli, Brussels sprouts, and the like.¹

In May, when the tender foliage of the beech appears, the woods at Paxton were a few years ago annually visited by great numbers of Cushats, which fed on the newly-developed leaves of this ornamental tree, so that, in addition to the damage done by the Cushat to the crops of the farmer and the gardener, the forester has sometimes reason to complain of its misdeeds.

As a further instance of this it may be mentioned that at a meeting of the Berwickshire Naturalists' Club, held at Marchmont on the 27th of August 1879, Mr. Loney called attention to the topmost shoots of many of the spruce and silver firs there which had been broken by the weight of Pigeons which had perched upon them, and it was found that there were hundreds of trees in this condition.²

Although the Cushat, when its numbers become too great, is exceedingly destructive to the crops of the farmer, yet it does a certain amount of good by devouring the young leaves, seed pods, and seeds of several noxious weeds in the fields. Amongst these may be mentioned the wild mustard (*Sinapis arvensis*), the mother of wheat or speedwell (*Veronica hederæfolia*), the chickweed (*Stellaria media*), and *Cerastium viscosum*.³

In autumn, after the corn is gathered into the stackyard, it assembles in great flocks, and feeds on the scattered grain left in the stubble fields. It is then very shy and wary.

¹ Mr. Hardy, writing on the 27th of January 1880, mentions that Cushats have destroyed the broccoli in Dunglass garden.—*MS. Notes*. Dr. Stuart, Chirnside, in a paper on the effects of the winter of 1878-79, mentions, under date of the 16th of March 1879, that "Wood Pigeons came into the gardens in the middle of the village here, and, in front of the windows, ate the broccoli, Brussels sprouts, and other greens which they could get near."—*Hist. Ber. Nat. Club*, vol. ix. p. 184.

² *Hist. Ber. Nat. Club*, vol. ix. p. 48.

³ Mr. Hardy, writing under date of 26th July 1880, says: "I examined the crop of a young Cushat lying in Blackburnrig Wood, from which I had frightened a Hawk. It was crammed with the calices and capsules of *Cerastium viscosum*."—*MS. Notes*.

The Cushat begins to build in April, and continues to breed the whole season through until September, or even the beginning of October, August being a favourite month on account of the plentiful supply of food in the shape of ripening grain.

The well-known nest is constructed of small sticks and twigs, which are often so loosely put together that the eggs can be seen by a person looking up from below. In some instances, however, a new nest is constructed on the top of an old one, as in the illustration given below. Although the bird usually nests in fir woods and plantations at a distance from the habitations of men, yet it often throws aside its natural timidity and selects a situation close to a dwelling-house. Several pairs used to breed in the trees around my house at Paxton every year, and were then so tame that they allowed people to approach within a few yards of the branch upon which they were perched before they took to flight. It is thought that their motive in selecting a site for their nests near dwelling-houses is to avoid the danger of being robbed by Hooded Crows or Hawks. They likewise frequently rear their young in tall thorn hedges which surround corn-fields, a position in which I have often seen their nests in East-Lothian. The eggs are two in number, and pure white.¹

Any variation in the plumage of the Cushat is rare, but the occurrence of a white specimen at Lintlaw during the winter of 1874 is mentioned by Mr. John Anderson, Preston, who also states that "there was another for two or three years among the woods on the Marygold Hills, where it was a very conspicuous object when sitting on the top of a lofty spruce fir; but, unfortunately, in the spring of 1869 it was shot by a crow-herd." ² I have a pure white example in my

¹ Boys suck Cushats' eggs, which they think make them long-winded.

² *Hist. Ber. Nat. Club*, vol. vii. p. 515.

collection, which was killed near Kelso in March 1878,¹ and was kindly presented to me by Mr. W. C. Caverhill, Berwick-on-Tweed. With regard to the local folk-lore of the Cushat, Mr. Hardy writes: "It is said that Cushie Doos once laid their eggs on the ground, and that cows destroyed the eggs. They afterwards had recourse to trees, and cry from their security, 'Rookety, coo, coo, ye'll no win at me noo.'" He likewise relates that it is said "there was once a man called Barney who went out to steal a cow, and the Cushie Doos saw him and called to him, 'Barney, take two, two.' For their knavery they have cried that ever since."

¹ The young birds in their first plumage may easily be distinguished by their want of any white marks on the neck. The plumage of the Wood Pigeons which come on migration to the county from the north of Europe in the autumn and early winter months is in general darker and duller in hue than that of our home-bred birds.



THE STOCK DOVE.

WOOD DOVE, BLUE-BACKED DOVE.

Columba ænas.

*The Stock Dove builds her nest
Where the wild flower odours float.*

MACKAY, *Angling.*

IMMEDIATELY to the west of Paxton House, which stands on elevated ground on the north bank of the Tweed, there is a deep, rocky, wooded dean,¹ through which a small stream meanders; and there may be seen the remains of the "Old Heronry Wood," consisting of a few gigantic silver firs towering to a height of upwards of a hundred feet.

The opposing precipitous rocks almost meet at a narrow part of the defile, and, with the umbrageous trees above, form in summer a beautiful shady dell, whose sides are clothed with various kinds of ferns and wild flowers. At this season the little burn rippling over its stony bed is a favourite haunt of the Water Ouzel and the Grey Wagtail, whilst amongst the huge masses of fallen stone by its sides the Otter and the Fox find a secure retreat.

Here in the summer of 1877 the Stock Dove made its appearance. It was very shy, and rushed from its retreat with sounding wings in the greatest alarm whenever the place which it frequented was approached. The bird was again noticed in the spring and summer of the two following

¹ Here King Charles I. placed one of his outposts in May and June 1639, when he lay with an army of 16,000 men at the "Byrke Houses," a hamlet on the English side of the Tweed, opposite the village of Paxton, to overawe the Scottish Covenanters, who, under General Leslie, occupied the top of Duns Law.

years flying out from the south side of the ravine, but the exact spot from which it came was not determined until the summer of 1879, when it was seen to leave a rabbit hole, the mouth of which was almost entirely concealed by a large overhanging tuft of wood grass (*Luzula sylvatica*). On the burrow being examined a nest was found within a short distance of the mouth containing two white eggs, which were not disturbed. It has since nested there annually, as well as in the dean below the Avenue Bridge.

The late Mr. Robert Gray records that Mr. Charles Watson, solicitor, Duns, in a letter to him dated the 18th of April 1878, stated that a few months before he was shown a specimen of this bird which was shot in the woods of Duns Castle, and that the gamekeeper there had informed him that Stock Doves had bred there for several years.¹ Mr. Gray also mentions that a beautiful male of this species had been sent to him on the 12th of March 1879 by Mr. Watson, which had been shot on the previous day in the same woods.²

Mr. George Bolam, writing in the *History of the Berwickshire Naturalists' Club* regarding the Stock Dove, says: "I have to record what is, so far as I am aware, the first authenticated instance of the breeding of this bird in Scotland. On the 20th of April 1879, whilst walking on the steep banks on the north side of the Whitadder, a short way above Hutton Bridge, a Stock Dove flew out some little way below me, and on going down to the place I was agreeably surprised to find its nest, containing two eggs, a good deal incubated, placed a foot and a half down a rabbit hole. After watching the bird for some time, and satisfying myself that I had not mistaken the species, I removed the eggs, and they now form an interesting addition

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 364.

² *Ibid.* vol. viii. p. 499.

to my collection. On revisiting the place about six weeks later, namely, on the 3rd of June, in company with Mr. Muirhead of Paxton, we were not a little astonished to find that the nest contained two fine young ones almost fully feathered, and we again saw the old bird leave the hole."¹

Mr. Bolam states that, about the middle of April 1880, he discovered another nest with two eggs on the banks of the Whitadder, near Edrington, in a slight natural depression of the ground at the bottom of a whin bush, and sheltered by long grass, which, growing from both above and below, completely concealed it from view.²

Mr. Harvie-Brown mentions that in 1881 a bushy lime-tree in the grounds of Duns Castle, where the nest of this bird had been found, was pointed out to him by Mr. Wait, bird-stuffer, Duns.³

Dr. Stuart, Chirnside, has informed me that a Stock Dove had its nest in a rabbit hole in a terrace below Blackadder House in the spring of 1884; and Mr. John Thomson, Maxton, has written to me that "the bird is now (1886) pretty frequently met with at Mertoun, Dryburgh, Cowden Knowes, and Drygrange." Mr. Robert Campbell-Renton, yr. of Mordington, told me on the 5th of May 1887 that a pair had their nest that year in a thick silver fir near the stables there, and that the bird was becoming so plentiful about Mordington that he had killed ten or twelve specimens while shooting Wood Pigeons during the previous winter. On the 12th of May 1887 I saw a Stock Dove fly from its nest at the Raven's Craig, near Fellcleugh, on the Whitadder, thus showing that it has extended its breeding grounds towards the Lammermuir Hills.

This bird does not appear to have been observed in Scotland before 1874 or 1875, when it was seen in Perth-

¹ *Hist. Ber. Nat. Club*, vol. ix. pp. 165, 166.

² *Ibid.* vol. ix. p. 166.

³ *Proceedings of the Royal Physical Society*, 1881-83, p. 262.

shire.¹ Since then it has been gradually spreading and increasing in various counties. In Berwickshire it seems to be partial to the banks of rivers and streams, where it breeds in rabbit holes or under overhanging bushes.


In its habits this species bears considerable resemblance to the Wood Pigeon, feeding on the stubble fields in the autumn and the newly-sown fields in spring, like that well-known bird. It also eats the seeds of various weeds.²

The Stock Dove may be distinguished from the Cushat, even when on the wing, by its smaller size and the want of any white marks on the neck or wing coverts. It differs from the true Rock Dove in not having any white on the rump. Its note is not so sonorous or continuous as that of the Wood Pigeon. It nests in various situations, according to the locality, sometimes choosing a hollow tree, or the old nest of a Crow or Magpie, and frequently rabbit holes, or the ground under a whin or other thick bush. The eggs are two in number, and creamy white in colour.

It was formerly thought that the Stock Dove was the ancestor of our common dovecot Pigeon, and that it derived its name from this circumstance. It is now, however, believed that the Rock Dove is the progenitor of the domestic Pigeon, and that the Stock Dove got this name from building in the stocks of trees.

¹ *Proceedings of the Royal Physical Society*, 1881-83, p. 251.

² On the 14th of December 1887 as many as 1260 seeds of grub grass (*Galium aparine*) and two grains of barley were taken out of the crop of a specimen of this bird sent to me by Mr. Robert Campbell-Renton, yr. of Mordington, which he had shot there.



THE ROCK DOVE.

WILD PIGEON, ROCK PIGEON, WILD DOVE, DOO.

Columba livia.

The Doo.

*The Dow, with whistling wings sa. blew,
 The winds can fast collect;
 Her purpour pennies turnes merry haw,
 Against the sunne direct.*

ALEXANDER HUME, *Thanks for a Summer Day*, 1575-1590.

THIS interesting bird is found in considerable numbers in the caves which occur in several parts of the precipitous rocks on the sea-coast of the county, from Lamberton to Cockburnspath, and appears to be most abundant in the neighbourhood of St. Abb's Head.¹

Proceeding along the sea-coast from Lamberton, and passing Burnmouth, we find in the neighbourhood of Fairneside and Gunsgreen the "Dow Cave," so called on account of its having been long frequented by Pigeons. Leaving Eyemouth and the little fishing village of Coldingham Shore behind, we next come to a cavern at Kirkheugh,² where, as well as at the Caulderon or Piper's Cove, a short distance to the north, dwells a colony of Rock Doves. The Lighthouse is now reached, and we have before us the


¹ There are some Pigeons of various colours, such as sandy and white, which inhabit the caves frequented by the Rock Doves. The former are evidently either domestic Pigeons which have deserted their dovecot or have been bred from these. It may be conjectured that the majority of the blue Pigeons in the caverns are the descendants of the wild Rock Dove, which has inhabited the precipitous coast of Berwickshire from time immemorial.

² So named from its proximity to the site of the ancient kirk of St. Abb's, of which very little now remains.

lofty and precipitous rocks of St. Abb's Head. "This magnificent promontory," says Dr. Johnston, "is a huge insulated mass of trap rocks, whose seaward sides form precipices of vast height, hollowed in many places with caverns, in which the wild Pigeons (*Columba livia*) build their nests and nurture their young in safety amid the spray of waves that never sleep in rest. In some parts the caverns penetrate far and end in darkness; in others they are pervious, and give a romantic passage by another opening equally superb."¹ A little distance to the west of the Lighthouse is the Cleaver Rock, immediately to the west of which another retreat occurs. Rounding the Head, and just before we reach Petticowick Harbour, we come to another great fissure inhabited by Pigeons, with Guillemots on the rocks above its entrance. Mr. Hardy writes to me that further along the coast towards the west there are several resorts of this bird about the Gull Rocks, in the neighbourhood of Fast Castle, and again at the Rammel Cove, which is nearly opposite Dowlaw Mill Pond. He adds that it likewise nests at Windylaw Cove, which is towards the Redheugh Shore, at Siccar, and in the cave mouth at Swallowcraig, and at Greenheugh, near Oldcambus. When the mouth of one of these deep and dark caverns, moist with the spray of the thundering surge, is entered by a boat, the Pigeons dash out in great alarm, bringing to our remembrance the following beautiful and descriptive lines in Dryden's translation of Virgil:—

As when a Dove her rocky hold forsakes,
Roused in a fright her sounding wings she shakes,
The cavern rings with clattering, out she flies,
And leaves her callow care and cleaves the skies;
At first she flutters, but at length she springs
To smoother flight, and shoots upon her wings.

¹ Address to the members of the Berwickshire Naturalists' Club by George Johnston, M.D. (read at its first anniversary meeting held at Coldstream on the 19th of September 1832).—*Hist. Ber. Nat. Club*, vol. i. p. 5.



Sometimes sportsmen go round the coast in a boat to shoot the Pigeons as they fly out of the caves, frightening the birds off the rocky ledges inside by shouting, clapping the hands, or firing a shot at the entrance,¹ whereupon they rush over the heads of the intruders, and are then very difficult to bring down. When thus disturbed they generally pass close round the face of the precipitous rocks and make for some other neighbouring retreat. Their flight is strong and very rapid.²

This species commences to breed early in spring, and continues to do so at intervals until autumn. It makes a slight nest on the rocky ledges of the caves, and lays two white eggs. It often assembles in large flocks, which may be seen feeding in the fields near the sea; and in snowy weather in winter it visits stackyards in the neighbourhood of the coast to pick up grain. In July it feeds on the lea fields in great numbers, and also on the ground from which hay has been cut. The food consists chiefly of grain and the seeds of various weeds.

There can be little doubt that this bird formed the principal stock from which the common Pigeon of our dovecots was originally derived, although the latter is modified in its habits and varies much in colour. Even yet the domestic bird sometimes reverts to the wild life of its original ancestors, and forsakes its home for a cavern on

¹ When a gun is fired inside a Pigeon cave the reverberation is deafening.

² Mr. Tegetmeier states that the average rate at which the fastest Homing Pigeons flew in eighteen races, which took place in 1883, and which extended to the aggregate distance of 3189 miles, was 17·65 yards per second, 1059 yards per minute, or about 36 miles an hour. The greatest speed attained was 27 yards per second, 1620 yards per minute, or about 56 miles an hour for four hours in succession.—See *The Field* of 22nd January 1887. Mr. Griffith found by experiments with the chronograph that the very best "Blue Rocks" supplied by Mr. Hammond of the Hurlingham Club flew through a forty-yard covered range at the average rate of 14·3 yards per second, 858 yards per minute, or about 29½ miles per hour. In the open they flew at the rate of 13·15 yards per second, 789 yards per minute or about 27 miles an hour.—See *The Field* of 19th February 1887.

the sea-coast, or a rocky hold on the banks of the Tweed or Whitadder.

The dovecot Pigeon has from early times been under the protection of the law, and for the purpose of encouraging its increase in Scotland we find James IV., in his sixth parliament (11th March 1503), enacting that "everilk Lord and Laird, make them to have Parkes with Deare, stankes, cunninggares, dowcattes, orchardes, hedges, and plants, at the least, ane aicker of Woode."¹ In a confirmation by the same king, given at Stirling the 20th of July 1510, of a husbandland in "Hirsell" to the Prioress of the Cistercian convent of Coldstream, "cumbis" and "cumbarijs" are mentioned,² which shows that pigeon houses were then considered valuable adjuncts to landed property.

Thefts of "Dowes furth of Dowcates" were severely punished (James I., Parl. 2, c. 33; James III., Parl. 10, c. 60; James IV., Parl. 6, c. 69, &c.) A breaker of "dowcats" by Scots law was fined £10 Scots for the first fault, and £20 for the second, and it bears that for the third and obduracy "he may be hanged to death." When children were the culprits, the fathers or masters were to pay 13s. 4d. for "ilk time of trespas," or "else sall deliver the said childe to the Judge, to be leisched, scourged, and dung for his fault."³ It would seem that the enactment of James IV. with regard to the making of "dowcates" had been carried out too well, and that Pigeons became troublesome from their numbers in the reign of James VI., for he, "considering the great inconvenients sustained by the Leiges of this realm through the frequent building of dowcats

¹ *Laws and Acts of Parliament made by the Kings and Queen of Scotland.* Collected by Sir Thomas Murray of Glendook, Bart., 1681.

² *Chartulary of the Cistercian Abbey of Coldstream*, by Rev. C. Rodgers, LL.D., p. 56.

³ *Regiam Majestatem*, edition 1609. *The Forest Lawes*, fol. 139, b., chap. iii., Nos. 5 and 7.—Mr. Hardy's *M.S. Notes*.

by all manner of persons," passed an Act in 1617 to the effect that no person shall build a "doucate" unless he shall be possessed of lands yielding ten chalders of victual, lying around the said "doucate," or within two miles of it.

There is a farm near Fast Castle called Dowlaw, which has no doubt derived this name from the great number of Rock Doves frequenting the ground, the old spelling of the word in the Coldingham Session Records being Dovelaw.

Mr. Hardy informs me that a white Pigeon was supposed to be an emblem of innocence,¹ and was sometimes sent up in the air at executions by friends of the culprit as a sign of guiltlessness. An example of this took place at the execution of Grace Griffins, who was hanged at Berwick on the 26th of July 1823 for the murder of her husband, a white Pigeon being liberated above the crowd at the moment when the fatal bolt was withdrawn.

A popular saying sometimes heard in Berwickshire is that "a doo is the only bird without a ga'," ² which peculiarity is thus referred to by the poet Oldham:—

As if thou hadst unlearned the power to hate,
Or, like the Dove, were born without a gall.

A piece of Lauderdale folk-lore is that "Pigeons never breed when the pea blooms." Probably this may have had its foundation in the fact that they do not produce many young when their food is scarce, which is the case

¹ He mentions as instances of this that when St. Quentin was decapitated during the persecution of Domitian against the Christians, "a white Dove escaping from his neck ascended to the heavens" (*Proprium Sanctorum*, f. cxxxvi., ap. Brev. Alerd. t. ii.); also that it is related that a certain damsel, severely distempered, having been carried to the shrine of St. Ebba, at Coldingham, recovered after beholding a white Dove on the altar as a vision (*Proprium Sanctorum*, f. lxxxviii., ap. Brev. Alerd. t. ii.)—Mr. Hardy in letter dated the 15th of December 1886. For further instances see *Folk-Lore of British Birds*, p. 168.

² "The gall-bladder is wanting in Pigeons, in which, as in many other respects they differ from the gallinaceous birds."—Macgillivray, *History of British Birds* vol. i. p. 65.

about the end of June when the pea blooms, for then there is little grain in the stackyards or in the fields.

In the neighbourhood of Paxton I have sometimes heard the country people describe a frosty morning in spring, when rime is seen lying thickly on the ground, by saying that "everything is as white as a doo this morning." In some districts it is a popular belief that the return of Pigeons to their dovecots later in the evening than usual is a prognostication of rain on the following day.¹

Amongst some MS. Notes on Birds by the late Dr. Johnston of Berwick, kindly given to me by his daughter, Mrs. Barwell Carter, I find the following:—"A Pigeon or two is wont to stray occasionally from its dovecot and associate with the Rooks, and the boy who is sent to frighten away the latter from the newly-sown corn does his best to shoot the wanderer as a better prize and more worthy of his aim than the cawing crowd. Hence the saying common in the county when a young man has taken up with suspicious company, and is charged with an offence to which he pleads not guilty, 'An he hadna' taen up with the craws he wadna' been shot.'"

¹ Information from Mr. John Thomson, Maxton on the 3rd of May 1886.



THE TURTLE DOVE.

Turtur communis.

*The Turtour for hir maik,
Mair dule may nocht indure;
Nor I do for hir saik,
Evin hir quha hes in cure
My hairt, quhilk sal be sure.*

DARNLEY'S Ballat, 1542-1567.

THE Turtle Dove is rarely seen in Berwickshire. It, however, sometimes occurs in the county in autumn, probably on migration southwards from Denmark or Scandinavia, which appear to form its northern European breeding range.

An adult female, preserved in Berwick Museum, was shot near Edrington, on the Whitadder, on the 21st of October 1872,¹ and a young male was killed not far from the same place on the 19th of November 1874.² Another young male was obtained at Lamberton by Mr. James Mein on a very stormy day about the middle of September 1880. It was apparently much fatigued, and could not fly well.³

This species is a summer visitor to England and Wales, where it generally arrives about the beginning of May, departing southwards again in September. It is common in the midland and southern counties, but becomes rare in the north.

I have seen numbers of Turtle Doves in the neighbourhood of Remorantin, Loir-et-Cher, France, where they fed in the rye-fields, and built their nests in the birch-trees which overhung the tributaries of the river Sauldre. Their flight was very rapid and tortuous.


¹ *Hist. Ber. Nat. Club*, vol. vi. p. 434.

² *Ibid.* vol. vii. p. 236.

³ *Ibid.* vol. ix. p. 402.

Seebohm says that the winter quarters of this species are absolutely unknown, but as it passes through Northern Africa, and has not been found in South Africa, they must be in some region in the centre of that continent.¹

¹ Seebohm, *British Birds*, vol. ii. p. 412.



THE PASSENGER PIGEON.

Ectopistes migratorius.

*Now down through dismal swamps pursue your way,
Where pine and hemlocks thick obscure the day;
Whose mingled tops an hundred feet in air,
The clustering nests of swarming Pigeons bear.*

ALEXANDER WILSON.

ACCORDING to Mr. Howard Saunders, in his continuation of Professor Newton's edition of Yarrell's *British Birds*,¹ there are only five undoubted instances of the occurrence of the Passenger Pigeon in the British Islands. Of these a specimen in the collection of the late Lord Haddington at Mellerstain, shot by himself in the immediate vicinity of that place, forms the fourth. Lord Binning, in communicating to Dr. Turnbull a note of its occurrence at Mellerstain, adds: "The bird is, however, somewhat deprived of the interest which would otherwise attach to it, from the fact of a gentleman in Berwickshire having 'turned out' several Passenger Pigeons shortly before the Mellerstain specimen was shot. Presuming, however, that this was one of the birds 'turned out,' it is rather remarkable that, after their release, no other specimen was heard of as having been seen in our part of the country."² The date when the bird was shot is not given by Lord Binning, but in some MS. notes, kindly supplied to me by Mr. Hardy for use in this work, I find that the latter, writing under date 1857, says: "A Passenger Pigeon was killed at Mellerstain four years

¹ Vol. iii., 1882-84, p. 28.

² Turnbull's *Birds of East-Lothian*, 1867, p. 41.

ago, and when opened by Mr. Heckford,¹ who preserved it, the crop was full of beech nuts."

Audubon and Wilson, in their works on American Birds, give graphic accounts of the extraordinary migrations of the Passenger Pigeon, over which in boyhood I have often pored with delight.

Mr. Saunders says its food consists largely of the service berry (*Amelanchier alnifolia*), acorns, and beech mast, and that as soon as the supply becomes exhausted, the immense flocks suddenly disappear, and do not return for a long period.

It may be distinguished from our other Pigeons by its long wedge-shaped tail.

¹ Mr. G. S. Douglas of the *Chronicle* office, Kelso, writes to me under date 7th May 1887: "Mr. Heckford was a native of Blandford, Dorsetshire, and began life as a hairdresser. Mr. Douglas of Cavers was in that neighbourhood and took a fancy to Heckford, who was attending him (these were the days of perukes, &c.) After twenty-three years' service at Cavers, Heckford came to Kelso in 1827, and settled there. When the museum was founded he was appointed conservator, and performed his duties gratuitously as well as efficiently. His knowledge of taxidermy and natural history generally had been gained at the University of Edinburgh, which he had the opportunity of attending when the Cavers family were resident in that city during winter. He died on the 28th of February 1877, aged ninety years."



PALLAS'S SAND GROUSE.

THREE-TOED SAND GROUSE.

*Syrrhaptes paradoxus.**. The loveliest bird in Frangistan !*BYRON, *The Giaour.*

ON the morning of the 25th of May 1888 my friend Mr. William Evans telegraphed to me from Edinburgh that, as several pairs of Sand Grouse had been recently seen in the neighbourhood of Dunbar, the bird might be expected to make its appearance in Berwickshire. I mentioned this in Berwick Market to Mr. H. H. Craw, Foulden West Mains, on the afternoon of the same day, and asked him to be so good as to let me know if any specimens should be noticed in his neighbourhood. This he kindly undertook to do, and in the course of a few hours a messenger from him came to my house at Paxton with a cage containing a bird which had just been caught by a boy on his farm while engaged in rolling a field sown with barley. In the cage I found a beautiful live Sand Grouse in full plumage, and at once wrote to Mr. Craw suggesting that, to keep it alive, he should feed it on small seeds, and that he should present it to the Zoological Society of London. He accordingly forwarded the bird to Dr. Selater, whose address I supplied, and I had the pleasure of seeing it in the gardens of the Society in a thriving condition in the month of December following. It was a female, and when captured by the boy was so exhausted that it could not fly. It was said to have been one of a flock of twelve which visited the farm on the day mentioned.

The gamekeeper at Abbey St. Bathans informed me on the 17th of June 1888 that, in the previous week, several Sand Grouse were shot on Fannanside, near Godscroft, by Mr. John Moffat, Bankend; and on the 1st of July following, Mr. Millican, Harelaw, near Chirnside, told me that two specimens had recently been got at Whitfield, near Ayton. On the 9th of July 1888 the gamekeeper at Quirwood killed a fine male out of a flock of nine which were feeding in a field near the Retreat newly sown with rape and grass seeds. They were very wild, and rose at a distance of a hundred and fifty yards, but the bird which he secured remained sitting on the ground until he approached within thirty yards of it.¹ In the same month a specimen was procured from a flock of ten or twelve at Raecleughhead by Mr. Charles Marshall, Duns.² Flocks of Sand Grouse are said to have been seen also in the parishes of Hutton,³ Foulden,⁴ Chirnside,⁵ Coldingham,⁶ Longformacus,⁷ Cockburnspath,⁸ and Abbey St. Bathans⁹ in the months of June and July 1888.

This beautiful bird inhabits the sandy steppes of Asia in summer, from the eastern shore of the Caspian to Lake Baikal, migrating in winter to Mongolia and China.¹⁰ Its food in Scotland apparently consisted chiefly of the seeds of

¹ Information from Mr. John Hogg of Quirwood, 19th July 1888.

² Information from Mr. John Barrie, gamekeeper, Preston, 6th February 1892.

³ ⁴ Mr. Compton-Lundie of Spital observed a flock of twelve Sand Grouse passing over Spital House from south-east to north-west, about ninety feet high in the air, on the morning of the 9th of June 1888. They uttered a cry like the words "turook, turook."

⁵ Dr. Stuart, Chirnside.

⁶ Mr. W. Evans, in *Proceedings of the Royal Physical Society*, vol. x. p. 109. Also Mr. Bertram, Heughhead, 28th July 1888.

⁷ Colonel Brown of Longformacus saw a flock on a grass park near Longformacus House on the 1st of June 1888. Information given to me by him on the 25th of July following.

⁸ J. Hardy, *Hist. Ber. Nat. Club*, vol. xii. p. 188.

⁹ J. Shiels, gamekeeper, Abbey St. Bathans, 13th July 1888.

¹⁰ Saunders, *Manual of British Birds*, 1889.

various plants, such as spurrey (*Spergula arvensis*), knot-grass (*Arrhenatherum avenaceum*), clover, chickweed (*Stellaria media*), dock (*Rumex*), and the like.

Its flight is rapid, and resembles that of the Golden Plover. Great numbers visited the British Islands in May 1863, when several flocks were observed in East-Lothian; but by the following winter and spring the bird had disappeared from England as well as from Scotland.

Little further was heard of the Sand Grouse in this country until May 1888, when it was again seen in nearly every part of the kingdom.

Professor Newton records that it bred on the Culbin Sands, Morayshire, in August 1889.¹

An Act of Parliament was passed on the 24th of December 1888 for its protection from the 1st of February 1889 to the 1st of June 1892, with the view of the bird becoming acclimatised, but it has now (February 1892) quite disappeared from Great Britain.

¹ *Ibis* sixth series, vol. ii. pp. 211-214.



THE BLACK GROUSE.

BLACK-GAME, BLACK-COCK—THE MALE;

GREY HEN—THE FEMALE.

*Tetrao tetrix.***The Black-Cock, The Grey Hen.**

*The livelong day Lord Marmion rode:
 The mountain path the Palmer show'd,
 By glen and streamlet winded still,
 Where stunted birches hid the rill.
 They might not choose the lowland road,
 For the Merse forayers were abroad,
 Who, fired with hate and thirst of prey,
 Had scarcely failed to bar their way.
 Oft on the trampling band, from crown
 Of some tall cliff, the deer looked down;
 On wing of jet, from his repose
 In the deep heath, the Black-Cock rose.*

SCOTT, *Marmion*.

ALTHOUGH the great extension of cultivation during the last hundred years and the enclosing and draining of many parts of the moors and boggy grounds of the county have considerably reduced the area suitable for Black Grouse yet it is probable that, in certain localities, they are more plentiful than they were in the beginning of the present century, when shootings were not preserved, and birds of prey were unmolested by gamekeepers. In support of this conjecture I may state that in some extracts from a diary which was kept by Captain Bell of the Berwickshire Militia, from 1802 to 1826, kindly supplied to me by Mr. Hardy, I find that, between 1803 and 1814, he frequently shot over the moors at Kettleshiel, Bedshiel, Scarlaw, Longformacus, Monynut, Barnside, Godscroft, Quixwood, and Whit-

chester, and although he often makes mention of seeing and killing a few "Moor-fowl," he does not allude to any Black Grouse being observed or shot. In the neighbourhood of Lauder this bird does not appear to have been known before the early part of the present century, for Mr. Scott, late gamekeeper of Thirlestane Castle, informs me that he was told by an old dyker named Chisholm that about the time mentioned it was first seen in that locality at a place called Langshaw, about six miles south of Lauder. A specimen was shot at Woodhead Hill on Lord Lauderdale's estate some time afterwards, and the man who killed it had not seen a bird of the kind before. It was forwarded to the Earl, who was staying in London at the time, and who sent word that it was a Black-Cock. Mr. Kelly, in his *Account of some of the Birds of Lauderdale*, says: "Of the Berwickshire precincts of Lauderdale the Black-game does not appear to have been an acknowledged occupant till 1830."¹ These statements would seem to suggest that it was by no means a plentiful bird in the county long ago. Unfortunately, very little is said about the game, or birds generally, by the writers of the reports on the various parishes in Berwickshire, which are given in the *Old Statistical Account of Scotland* (1795), and not much more information on these subjects is supplied in the *New Statistical Account* (1835). This is to be regretted, for, if some notices of the wild animals and birds found in each parish had been given, they would now have been of great value for comparison with the fauna in the respective localities at the present time. One of the reporters in the *New Statistical Account*, who alludes to the various kinds of game in his parish, is the Rev. George Fulton Knight, minister of Mordington, who, writing in February 1835, states that the common varieties,

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 523.

“as Hare, Partridge, Black-Cock, Dotterel, and Wood-Cock, are plentiful.” The “Black-Cock” mentioned in Mr. Knight’s list then frequented Lamberton Moor, and continued to do so, as I have been informed by the proprietor of Mordington Estate, Major Campbell-Renton, for many years after the above date; they became extinct about 1870, when a Grey Hen was shot near Mordington House. There were none seen for some years afterwards in the neighbourhood, until the winter of 1882, when a Black-Cock and three Grey Hens appeared; but since then they have regularly bred every year on the moor in small numbers.¹

If a line be drawn on a map of Berwickshire from Coldingham Village to Earlstoun, it will divide the county into two halves of nearly equal size. The northern half is the district in which the Black Grouse is at present found in greater or less numbers, and includes the following parishes:—Abbey St. Bathans, Buncle, Channelkirk, Cockburnspath, Coldingham, Cranshaws, Duns, Earlstoun, Gordon, Greenlaw,² Langton, Polwarth, Legerwood, West-ruther, Lauder, and Longformacus. I have observed that this species is numerous in the neighbourhood of Cattle-shiel and Bedshiel, as many as eleven brace having been killed at the latter place in a day’s shooting in August about the year 1882 by the late Mr. Hume-Purves of Purves Hall.

The best bags of Black-game in the county are generally made on Spottiswoode Estate, concerning which the following notes have been kindly supplied to me by Mr. John Young, gamekeeper to Lady John Scott Spottiswoode

¹ The gamekeeper at Mordington informed me on 9th December 1887 that there were then fifteen Black Grouse on Lamberton Moor.

² Mr. W. Smith, head gamekeeper, Haddo House, Aberdeenshire, informed me on the 4th December 1891 that he once found as many as seven nests of this bird in a day while searching for Pheasants’ eggs in Foulshotlaw Wood, Berwickshire, in the end of April 1878, the nests being placed amongst dead Scotch fir branches.

of Spottiswoode, 1881, 17 brace; 1882, $34\frac{1}{2}$ brace; 1883, $20\frac{1}{2}$ brace; 1884, 32 brace; 1885, 38 brace; 1886, 24 brace; 1887, 13 brace; 1888, $15\frac{1}{2}$ brace; 1889, 22 brace; 1890, $6\frac{1}{2}$ brace; 1891, $25\frac{1}{2}$ brace; or in all, $248\frac{1}{2}$ brace in eleven seasons. The heaviest bag in one day was made on Flass Farm, on the 15th of September 1887, when 7 brace were killed. On the 16th of October 1887, 6 brace were got on Cattleshiel Farm.

The favourite haunts of this species are the lower slopes of the Lammermuirs, where fir plantations and thickets of birch, as well as stunted willow coverts, afford it shelter. In the early part of the shooting season the young birds are easily approached as they lie concealed in long heather, rushes, or ferns; but later, in autumn and winter, Black Grouse are very wild and wary, and will not allow the sportsman to come near them.

The principal food of this bird is heather; the seeds of rushes, and wild berries of various kinds are also eaten; while in autumn it visits the stubble fields on the skirts of the moors in search of barley and other grain. In winter it feeds upon the buds of the Scotch fir.¹

It is polygamous, and in spring, during the time of the "lek," severe fights take place between the rival males. The nest is generally placed on the ground under a low bush or tuft of heather, and contains from six to ten eggs of a yellowish white, speckled with reddish brown.

Amongst the prices of the various kinds of game fixed by the Scottish Parliament in the reign of Queen Mary (1551), those of the Black-Cock and Grey Hen are stated to be "sex pennies" the "peece."

¹ Mr. Smith, head gamekeeper, Haddo House, Aberdeenshire, says he has seen numbers feeding on Scotch fir buds at Kyleshill, and Backlea Woods near Polwarth, Berwickshire.

THE RED GROUSE.

MUIR-FOWL, MOOR-FOWL, MOOR-COCK, MOOR-HEN, GOR-COCK
RED GAME, RED PTARMIGAN.

Lagopus scoticus.

Muir-fowl, Muir-cock, Muir-hen.

*With earliest spring
. the Gor-cock's call
Is heard from out the mist, high on the hill;
But not till when the tiny heather bud
Appears, are struck the spring-time leagues of love.
Remote from shepherd's hut, or trampled fold,
The new joined pair their lowly mansion pitch,
Perhaps beneath the juniper's rough shoots;
Or castled on some plat of tufted heath,
Surrounded by a narrow sable moat
Of swampy moss.*

GRAHAME, *Birds of Scotland.*

ALTHOUGH the Red Grouse is indigenous to Berwickshire, the first notice of it which I can find with reference to this county is in Godscroft's *MS. History of the Homes of Wedderburn*, written in 1611, where that author, writing of his brother, Sir George Home of Wedderburn, who was born about 1550 and died in 1616, says: "He was very handsome and well-proportioned, and of great strength and swift of foot. He was a keen hunter, and delighted in hawking. He was so much given to that sport that he built a hunting lodge, called Handaxe Wood,¹ in the Lammermuir Hills, in which he often spent the night. He had Hawks called

¹ A locality in the neighbourhood of Byreclough.

Merlins and Falcons, and afterwards another kind called Tercells, which he delighted in even in his old age. He caught both Partridges and *Muir-fowl*."¹ Mr. Campbell-Swinton of Kimmerghame mentions, in the *Men of the Merse*,² that in a diary commenced by George Home of Kimmerghame in 1694, he finds the following entry referring to a day in June about the above date:—"To the setting at Kettleahiel, where the dog sett several times; but it was either an old fowl who rose before the net was ready, or young fowls that were scattered; so that there was none caught by the net but one old hen; but a hawk of Cavers took severals, and some were marked down where they sat and were taken."³ These references show that upwards of two hundred years ago the pursuit of Muir-fowl was, as now, considered to be excellent sport, and was enjoyed by gentlemen in the county.

In the *Old Statistical Account of Scotland*, which was written in 1795, Muir-fowl are mentioned in two of the reports on the parishes in Berwickshire. Thus the reporter on Legerwood parish says: "The tracts covered with heath are frequented by Muir-fowl, and the cornfields are haunted by Partridges. During the long-continued and intense severity of the year 1794-95 many of these wild animals perished with cold and hunger, and many in the extreme weakness to which they were reduced became an easy prey to whatever chose to pursue them."⁴ In the account of Abbey St. Bathans parish the writer says: "On the lands are plenty of Muir-fowl, Partridges, and Plover."⁵

In the early years of the present century, before the days of game preservation, Grouse seem to have been

¹ *MS. History of the Homes of Wedderburn*, 1611.

² Page 60.


³ The probability is that Red Grouse are here referred to, although the "old hen" may refer to Black Grouse.

⁴ *Old Statistical Account of Scotland*, vol. xvi. p. 486.

⁵ *Ibid.* vol. xii. p. 66.

very scarce on the Lammermuirs, for in a diary kept by Captain Bell of the Berwickshire Militia in 1812-14, I find the following entries:—"1812, Aug. 18th.—Went to the moors at Kettleshiel and Bedshiel from nine till after two o'clock. Saw only fourteen birds—did not get a shot. 1813, Aug. 12th.—From one to three o'clock tried the muirs of Scarlaw, and saw only a few birds, and they were very shy—got only one. Aug. 13th.—Tried the muirs at Longformacus—saw none; then Barnside, Godscroft, Monynut, Quickswood—saw very few, which were very shy. Got only one shot. 1814, Aug. 20th.—Tried the muirs of Kettleshiel and saw six birds, and did not get a shot. Sept. 10th.—Killed at Whitechester one muirfowl; a very long shot with No. 7."

In the *New Statistical Account* (1835) only one writer mentions Red Grouse as inhabiting his parish in Berwickshire—the Rev. Andrew Baird, minister of the united parishes of Cockburnspath and Oldcambus, who says that "it is tolerably abundant;" but this must be due to omission. The following is a list of the various parishes in the county where this bird is now to be found:—Abbey St. Bathans, Channelkirk, Cockburnspath, Coldingham, Cranshaws, Duns, Earlstoun, Gordon, Greenlaw, Langton, Lauder, Legerwood, Longformacus, Mordington, Oldhamstocks, Polwarth, and Westruther. It is considered to be very plentiful in the neighbourhood of Byrecleugh, the Duke of Roxburghe's shooting lodge, in the parish of Longformacus, and at Carfrae, in the parish of Channelkirk. As instances of the abundance of Grouse in these two localities, I may mention that Mr. James Smith, shepherd, Byrecleugh, told me in July 1886 that the Duke, about 1871, killed on the 13th of August, between nine A.M. and six P.M., 69 brace of Grouse to his own gun; and at a Grouse drive in 1885 his Grace shot 35 birds from one



"box."¹ Sir George Houston-Boswall, Bart. of Blackadder, informed me, on the 6th of September 1886, that when he was shooting with Lord Tweeddale near Carfrae Mill on the Lammermuirs on the 12th, 13th, and 14th of August in that year, the following bags of driven Grouse were got by a party of nine guns:—12th August, 161 brace;² 13th August, 85 brace; 14th August, 122 brace; in all, 368 brace. The 85 brace were got between Lammerlaw and Carfrae Mill. Colonel Brown of Longformacus tells me that very large bags of Grouse were got during the shooting season of 1872 on the whole of the Lammermuirs, the greatest number being obtained on the Byrecleugh ground, where over 700 brace were shot in a fortnight by three guns.

On the 12th of August 1882, Mr. George Turnbull of Abbey St. Bathans, Lord Low, and another gentleman, whilst shooting on Ellemford moors, bagged $27\frac{1}{2}$ brace of Grouse; on the 12th of August 1889, 20 brace; and on the 12th of August 1891, $20\frac{1}{2}$ brace; all killed over dogs. On the 25th of November 1887, 21 brace were got there by Mr. George Turnbull, Mr. Hunter of Thurston, Mr. John Miller, Manderston, Mr. Brooks, Oxenden Tower, and Mr. George Muirhead, Paxton, the birds being driven over the guns. These moors have long been celebrated as a favourite resort of Grouse, and as early as 1639 we find David Hume in his *Poemata Omnia*³ thus referring to them:—

¹ The following note appeared in the *Berwickshire News* of the 13th of September 1888:—"On the Byrecleugh moors a party consisting of the Duke of Roxburghe, the Marquis of Bowmont, Lord Kensington, and Lieutenant-Colonel Brown of Longformacus, have bagged 450 brace of Grouse. Birds reported to be strong and plentiful."

² Colonel Brown says this is the largest bag of Grouse ever killed on the Lammermuirs in one day, and, with the exception of 1872, the season of 1886 was the best for Grouse on these hills in his experience.

³ *Davidis Humii, Wedderburnensis, Poemata Omnia, Parisiis, 1639.*

Collis erat modico tollens fastigio olivo
 Miscet ubi Albenti¹ se Dius² hospes aquas
 Gleba uber : Cererisque coma formosus ; et umbra
 Arborea : et Floræ numine amœnus ager.
 Fons saliens sole a medio declivis ad ortum
 Illimes leni murmure volvit aquas,
 Hinc densæ circum salices, corylique, rubique
 Alitibus fidum perfugiumque feris.
 Dives ager late ad dextram perdicibus illis,
 Quas humilis tenui nutrit Erica coma.
 Hic me seu casu, seu jam tibi amica, Cupido,
 Clam tulit in casses flava Diana tuas
 Incautum, dum sector ; et in fruticeta paventes
 Specto agat ut pennâ præpete Nisus aves.

ELEGIA III.

A short distance to the north of Ellemford lies David Hume's patrimonial estate of Godscroft,³ in the parish of Abbey St. Bathans. Quixwood adjoins Godscroft, and here, on the 13th of August 1889, Mr. Hogg and party (five guns) got 28 brace, and two years later, on the 12th, 26 brace. On Spottiswoode estate 23 brace were killed on Flass moor on the 14th of August 1886 (two guns); 24 brace on the 15th of August 1888 (two guns); and 25½ brace on Cattleshiel ground on the 12th of August 1889 (two guns). The total bags of Grouse got on this property were—in 1881, 73½ brace; 1882, 91 brace; 1883, 96½ brace; 1884, 64½ brace; 1885, 124 brace;

¹ Fluvius inter Lammyrios montes, vulgo Whytwater dictus.

² Alius fluvius vulgo Daye dictus, in Albentum fluvium influens.

[TRANSLATION.]

There was a hill rising to a point with a moderate slope where the tributary, the Daye, mixes itself with the Whytwater—of fruitful soil—and beautiful with corn ; and a leafy shade : and a field pleasant to the Goddess of Flowers. A fountain bubbling from the middle of the earth rolls its clear waters with gentle murmur, sloping towards the east.

Around this place are dense willows, hazel-trees, and brambles ; and a safe refuge for wild birds : a field stretching towards the right rich in those partridges which the dwarfish heather nourishes in her tender hair. Here golden-haired Diana secretly drove me unawares, either by chance, or already friendly to thee, O Cupid, into thy nets : while I follow : and I see how the sparrow-hawk with swift wing drives the frightened birds into the thicket.

³ While shooting over the small moor belonging to this ancient property on the 12th of August 1873, I bagged 10½ brace of Grouse.

1886, 162½ brace; 1887, 30 brace (owing to disease); 1888, 159½ brace; 1889, 150 brace; 1890, 179 brace; 1891, 178 brace; or in all, 1238½ brace in eleven years, no attempt having been made to secure large bags.¹

Since 1838, when the Grouse disease first attracted attention, the Lammermuirs have been repeatedly visited by this scourge, the most destruction being caused by the epidemics of 1867 and 1872. In the winter of the latter year the birds were nearly exterminated by the disease, which commenced in December, although they were exceedingly plentiful during the previous autumn. It appeared again in the spring of 1887 at Byrecleugh and other localities, when many dead birds were found on the moors. Like the salmon disease, which for a number of years past has destroyed thousands of fish in the Tweed and other rivers, the Grouse disease has been studied by many naturalists, scientific men, and sportsmen, who do not seem, however, to have arrived at any definite conclusion as to its cause or cure.

The Red Grouse is an early breeder, making its nest with a little dry grass and a few feathers amongst the heather, and laying from eight to twelve eggs of a whitish ground colour closely blotched with dark brown and red. The hen alone attends to the hatching of the eggs, and

. Sits, till, with redoubled joy,
Around her she beholds an active brood
Run to and fro, or through her covering wings
Their downy heads look out; and much she loves
To pluck the heather crops, not for herself,
But for their little bills.

GRAHAME, *Birds of Scotland*.

The chicks are generally seen running about the heather on the Lammermuirs for the first time in the season

¹ Information kindly supplied by Mr. John Young, gamekeeper to Lady John Scott-Spottiswoode of Spottiswoode, 23rd December 1891.

about the end of May or beginning of June.¹ The "Kok, kok, kok" of the male when he is alarmed, and his morning cry, as well as the sudden spring of the covey from the heather, are familiar sounds and sights in the Lammermuirs which attract the attention of visitors from the Merse. Besides the young shoots of the heather² and the leaves and fruit of various wild plants, such as crowberries (*Empetrum nigrum*), and blaberries (*Vaccinium myrtillus*), the Red Grouse visits oatfields in the neighbourhood of the moors to feed on the stooks, and to search the stubble for fallen grain. When heavy snow lies on the hills it often descends in numbers to the lower ground for food and shelter. During severe weather in winter many frequent the grass parks at Longformacus.³ The plumage of this bird varies considerably, and an albino, or one variegated with white, is sometimes seen. A white Grouse was shot at Byrecleugh in 1885,⁴ and two were seen on Wedderlie Farm in 1887.⁵

The indiscriminate burning of heather is so very injurious to Red Grouse that at various times Parliament has passed Acts on the subject.

So long ago as 1401 the Scottish Parliament⁶ made a statute "to be observed through the whole realm that there should be no muir-burning or burning of heath, except in

¹ Mr. Hardy in his *MS. Notes*, under date 29th June 1844, says: "Moor-fowl led dog far away from her young by flying and alighting and fluttering, till, at a great distance,

O'er the rough moss, and o'er the trackless waste,
The heath hen flutters, pious fraud! to lead
The hot-pursuing spaniel far astray."

THOMSON, *Spring*.

² In the crop of a Grouse which was shot in a drive at Abbey St. Bathans on the 25th of November 1887, I found no fewer than 6000 pieces of the top shoots of heather, which, when dried, weighed 818 grains, and filled three ordinary sherry glasses.

³ ⁴ Information from Colonel Brown.

⁵ Information from Mr. Clay, Kerchesters.

⁶ In the list of the prices of game fixed by the Scottish Parliament in the reign of Queen Mary (1551), "small mure fowle" stand at "four pennies."

the month of March, and that a penalty of 40 shillings should be imposed upon any one who dared to contravene this regulation, which should be given to the lord of the land where the burning had place."¹ By the Act of George III., which is at present in force, every person who shall set fire to any heath, from the 11th of April to the 1st of November, shall forfeit £2 for the first offence, £5 for the second, and £10 for the third; or, in default of payment, six weeks', two months', or three months' imprisonment respectively. The annual burning of the heather on the Lammermuirs in spring is a sight which I remember seeing as a boy in East-Lothian, where the long straggling fires by night, and the clouds of smoke by day,² reminded one of Leyden's graphic description:—

How grand the scene yon russet down displays,
While far the withering heaths with moor-burn blaze!
The pillar'd smoke ascends with ashen gleam;
Aloft in air the arching flashes stream;
With rushing, crackling noise the flames aspire,
And roll one deluge of devouring fire;
The timid flocks shrink from the smoky heat,
Their pasture leave, and in confusion bleat,
With curious look the flaming billows scan,
As whirling gales the red combustion fan.

Mr. Hardy says: "It is a popular belief that when Moor-fowl call near houses in moorland places much rain may be expected, and that the cocks make an oft-repeated "Kick-dick, dick, dick," before rain."³

¹ Tytler's *Scotland*, vol. iii. p. 110.

² In East-Lothian heather-burning was supposed to bring rain. According to Dr. Johnston of Berwick this belief was also prevalent in Berwickshire.—*Bot. East. Borders*, p. 187.

³ *M.S. Notes*.



THE PHEASANT.

COMMON PHEASANT, RING-NECKED PHEASANT, BOHEMIAN
PHEASANT.

Phasianus colchicus.

The Faisan.

*See from the brake the whirring Pheasant springs,
And mounts exulting on triumphant wings,
Short is his joy; he feels the fiery wound,
Flutters in blood, and, panting, beats the ground.*

POPE.

THE earliest record of the occurrence of the Pheasant in Great Britain is in a bill of fare drawn up by Harold in 1059.¹ It is first mentioned in Scottish Acts of Parliament in 1594, when it was "ordained, that quwhat-sum-ever person or persones, at onie time heirafter, sall happen to slay deir, harts, phesants, fouls, partricks, or uther wild-foull quwhat-sum-ever, ather with gun, croce-bow, hand-bow, dogges, halkes, or girnes, or be uther ingine quhat-sum-ever," in the King's "haill Wooddes, Forrests, Parkes, Hanynges," without His Majesty's special permission, "their haill guddes and gear sall be escheit and inbrocht to his Hienes use, and their persons punished at his Hienes will."

Although, from the above Act of Parliament, it would appear that this bird was to be found in Scotland in 1594, it does not seem to have been introduced into Berwick-

¹ Yarrell's *British Birds*, fourth edition, vol. iii. pp. 94, 95.

shire for more than two hundred years afterwards; and there is apparently no record of its occurrence in the county previous to 1810, in which year, according to an old game-book kept at the Hirsell, one Pheasant was killed there. The Hon. H. R. Scott, who has kindly furnished me with notes from the above game-book, adds that "in 1816 there is an entry by Lord Home that in shooting the covers on the Hirsell he saw only five or six Pheasants, where, the previous year, he had seen thirty brace." Writing in 1834, the Rev. George Cunningham, minister of Dunse parish, says: "Pheasants were introduced into the woods of Dunse Castle about twenty years ago, and abound there, and in the neighbouring plantations."¹ Mr. Peter Scott, Lauder, whose father was for many years gamekeeper at Thirlestane Castle, has informed me that they were first turned out into the coverts there in the time of James, the 8th Earl of Lauderdale, who had taken into his employment a gamekeeper named Robert Fortune, from Salton Hall, or Whittingham, in East-Lothian. Fortune visited Whittingham, or Lochend, where he procured a supply of the eggs of this species, from which young birds were reared and set at liberty in the policy woods of Thirlestane Castle. Mr. Scott likewise told me that Pheasants were kept at Spottiswoode a year or two previous to their introduction to Lauderdale, but were confined in an enclosure. In 1821 they appear to have been still found in rather small numbers at the Hirsell, for in Captain Bell's diary I find an entry dated the 19th of October of that year: "Was at Hirsell shooting, and killed three Pheasants and three hares."² The Rev. George Knight, minister of Mordington parish, mentions in 1835 that

¹ *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 251.

² Excerpt from diary kept by Captain Bell of the Berwickshire Militia, from 1802 to 1826.

"brown and silver Pheasants are occasionally found in the woods of Edrington."¹

Most of the landed proprietors in the county appear to have begun to preserve this beautiful game bird in their policy grounds and woods before the middle of the nineteenth century; and on properties where there is much cover shooting great numbers of Pheasants are now artificially reared every season, to form an addition to those which are hatched in the plantations and hedge-rows.

In former times when the birds were scarce, setters or spaniels were used to find them, but now they are generally driven out of the covers by men and boys, and forced to fly as high as possible over the sportsmen, who are conveniently placed to intercept them.

Some writers have decried Pheasant shooting as unmanly, owing to the alleged tameness of the birds; but in November and December, when they have become wild, and strong on the wing, great skill is required to bring them down as they pass like rockets high overhead in the air.² This they invariably do if the covers are properly driven, and the guns are posted at a suitable distance from the side of the wood out of which the birds suddenly spring and mount rapidly in the air to escape from the beaters.

The following records of some of the best bags of Pheasants got in various parts of Berwickshire have been kindly supplied to me by correspondents in the respective parishes mentioned; and I take this opportunity of thanking them for their notes, which will doubtless be of interest to sportsmen in the county, not only now, but in years to come.

¹ *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 840.

² See sketch, "As high as ever you saw them," in *Field and Covert Shooting*. Badminton Library, second edition, 1887, p. 194.

Parish.	Estate.	Proprietor.	Cover.	Guns.	Date.	Pheasants bagged.	Correspondent.
Ayton.	Ayton Castle.	Alex. Harold Mitchell-Innes, Esq. of Ayton and Whitehall.	Ayton Castle Woods.	Seven. Regd. Pringle, Esq.; John Miller, Esq.; — Barclay, Esq.; R. Campbell-Renton, Esq.; Major Brook; G. Muirhead, Esq.	1866. Nov. 22.	182.	Mr. Hugh Fraser, gamekeeper, Kelloe, formerly head gamekeeper to the late Alex. Mitchell-Innes, Esq. of Ayton and Whitehall.
			Whitfield Woods.		1876. Nov. 18.	111.	
			Ayton Castle Woods.		1875. Nov. 16.	166.	
					1888. Nov. 13.	93.	
Chirnside.	Whitehall.	Alex. Harold Mitchell-Innes, Esq. of Ayton and Whitehall.	Harelaw, West-heads, and Pearbank.	Hon. Edward Marjoribanks, M.P.; Lord Curzon; H. Gladstone, Esq.; Captain Tippings; — Guest, Esq.	1891. Nov. 6.	91.	Mr. Thos. W. Walker, gamekeeper to the Hon. Edward Marjoribanks, M.P., at Edington Hill.
Coldstream.	Milne Graden.	David Milne-Horne, Esq. of Milne Graden.	Milne Graden Woods.	Hon. Henry Scott; Col. Milne-Horne; Captain Forbes, R.N.; Captain Ramsay; James Hunter, Esq.; George Muirhead, Esq. Admiral Hotham; Captain the Hon. Henry Baillie-Hamilton, R.N.; Capt. Forbes, R.N.; Jas. Hunter, Esq.; G. Muirhead, Esq.	1887. Oct. 6.	54.	
					1888. Oct. 10.	65.	
Duns.	Manders-ton.	Sir James Miller, Bart. of Manders-ton.	Manders-ton Woods.	Eight.	1890. Dec. 3.	103.	Mr. Jas. Smith, gamekeeper, Manders-ton.
	Do.	Do.	Do.	Eight.	Dec. 4.	233.	Do.
	Do.	Do.	Do.	Seven.	1891. Dec. 3.	122.	Do.
	Do.	Do.	Do.	Eight.	Dec. 9.	339.	Do.
	Duns Castle.	W. J. Hay, Esq.	Duns Law and Braid-fern Woods.	One.	1887. Oct. 17.	45.	Mr. W. Smith, gamekeeper, Duns Castle.
	Wedderburn.	Col. Milne-Horne.	Polley Woods.	Six. Five.	1882. Nov. 3. Dec. 7.	66. 83.	Mr. R. Bruce, late gamekeeper to E. F. Laubour, Esq.
			Do.	W. Compton-Lundie, Esq.; S. Hull, Esq.; G. Muirhead, Esq.	1887. Nov. 3.	14.	

Parish.	Estate.	Proprietor.	Cover.	Guns.	Date.	Pheasants bagged.	Correspondent.
Harlston.	Mellerstain.	Earl of Haddington.	Mellerstain Woods.	Four.		120.	Mr. James M'Pherson, gamekeeper, Mellerstain.
Roche.	Lees.	G. F. Marjoribanks, Esq.	Ferneyrig Covers.	Four.	1890. Nov. 21.	101.	Mr. G. Landels, gamekeeper, Ferneyrig.
Edrom.	Broom-house.	Capt. Logan Home of Broom-house.	Broom-house Woods.	E. Clapham, Esq.; W. Compton-Lundie, Esq.; S. Hull, Esq.; G. Muirhead, Esq.	1887. Nov. 1.	75.	Mr. John Nisbet, gamekeeper to the late Mrs. Brown of Longformacna, at Nisbet House.
			Do. †	E. Clapham, Esq.; W. Stone, Esq.; G. Muirhead, Esq.	1896. Nov. 26.	46.	
	Nisbet.	Lord Sinclair of Herdmanston.	Nisbet House Covers.	Four.	1887. Nov. 5.	23.	
	Blackadder.	Sir George Houston-Boswall, Bart.	Blackadder Woods.	Three.	1890. Nov. 15.	14.	
Fogo.	Charterhall.	Col. Trotter of Charterhall.			1891. Dec. — (one day's shooting.)	210.	Mr. Wm. Thomson, gamekeeper, Charterhall.
			Fogomoor Wood.	Five.	1889. Nov. 16.	127.	
			Big Wood.	Five.	Nov. 23.	52.	
			Fogomoor.	Five.	1890. Nov. 19.	98.	
			Big Wood.	Four.	Dec. 3.	52.	
			Do.	Four.	1891. Jan. 3.	45.	
Hutton.	Paxton.	Col. Milne. Home of Wedderburn, &c.					
			Paxton Covers.	R. Pringle, Esq.; George Turnbull, Esq.; W. Compton-Lundie, Esq.; G. Muirhead, Esq.; E. Clapham, Esq.	1887. Oct. 24.	33.	
				W. Compton-Lundie, Esq.; Captain Godfrey; G. Muirhead, Esq.	1887. Nov. 15.	22.	
				Captain Richards; G. Muirhead, Esq.	1881. Nov. 23.	25.	
				Captain Richards; G. Muirhead, Esq.	1888. Nov. 11.	31.	
	Spital.	W. Compton-Lundie, Esq. of Spital.	Spital Covers.				

Parish.	Estate.	Proprietor.	Cover.	Guns.	Date.	Pheasants bagged.	Correspondent.
Langton.	Langton.	Hon. Robert Baillie-Hamilton of Langton.	Home Covers.	Hon. Robt. Baillie-Hamilton; Earl of Haddington; Lord Binning; Hon. and Rev. A. Baillie-Hamilton; Admiral Baillie; Col. Milne-Home; Capt. Hamilton; E. F. Lantour, Esq.	1888. Dec. 12.	156.	Mr. Geo. Mercer, gamekeeper, Langton.
			Do.	Earl of Haddington; Capt. Hamilton; Hon. H. Scott; Hon. G. Home; Hon. and Rev. A. Baillie-Hamilton; — Hamilton, Esq.	1884. Dec. 10.	100.	
			Do.	Six.	1885. Dec. 5. 1886.	114.	
			Do.	Five.	Dec. 15. 1890.	131.	
			Do.	Seven.	Nov. 15.	131.	
			Do.	Sir Geo. Houston-Boswall, Bart.; Capt. Hamilton; Captain Forbes, R.N.; George Dundas, Esq.	1891. Jan. 28.	138.	
			Do.	Earl of Haddington; Hon. and Rev. A. Baillie-Hamilton; Sir R. B. Harvey; Colonel Trotter; — Trotter, Esq.; Colonel Brown; Sir Harry Vernon; George Dundas, Esq.	Dec. 2.	228.	
			Do.	Same as on Dec. 2, 1891, but Captain Hunter instead of Colonel Brown.	Dec. 2.	169.	
Mordington.	Mordington.	Major Charles Fred. Campbell-Renton of Mordington.	Mordington Covers.	Seven.	1886. Dec. 31.	100.	Robert C. Campbell-Renton, Esq. of Mordington.
				Eight.	1887. Nov. 4. 1888.	126.	
				Six.	Nov. 9. 1889.	98.	
				Six.	Nov. 15. 1890.	115.	
				Seven.	Nov. 7. 1891.	106.	
		Robert C. Campbell-Renton, Esq. of Mordington.		Five.	Nov. 6.	202.	

Parish.	Estate.	Proprietor.	Cover.	Guns.	Date.	Pheasants bagged.	Correspondent.
Polwarth.	Marchmont.	Sir Hugh Hume-Campbell, Bart. of Marchmont.	Fish Pond Cover, Saw Mill Cover, Willie Close, White Gate, Railway Banks.	Sir Hugh Hume-Campbell, Bart.; Sir George Warrender, Bart. of Lochend; Sir George Houston-Boswall, Bart. of Blackadder; Colonel Trotter of Charterhall; Charles Home Purves, Esq. of Purves Hall; Hon. Robert Baillie-Hamilton of Langton; the Earl of Home.	1888. Nov. (one day's shooting.)	287.	
West-ruther.	Spottiswoode.	Lady John Scott-Spottiswoode of Spottiswoode.	Home Covers.	Two. Two. Two. Three.	1885. Jan. 17. 1887. Dec. 15. 1888. Dec. 11. 1889. Dec. 11. 1891. Jan. 15.	40. 43. 53. 75. 65.	Mr. John Young, gamekeeper at Spottiswoode.
	Do.	Do.			Year. 1887.	Total bags. 167.	
					1888.	203.	
					1889.	238.	
					1890.	250.	
					1891.	104.	

When fully on the wing the flight of this bird is very strong and rapid.¹ As an instance of this, it may be mentioned that about fifteen years ago, during a cover shooting at Marchmont House, a Pheasant, which had sprung out of an adjoining plantation, dashed through a pane of the drawing-room window, and struck its head so severely against a large mirror which was hanging on the opposite wall that it cracked the centre of the thick plate glass of the mirror and fell dead on the floor. Several ladies

¹ Mr. Griffith found by experiment that the average flight of three Pheasants in the open, the time being carefully taken by a stop-watch, was at the rate of $16\frac{1}{2}$ yards per second, 990 yards per minute, or $34\frac{1}{2}$ miles per hour. See *The Field* of 19th February 1887.

were in the room at the time when this singular accident occurred. The reflection of the mirror had apparently deceived the bird and caused it to fly straight through the room.

There can be no doubt that *Phasianus colchicus* is the original stock of our common Pheasant, the so-called Bohemian being only a buff-coloured variety. The introduction of the Chinese species (*P. torquatus*) to the coverts of this country has produced the beautiful ring-necked birds which we often see in our woods.

The Pheasant is fond of thick bushy under-cover, where brambles and long grass abound. It seldom strays very far from plantations, but in the morning and evening it may be seen feeding on the adjoining stubble fields, where it picks up fallen grain, insects, and worms. It eats large numbers of wire-worms.¹ Acorns, beech-nuts, sloes, haws, and blackberries also form part of its food.

It makes its slight nest on the ground amongst the herbage of woods and plantations, or in the bottom of a thick hedge-row, or sometimes amongst growing corn. The eggs, which are olive-brown in colour, are usually laid in April or May, and vary from ten to fourteen, although a larger number has been found, when more than one hen has laid in the same nest.

Yarrell states that the well-known suppression of the scent of a sitting hen, so necessary for the safety of ground nesting species, is due to vicarious secretion—that is to say, the odoriferous particles which are usually exhaled from the skin are, during incubation, excreted from the intestinal canal.²

¹ Yarrell mentions an instance of 1200 wire-worms being taken out of the crop of a single Pheasant.—*British Birds*, fourth edition, vol. iii. p. 99.

² *Ibid.* p. 98.

THE COMMON PARTRIDGE.

THE GREY PARTRIDGE.

*Perdix cinerea.**The Partridge.*

*Stillness, heart soothing, reigns,
Save, now and then, the Partridge's late call;
Feetly athwart the ridge she runs, now seen,
Now in the furrow hid; then, screaming, springs,
Joined by her mate, and to the grass field flies:
There, 'neath the blade, rudely she forms
Her shallow nest.*

GRAHAME, *The Birds of Scotland.*

THE Partridge is plentiful in some of the lower parts of Berwickshire, but in other districts it is rather scarce, probably owing to the clayey nature of the soil or to the ground being too heavily wooded.

It appears to prefer well-cultivated, warm, and dry localities, where the fields are of moderate size and surrounded by thick hedge-rows, in the herbage at the bottom of which it can find a secure nesting place. In the higher districts of the county, however, and along the base of the Lammermuir Hills—in the vicinity of Abbey St. Bathans and Cockburn for instance—it is found in considerable numbers, though there it is generally much wilder than in the Merse, and takes longer flights in the shooting season; it is then occasionally a difficult matter to get a second time within range of the same covey, for the birds often fly a mile before they again alight.

Sometimes it is found far from cultivated ground, and, as an example of this, Colonel Brown of Longformacus has informed me that for several years past a covey has been

seen frequenting the bare moor about three miles above Byreclough.

Before fowling-pieces came into use Partridge hawking seems to have been a favourite amusement of some of the proprietors in the county; for we find Godscroft, in his *MS. History of the Homes of Wedderburn*, relating that his brother, Sir George Home of Wedderburn, who was born about 1550 and died in 1616, "had Hawks called Merlins and Falcons, and afterwards another kind called Tercells, which he delighted in, even in his old age. He caught both Partridges and Muir-fowl."¹

In later times nets with setters were used for taking Partridges, the dog lying down on pointing a covey and the net being then drawn over the birds by the men who carried it.

When milder Autumn Summer's heat succeeds,
And in the new-shorn field the Partridge feeds,
Before his lord the ready spaniel bounds,
Panting with hope, he tries the furrow'd grounds;
But when the tainted gales the game betray,
Couch'd close he lies and meditates the prey.
Secure they trust the unfaithful field beset,
Till hovering o'er 'em sweeps the swelling net.

POPE.

Shooting game while on the wing did not come into use until towards the middle of last century, after which period Partridges were killed with the gun over pointers and setters. This method was carried on so long as corn was cut with the sickle, and the stubble left rough enough to afford good cover for the birds, but with the advent of the reaping machine about 1860 and the consequent closely shaven stubble, the system of driving the birds into the cover of turnips and then walking them up in line, without the use of pointers or setters, began to be

¹ *MS. History of the Homes of Wedderburn*, by David Home of Godscroft, 1611.

practised. This plan is usually carried out in the following manner:—Early in the morning some men are sent to beat the stubbles and move the Partridges into the adjoining turnip fields, where, later in the day, the sportsmen, gamekeepers, and beaters form into a straight line and walk across the turnip drills, the birds being shot as they rise by the guns which have been placed along the line at equal distances apart. Retrievers only are used, and well-trained dogs are necessary, for without their aid many wounded birds are lost. "Driving" Partridges has of late years been practised in some parts of the county favourable for this system of shooting, which requires a large number of beaters and good management. The sportsmen stand behind a hedge or some other cover, and the beaters, walking in line through the turnip or other fields towards them, drive the birds over the guns, whilst assistants stationed in conspicuous positions with flags, which they wave when necessary, endeavour to prevent the birds from escaping at the flanks and to keep them flying in the required direction. This method has several advantages, as not only is great skill in shooting required to bring down the game,¹ but a larger proportion of old birds is killed by this than by any other plan; for they are generally the first to fly over the guns, whereas by the other systems they often escape.² Good sport can also be had by "driving" late in the season, when the birds will not generally allow the sportsmen to approach within range, but fly off as soon as the field in which they are resting or feeding is entered. The largest bags of Partridges ever made in Berwickshire have been got by this means on

¹ Mr. Griffiths, in his experiments with regard to the velocity of the flight of birds, found that in the open the Partridge flies at the rate of 14·6 yards per second, 876 yards per minute, or 29·8 miles per hour.—*The Field* of 19th February 1887.

² When there are too many old birds on the ground they drive off the young, which are the most productive breeders.

Lord Tweedmouth's property of Edington and Foulden West Mains, where the Hon. Edward Marjoribanks, M.P., with three friends, on the 21st of October 1891, bagged 130 brace, and on the following day, at Whiterig and Prendergust, 113½ brace. Regarding the former wonderful bag, Mr. T. W. Walker, gamekeeper at Edington, writes to me: "The 260 Partridges which were killed at Edington on the 21st of October last, were got solely by 'driving,' and with only one set of beaters. We had a high cheek wind until lunch-time, which made it difficult to drive the birds up to the guns, as well as to bring them to the bag. Our total score of Partridges for the season (1891-92) is 1723."

I am indebted to the correspondents whose names are given below for the following records of some of the best bags of Partridges which have been got in their respective districts of late years.

Parish.	Estate.	Proprietor.	Farms.	Guns.	Date.	Partridges bagged.	Correspondent.
Abbey St. Bathans.	Abbey St. Bathans.	John Turnbull, Esq. of Abbey St. Bathans.	Ellemford.	G. G. Turnbull, Esq.	1888. Sept. 21.	84.	Mr. James Shiels, gamekeeper, Abbey St. Bathans.
			Do.	Do.	1891. Oct. 12.	40, all killed over dogs.	
	Quixwood.	John Hogg, Esq.	Quixwood.	Four. Four.	1884. Oct. — 1889. Oct. 16.	64. 26.	Mr. John Funton, gamekeeper, Quixwood.
Ayton.	Ayton.	A. Mitchell-Innes, Esq.	Whitfield.	Seven.	1875. Nov. 16.	21.	Mr. Hugh Fraser, late gamekeeper at Ayton Castle.
	Whiterig and Prendergust.	Lord Tweedmouth.	Whiterig and Prendergust.	Four.	1891. Oct. 22.	227.	Mr. T. W. Walker, gamekeeper, Edington.

THE COMMON PARTRIDGE.

Parish.	Estate.	Proprietor.	Farms.	Guns.	Date.	Partridges bagged.	Correspondent.
Buncle.	Bonkyl.	Earl of Home.	Marygold.	Five. Captain the Hon. C. D. Home and party.	1884. Nov. 3.	102.	Mr. John Barrie, gamekeeper, Preston.
	Do.	Do.	Preston.	Three.	1887. Sept. 9.	101.	
	Billie.	Col Milne-Horne of Wedderburn, &c.	Billie Mains.	Seven.	1885. Sept. 18.	111.	Mr William Preston, late gamekeeper at Paxton.
Chirnside and Foulden.	Edington.	Lord Tweedmouth.	Edington and Foulden West Mains.	Lord Wimborne; Hon. E. Marjoribanks, M.P.; — Hope, Esq.; — Whitbread, Esq.	1891. Oct. 21.	200.	Mr. T. W. Walker, gamekeeper, Edington.
			Do.	Duke of Roxburghe; Lord Curzon; Hon. E. Marjoribanks, M.P.; M. Guest, Esq.; H. Gladstone, Esq.; Captain Tippinge.	Nov. 4.	145.	
	Whitehall.	A. H. Mitchell-Innes, Esq. of Ayton and Whitehall.	Harelaw and Old-castles.	Lord Wimborne; Hon. E. Marjoribanks, M.P.; — Whitbread, Esq.; — Hope, Esq.	Oct. 20.	144.	Do.
			Causeway-bank, Harelaw, and Old-castles.	Do.	Oct. 23.	142.	
			Harelaw and Causeway-bank.	A. Mitchell-Innes, Esq. and party.	1890. Sept. 23.	95.	Mr. Hugh Fraser, late gamekeeper at Ayton Castle.
			Harelaw and Nether-mains.	Do.	Sept. 10.	66.	
Cockburnspath.	Dunglass.	Sir Basil Hall, Bart.		Two.	(One day's shooting.)	26.	Mr. John Bolton, gamekeeper, Dunglass.

Parish.	Estate.	Proprietor.	Farms.	Guns.	Date.	Part- ridges bagged.	Correspondent.
Colding- ham.	Berry- bank.	J. Mack, Esq. of Berry- bank.	Berry- bank, 800 acres.	A. S. Logan, Esq.; J. Mack, Esq.	1891. Oct. 8.	30.	J. Mack, Esq.
	Billie.	Col. Milne- Home of Wedderburn.	Auchen- crow Mains.	Col. Milne-Home and party.	1887. Sept. 12.	52.	
			East Reston.	Do.	Sept. 15.	57.	
			Billie Mains.	Do.	Sept. 16.	56.	
			Reston- hill.	R. Clapham, Esq.; Capt. S. Richards; G. Muirhead, Esq.	1883. Nov. 7.	27.	
Duns.	Duns Castle.	W. J. Hay, Esq.	Crum- stane.	One.	1888. Oct. 7.	47.	Mr. W. Smith, gamekeeper, Duns Castle.
	Mander- ston.	Sir J. Miller, Bart.		Two.	1891. Sept. 17.	57.	Mr. J. Smith, gamekeeper, Manderston.
	Wedder- burn.	Col. Milne- Home of Wedderburn.	Wedder- burn Mains and Cairn- hill.	E. F. Latour, Esq.; Capt. Houstoun- Borwall; Major Latour; and another.	1890. Sept. 16.	56.	Mr. R. Bruce, late game- keeper to E. F. Latour, Esq., at Wedderburn Castle.
			Wedder- burn Mains, &c.	Five. D. Brown, Esq., and party.	1887. Sept. 20.	111.	Mr. John Nisbet, late gamekeeper to Mrs. Brown, Nisbet House.
			Wedder- burn Mains and Cairn- hill.	A. T. Clay, Esq.; C. Vane-Tempest, Esq.; G. Muir- head, Esq.	1888. Nov. 19.	42.	
Marlston.	Meller- stain.	The Earl of Haddington.		One.	One day over dogs.	50.	Mr. J. M'Pher- son, game- keeper, Mellerstain.
Eccles.	Lees.	— Marjori- banks, Esq. of Lees.	West Mains.	Three.	1891. Nov. 17.	60.	George Landies, gamekeeper, Ferneyrig.
Eccles (and Green- law).	March- mont.	Sir Hugh Hume- Campbell, Bart.	Eccles Tofta.	Four.	One day in Oct. about 1882.	168.	

THE COMMON PARTRIDGE.

Parish.	Estate.	Proprietor.	Farms.	Guns.	Date.	Part- ridges bagged.	Correspondent.
Edrom.	Broom-house.	Capt. Logan- Home of Broom- house.		R. Clapham, Esq. ; W. Stone, Esq. ; G. Muirhead, Esq.	1884. Nov. 3.	23.	Mr. Hugh Fraser, gamekeeper, Kelloe.
	Blanerne.	E. R. J. Sandys- Lumsdaine, Esq.	Blanerne West Side.	Five.	1890. Sept. 11.	56.	
	Kelloe.	G. C. Fordyce- Buchan, Esq. of Kelloe.		Major Answell ; H. Ross, Esq. ; — Shakespeare, Esq.	1891. Sept. 29.	51.	
	Black- adder.	Sir George Houstoun- Boeswall, Bart. of Blackadder.		Major Answell ; Capt. Tippinge.	Oct. 8.	42.	
	Nisbet.	Lord Sinclair.	Mungos- walls.	Four.	1891. (One day's shoot- ing.) 1890. Sept. 21.	114. 88.	
Fogo.	Charter- hall.	Col. Trotter of Charter- hall.	Risclaw.	Five.	1891. Oct. 20.	108.	Mr. William Thompson, gamekeeper, Charterhall.
	Caldra.	Col. Milne- Home of Wedderburn.		F. Shaw, Esq. ; G. Muirhead, Esq.	1884. Sept. 4.	15.	
Hutton.	Spital.	W. Compton- Lundie, Esq.	Spital Mains, Clara- bad, &c.		1886. Oct. 7. 1887. Sept. 17.	82. 29.	W. Compton- Lundie, Esq. of Spital.
Langton.	Langton.	Hon. R. Baillie- Hamilton of Langton.	Choicelee and Wood- end.	Hon. R. Baillie- Hamilton ; Capt. Houstoun- Boeswall ; — Hepburn, Esq.	1884. Oct. 4.	58.	Mr. G. Mercer, gamekeeper, Langton.
			Middle- field and Ladyflat.	Seven.	1885. Nov. 6.	73.	
Mording- ton.	Mording- ton.	R. Campbell- Renton, Esq. of Mording- ton.	Mording- ton Mains and Lam- berton.		Best day over dogs.	50.	R. Campbell- Renton, Esq. of Mordington.

Parish.	Estate.	Proprietor.	Farms.	Guns.	Date.	Part- ridges bagged.	Correspondent.
Swinton.	Swinton.	Trustees of Mrs. Swinton of Swinton.	Harcaree, &c.	S. Hull, Esq. ; W. Compton- Lundie, Esq. ; G. Muirhead, Esq.	1887, Sept. 13.	33.	
West- ruther.	Spottis- woode.	Lady John Scott-Spottis- woode of Spottis- woode.	Flass.	Two.	1887, Sept. 15.	33.	Mr. John Young, gamekeeper, Spottiswoode.
			Jordon- law.	Two.	Oct. 12.	40.	
			Thorny- dykes.	One.	1888, Oct. 23.	25.	
			Howlet's Ha'.	One.	1889, Nov. 8.	27.	

Some proprietors, in order to increase the stock of Partridges on their estates and improve the breed by the introduction of fresh blood, have purchased eggs from a distance and reared young birds from them. Neither this method, nor the turning down of old birds procured from other parts of the country, is, however, found to succeed so well as the simple plan of changing the eggs in the nests on a property every season, a few being taken from each nest discovered before incubation has begun, and replaced by those in the same state from another nest. It would appear that the birds in a brood pair with each other under ordinary circumstances, and the produce is then apt to be small in number and weak; but when the eggs are changed in the manner indicated fresh blood is introduced and the stock is consequently greatly strengthened and increased.

The Partridge sometimes suffers much in Berwickshire from the effects of heavy storms of rain and snow. The wet summer of 1877 destroyed great numbers all over

the county, whole broods being found drowned in the hay-fields;¹ and in the terrible winters of 1878-81 many perished of cold.

It pairs very early in the season,² as mentioned by Grahame in the following beautiful lines:—

Bleak still, and winterly, o'er hill and dale,
Is nature's aspect: yet some pleasing signs,
Some heart-reviving preludes, faint and few,
Of Spring's sweet season, meet the eye or ear.
When calm the eve, I've heard the Partridge call,
And seen the pairing couple as they tripped
Athwart the wreaths that in the furrows lurk.

The nest is generally placed amongst thick herbage at the bottom of a hedge, or in a hay or corn field, and often by the side of a road or footpath. It consists of a slight hollow scraped in the ground, with a little grass or a few dead leaves for lining, and in it, usually in May, are deposited from ten to fifteen eggs of a uniform olive-brown colour. Sometimes more than the number mentioned are found in the same nest, but it is thought that in this case they are the produce of more than one bird. Boys have always had the reputation of being very fond of searching for Partridges' nests. This is exemplified by the following anecdote, for which I am indebted to my friend Mr. Hardy. The Rev. Dr. Waugh of London, a native of Berwickshire, on coming down from the pulpit of a church in Duns where he had been preaching, was accosted by an old grey-headed man, who inquired regarding his welfare. "But, man," said the Doctor, "I dinna ken ye." "Do you no mind Tam

¹ Mr. Hardy mentions that a well-grown brood of young Partridges with the old birds covering them were found all drowned in the summer of that year in a field near Oldcambus.—*MS. Notes.*

² The French have a proverb which says:—

Quand la Chandeleur est arrivée
La Perdrix grise est mariée.

They apply the term "vin de couleur d'œil de perdrix" to a fine pale wine of full body.

Houliston?" replied his grey-headed friend. "Aye, weel do I," added the Doctor. "Do you mind yon Sunday when we fand the Paitrick's nest and harried her?"

The young, which are hatched in twenty-one days, are attended to by both of the old birds, who show the greatest care for their safety, and often flutter away on being approached as if they could not fly, to draw the attention of the intruder from their offspring. The Partridge may be found on its feeding grounds in the morning and evening, but during the day it is generally concealed in cover of some kind, such as turnips, corn, or rough herbage.

Its food consists of insects and seeds of weeds of various kinds, as well as fallen grain which it picks up on the stubbles.

With regard to the means of distinguishing the sexes in this bird by the colours of the plumage, Mr. W. R. Ogilvie-Grant, of the British Museum, writes:—

"The only reliable characters by which a male Partridge may always be distinguished from a female, except when very young, are two.

"(1) In the male the sides of the neck are brownish-grey, or nearly pure slate colour, with fine wavy lines of black, and none of the feathers have pale buff stripes down the shaft.

"In the female these parts are olive-brown, and almost all the feathers have a pale buff stripe down the shaft, often somewhat dilated or club-shaped towards the extremity, finely margined with black.

"(2) In the male the ground colour of the terminal half of the lesser and median wing coverts is pale olive-brown, with a chestnut patch on one or both webs, and each feather has a narrow pale buff shaft-stripe, and narrow wavy transverse black lines.

"In the female the ground colour of these parts is

mostly black, shading into buff towards the extremity; each feather has a fairly wide buff shaft-stripe, and is also transversely and somewhat irregularly barred with buff, narrowly edged with black.

"To put it more simply, for those who are not versed in the technical names given to the different parts of the plumage. Having looked at the sides of the neck, and seen whether they are grey or brown, with pale buff lines down the middle of each feather, turn the Partridge back uppermost and examine the smaller feathers which cover the upper parts of the wings. If they are sandy-brown, blotched with chestnut, and with small black lines across them, the bird is a cock; if they are mostly black, with conspicuous buff cross bars, the bird is a hen. The buff cross bars on the wing coverts are an unmistakable character, and quite sufficient to distinguish the hen at a glance. The Partridge assumes the adult plumage of these parts of the body at the first moult; and, consequently, the above differences are strongly marked before the commencement of the shooting season, except in late broods."¹

This species does not vary much in its plumage, but occasionally white, pied, and light-coloured birds are observed. Mr. Kelly mentions that several pure white broods frequented the farms of Boon and East Mains, near Lauder, for many years;² and Mr. Thomas W. Walker, gamekeeper at Edington, tells me that five very light or cream-coloured specimens were to be found on the farm of Whiterig, near Ayton, a few years ago, but have now disappeared.³ An example with the primary feathers of the wing nearly pure white was shot by Lord Binning at Mellerstain in October 1865; and another having a horse-shoe mark of the same

¹ *The Field* of 21st November 1891, p. 795.

² *Hist. Ber. Nat. Club*, vol. viii. p. 146.

³ Letter dated 22nd February 1892.

colour on its breast was killed by that nobleman in the following December.

The subject of our notice is held in high estimation as a dish for the table, as the following couplet testifies :—

If the Partridge had the Woodcock's thigh,
It would be the best bird that ever did fly.

It appears to have been considered a great delicacy by the monks of old, for in *The Freirs of Berwick* we find from Freyr Robert's account of the interview between Dame Lauder and Freyr Johnne, when the latter had "knokit at the yet," that

He thankit hir : and said, " My awin luif deir,
Thair is ane pair of boasis, gude and fyne,
Thay hald ane galloun-full of Gaskon wyne,
And als ane payr of pertrikis new slane ;
And als ane creill full of broid of mane." ¹

Mr. Hardy mentions "The Pairick on the Pear Tree" as a rhyme which children in Berwickshire are sometimes heard repeating.

¹ *The Freirs of Berwick, a Tale*, thought to have been written by Dunbar before 1539.—Sibbald, *Chronicle of Scottish Poetry*, vol. ii. p. 377.



THE COMMON QUAIL.

THE QUAIL.

Coturnix communis.

The corn-land loving Quayle, the daintiest of our bits.

DRAYTON.

THE Quail is an occasional summer visitor to the county, where it has been found in several localities.

Mr. Peter Cowe, Lochton, has informed me that a specimen was shot in a turnip field on the farm of Dowlaw, in the parish of Coldingham, about 1863; and two young birds were killed at Butterdean, in the parish of Oldhamstocks, in 1872. Mr. John Wilson mentions that it used to visit the farm of Edington Mains at wide intervals, though only once has he known it remain there throughout the year.¹ Mr. Scott, gamekeeper, Thirlestane Castle, tells me that during the Partridge shooting season—about 1861—he shot two Quails in a stubble field on the farm of Bowerhouse, near Lauder, which he mistook for young Partridges when they first rose to the dog's point, and that they were very fat.² Mr. Hardy records that in the second week of September 1874 an example was killed at Whitburn, in the parish of Cockburnspath, in the Lammermuirs, by one of the Dunglass gamekeepers.³ In November 1882 Mr. George Low mentioned to me that

¹ *Hist. Ber. Nat. Club*, vol. vi. p. 400.

² Yarrell says that the Hebrew name *selav*, in Arabic *salsa*, from a root signifying "to be fat," is very descriptive of the round, plump form and fat flesh of the Quail.—*British Birds*, fourth edition, vol. iii. p. 128.

³ *Hist. Ber. Nat. Club*, vol. vii. p. 515.

his brother, the Hon. Lord Low of Laws, had shot a Quail at Godscroft, in the parish of Abbey St. Bathans, a few years previous to the above date. The gamekeeper at Mordington states that a specimen was seen amongst turnips in Jock's Park on Mordington Mains farm about 1874; and, according to Mr. George Duns, architect, Duns, two were got in the Damhead Field on Mungoswalls farm, in the vicinity of Nisbet House, in August 1885, another pair having been obtained in the same locality about eleven years before that date. Mr. James Purves, gamekeeper, Foulden, writes to me that he shot a Quail on St. John's farm, Foulden Estate, on the 12th of October 1878, and another in the Stackyard Field, Foulden Bastle, on the 30th of September 1882. Two were bagged on Todhillrigg on the 15th of October 1892.¹

It may be mentioned that Mr. Hardy records the breeding of this bird on Springfield farm, in Oldhamstocks parish, East-Lothian, on the western borders of Berwickshire,² and that Mr. George Bolam states that on more than one occasion he has heard its call within "Berwick Bounds," in the fields adjoining the roads leading to Paxton and Chirnside, on the eastern borders of the county. He says: "Like the Corn Crake, Quails are most vociferous at sundown, and it is when the twilight has pretty far advanced on a fine summer evening, and when most other birds are silent, that their 'Plup,' 'plup' is most noticeable." He adds that the note, which is often repeated two or three times in succession, somewhat resembles one of the sounds made by a Turkey Hen.³

The Quail is fond of frequenting grass and corn fields, where, on summer evenings, the peculiar cry of the male may be heard as he "clamours for his running mate."⁴

¹ Information from James Hunter, Esq. of Antonshill.

² *Hist. Ber. Nat. Club*, vol. vii. p. 515.

³ *Ibid.* vol. x. pp. 392, 393.

⁴ Thomson's *Seasons*—"Summer."

It is sometimes seen by Partridge shooters in September, its flight being quick, and generally straight and low. While shooting at Rentonhall, near Haddington, in September 1869, I found a Quail amongst some standing barley; and I have seen bebies in the rye fields near Orleans in France, where the cry of this bird is thought to resemble the words "paye tes dettes!" M. Rolland mentions that poachers in France employ an instrument made of the skin of a mole to imitate its cry. "On appelle *courcaillet* un instrument dont se servent les braconniers pour attirer les cailles. Il est formé d'une peau de taupe cousue comme une outre et à laquelle est adaptée une sorte de sifflet. Cette peau étant gonflée au moyen de la bouche, on imite parfaitement, par une pression particulière des doigts, le chant de la caille."¹

The food of the Quail consists of seeds of various kinds, including those of the chickweed, dock, and plantain, as well as grain; and it also eats many kinds of insects.

It generally makes its nest in a corn or grass field, scraping a slight hollow in the ground, and lining it with a little dry grass. The eggs, which are from seven to twelve in number, are yellowish-white, blotched with dark-brown.


It has long been esteemed an excellent bird for the table. Its price was fixed at "two pennies" by the Scottish Parliament in 1551; and it is associated with "sum daintie fair" in the following advice by Macrell to the Madyn:—

Than tak to stanche your morning drouth,
Ane cup of mavesie for your mouth,
For sume cast sucker in at south,
Togidder with a toist:

¹ *Faune Populaire de la France*, Eugène Rolland, tome ii., "Les Oiseaux Sauvages," p. 840.

Thrie garden gowps tak of the air,
And bid your page in haist prepair,
For your disjone sum daintie fair,
And cair not for na coist.
Ane pair of plevaris pypping hait,
Ane pertrick and ane quailie get, .
Ane cup of sack, sweit and weill set,
May for ane breckfast gaine.

ROBERT, LORD SEMPLE, 1568.



THE LANDRAIL.

CORN CRAKE, CORN CRAKER, LAND HEN, DAKER HEN.

Crex pratensis.

The Corn Crake.

*Poor bird, though harsh thy note, I love it well !
 It tells of summer eves, mild and serene,
 When through the grass, waist-deep, I went to wade
 In fruitless chace of thee ; now here, now there,
 Thy desultory call. Oft does thy call
 The midnight silence break ; oft, ere the dawn,
 It wakes the slumbering Lark ; he upward wings
 His misty way, and, viewless, sings and soars.*

GRAHAME, *Birds of Scotland.*

THE cry of the Corn Crake is generally heard in this county for the first time in the season from the beginning to the middle of May, when it arrives here from its southern winter quarters. The welcome note usually comes from some neighbouring grass field, but if the spring be late, as it was in 1887, and the grass and clover have not made sufficient growth to afford concealment, the bird hides amongst any rough herbage near its usual resorts, such as the long grass in young plantations and about boggy or waste places. As an instance of this, I may mention that on the afternoon of the 15th of May 1887, while walking along the side of the Tweed near the coat-house at Paxton, I was agreeably surprised to hear the loud "Crek, crek" of a Corn Crake amongst some bushes in an adjoining strip of tall ash and elm

trees, where it had taken shelter on its return from the south. Corn and hay fields are its favourite resorts, and its monotonous cry may be heard in the summer evenings and mornings, as well as during the day. It is very difficult to make out the exact spot where the bird is crying, the hopelessness of any endeavour to get a sight of it being thus quaintly alluded to by Montgomery:—

Go round the field, and round the field, and round,
You'll find my voice for ever changing ground;
And while your ear pursues my creaking cry,
You look as if you heard it with your eye.

I have, however, sometimes forced it to take wing by hunting it closely with a good terrier or spaniel;

and, when upraised,
With feet suspended, awkwardly she flies;
Her flight a ridge-breadth: suddenly she drops,
And, running, still eludes the following foot.

GRAHAM, *Birds of Scotland*.

Long ago the neighbourhood of Billy Mire, with its wide stretches of rushes and rough grassy meadows, would be a favourite resort of the Corn Crake; and we find Dr. Henderson thus alluding to the bird in that locality:—

On the Pyper knowes,¹ where the lang broom grows,
I sat me down in the gloamin' dim;
While lay the white mist on the reedy Mire's breast,
And the Crake 'mang the corn sang his evening hymn.

Its food consists chiefly of worms, snails, and insects. It makes a slight nest on the ground amongst long grass or corn, and the eggs, which vary from seven to ten in number, are pale reddish-white spotted with ash-grey and reddish-brown. A curious circumstance connected with the finding of a Corn Crake's nest in 1808 by some men while cutting grass with the scythe on a little island

¹ A round hill at the east end of Billie Mire, said to have been a favourite haunt of the fairies in bygone times.

belonging to the Salmon Fishery of Low Bells, on the Tweed near Paxton, is related by Yarrell, who, quoting from Daniel's *Rural Sports*, says: "The men, while mowing, cut the head from a Corn Crake that was sitting upon eleven eggs; about twenty yards from this spot they had nearly destroyed a Partridge in a similar way, which was sitting upon eighteen eggs; but, observing her, the mowers took the eggs from the nest of the Corn Crake and put them into that of the Partridge. Two days after, she brought out the whole brood, which were seen running about the island. The Partridge catered for them all, and was observed to gather her numerous family under her wings without any distinction."¹

This species generally leaves us about the beginning of the harvest, a period of the year thus happily described by Dr. Henderson:—

The flowers now fade on hill and dale,
And faintly bees are humming:
The corn is rustling in the gale,
And harvest days are coming:
The harping Crake has left the land,
The Swallow soon will follow,
And many a merry harvest band
Will meet in height and hollow.

It is, however, seen later in the season. An example was shot at Mellerstain on the 1st of September 1880;² and Colonel Brown of Longformacus informs me that he got two specimens at Cranshaws on the 8th of October 1884. Mr. Hardy relates that in the middle of the winter of 1835 a Corn Crake was caught in Blackburn Rigg Peat Moss, the site of which is now occupied by the railway. He gives the following as a popular rhyme of Berwickshire, from which it would appear that this bird in former

¹ Yarrell's *British Birds*, fourth edition, vol. iii. p. 141.

² *Hist. Ber. Nat. Club*, vol. ix. p. 399.

times was believed to hide itself and sleep through the winter :—

The bat, the bee,
The butterflee,
The cuckoo and the swallow,
The kittiwake,
And the corn crake,
Sleep a' in a little hollie.¹

It is highly esteemed as a dish for the table, and seems likewise to have had a reputation as a dainty in olden times, for we find Drayton in his *Polyolbion* alluding to it as—

The rayle, which seldom comes but upon rich men's spits.

It is referred to in the old Scottish poem entitled *The Houlate, or the Danger of Pride, maid be Holland*, 1453 :—

He gart the Emproure trow, and trewlye behald,
That the Corneraik, the pundare at hand,
Had poyndit all his pris hors in a poynd fald,
Beaus thai eite of the corn in the kirkland.

¹ *Hist. Ber. Nat. Club*, vol. i. p. 218.



THE SPOTTED CRAKE.

SPOTTED RAIL, SPOTTED WATER RAIL, SPOTTED WATER HEN
SKILTY.

Porzana maruetta.

*Where creeping waters ooze,
Where marshes stagnate, and where rivers wind.*

THOMSON.

THE Spotted Crake is very rarely seen in Berwickshire, there being only two instances on record of it having been found in the county. An adult female was shot at Greenknowe, near Gordon, by Mr. John Scott-Dudgeon, on the 18th of October 1873;¹ and Mr. John Aitchison, Duns, has informed me that a specimen of this bird, now in his collection, was found dead near Duns Railway Station on the 18th of April 1887, having been killed by flying against the telegraph wires.

It is a summer visitor to this country, arriving in March and leaving towards the end of October, and is nowhere plentiful, but seems to be more frequently found in the fens and marshes of Norfolk than elsewhere. It frequents bogs, swamps, and the margins of rivers and lakes overgrown with rank herbage, where it breeds; and, as the nest has been found in the adjoining county of Northumberland,² and as far north as Elgin,³ it is probable that it may yet be discovered in some of the few remaining

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 134.


² *Birds of Northumberland and Durham*, by J. Hancock, p. 125.

³ *Birds of the West of Scotland*, by R. Gray, p. 333.

bogs in Berwickshire, such as the Everett Moss at Legerwood, or Redpath Bog, near Cowdenknowes. Long ago, the great bog of Billie Mire, which extended for miles, and whose surface was covered with dense beds of reeds and rushes, would doubtless be a breeding place of the Spotted Rail.

The food of this bird consists of worms, slugs, and insects. Hewitson, quoting from Hancock, says that the nest, which is usually difficult to find, is placed in marshy ground in a thick bed of reeds, and is composed of the long ribbon-like grass of the reeds, lined with a finer soft grass.¹ The eggs, from seven to ten in number, are reddish-grey, spotted with reddish-brown. This species is smaller than the Corn Crake, darker in colour, and spotted over with small white specks on the neck, back, and wings.

¹ Hewitson, *Eggs of British Birds*, vol. ii. p. 376.



THE WATER RAIL.

BILCOCK, RUNNER, SKIT, SKIDDY-COCK.

Rallus aquaticus.

. lead on, where through the reedy bank
 The insinuating waters, filter'd, stray
 In many a winding maze.

SOMERVILLE.

THIS bird is occasionally seen in Berwickshire during the autumn and winter months. It is, however, by no means plentiful, and as yet there is no record of its breeding in the county. Owing to its skulking habits, and the difficulty of finding the nest amongst the rank herbage of the marshes which the bird frequents, it may, however, nest unobserved in some of the few remaining bogs, such as Redpath Bog, in Earlston parish, or amongst some of the reedy pools and ditches between Greenlaw and Westruther.¹

The Water Rail inhabits swamps and marshes, and the sides of streams, lakes, and pools, as well as ditches overgrown with reeds and other rank herbage, where it skulks, and from which it can scarcely be forced to take wing.

Mr. John Wilson, writing in 1872, mentions that he had seen the Water Rail on Edington Mains Farm four or five times during a residence there of sixty years.² A specimen is recorded by Mr. John Ferguson, Duns, as having been shot amongst the reeds at the side of Duns

¹ Mr. Smith, late gamekeeper at Duns Castle, tells me that a pair of Water Rails frequented the lake there throughout the seasons of 1887, 1888, and 1889, and probably nested amongst the reeds.

² *Hist. Ber. Nat. Club*, vol. vi. p. 400.

Castle Lake in 1873; and he adds that the bird is seen every year about the pools and ditches of Dogden Moss.¹ According to Mr. Cowe, Lochton, four examples were obtained on that farm in 1874. Mr. Kelly says that it is sometimes found at the side of the Leader, and that it frequents Legerwood Loch.² Specimens were killed in some old clay pits near Harcarse, and at Kimmerghame, in the winter of 1878, as recorded by Mr. Hardy.³ Dr. Stuart states that on the 5th of March 1879 a man brought to him a Water Rail which had been got at Billie Burn, in Chirnside parish;⁴ and Mr. John Aitchison, Duns, has informed me that about 1880 he sometimes found this bird in the ditches about Berrywell. Mr. Compton-Lundie of Spital shot a specimen in the bog near Spital House in October 1885, and another was caught in a ditch near the village of Whitsome in the first week of January 1886. It has been got several times during winter within the last fifteen years at Nabdean mill pond, in the parish of Hutton. Mr. Alexander Harold Mitchell-Innes of Ayton shot a specimen at the curling pond there on the 27th of December 1887. When the Water Rail is forced to take wing it flies with its legs hanging down like the Corn Crake, and generally drops amongst the nearest herbage which will afford it sufficient concealment.

Yarrell says that during the nesting season the birds are very noisy, uttering a loud and somewhat explosive cry. The nest, which is well concealed, is made of sedge, and is placed amongst the thickest aquatic plants, or sometimes in willow beds. The eggs are of a creamy-white, with small specks or blotches of ash-grey and reddish-brown, and the usual number is seven.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 121.

² *Ibid.* vol. viii. p. 532.

³ *Ibid.* vol. vii. p. 305.

⁴ *Ibid.* vol. viii. p. 529.

THE MOOR HEN.

WATER HEN, MARSH HEN, STANK HEN.

Gallinula chloropus.

The Water Hen.

*At distance from the water's edge,
On hanging willow's farthest stretch,
The moorhen 'gins her nest of sedge,
Safe from destroying schoolboy's reach.*

CLARE, March.

THIS well-known bird is plentiful all over the county wherever there are streams or pools, the lake at Duns Castle being one of its favourite resorts. Mill ponds and the parts of the Whitadder, Blackadder, Leader, and other streams, where the current moves slowly and where reeds, rushes, and other aquatic plants abound, are also much frequented by this species, and there it may often be seen swimming about on the surface of the water with a nodding motion of the head. Its usual haunts during the day are about the margins of pools, where it searches amongst the rank herbage for worms, insects, and water plants. When it is occupied in feeding at the edge of a mill pond I have often been amused at the precipitate manner in which it retreats to the other side on being approached, fluttering over the surface of the pool with its legs hanging down, and splashing up the water in its line of flight. On reaching the opposite side, however, it seems to consider itself safe, for then it walks about in a leisurely manner, flicking up its tail and thus show-

ing the white under coverts. In the morning and evening it often ventures out on the adjoining grass or meadow land to pick up worms and snails.

During the terrible severity of the winters of 1878-81, Water Hens suffered greatly; for all their usual resorts were frozen up, and in many cases the poor birds were reduced to such weakness for want of food that they allowed themselves to be caught by the hand in the snow.¹

When severe frost occurs in winter and ponds are frozen over, this species frequents running streams, and also occasionally comes about places where poultry are fed, to pick up what it can get. In some parts of the county, such as about Oldcambus, it leaves the ponds in winter, and does not return to them until March, or the early part of April, to breed.²

The nest of the Water Hen is usually placed amongst herbage by the side of the water, or about the roots or low branches of overhanging alders and other bushes. I have, however, occasionally seen it placed on a branch at some height above the ground; also on the open shallow water of a pond, the foundation in this case being made with sticks.³ The nest is made of reeds, sedges, rushes, and other water plants, and the eggs—usually from five to ten in number—are of a cream-coloured white, spotted with reddish-brown.

¹ On the 31st of December 1874 I found a Water Hen lying dead amongst the snow at Paxton, and several so weak that they allowed me to take them up in my hand. Writing on the 11th of February 1881, Dr. Stuart, Chirnside, says: "Coming home one day when at Broadhaugh I observed a Water Hen fly and alight on the top of a wall opposite the window of a cottage, where it allowed me to put my hands upon it."—*Hist. Ber. Nat. Club*, vol. ix. p. 390.

² Mr. Hardy in his *M.S. Notes* gives various dates between 24th of February and 7th of April, as the time when it returns to Oldcambus.

³ In the spring of 1886 a Water Hen built its nest in an open wooden spout used to flood the curling pond at Paxton.

THE COMMON COOT.

BALD COOT, CUTE, QUEET, BALD DUCK.

Fulica atra.

The Bell-poot.

The Coot dives merry on the lake.

SIR WALTER SCOTT.

THE Coot is found in considerable numbers on Duns Castle Lake, Legerwood Loch, the Hirsell Lake, Coldingham Loch, and the lake at Spottiswoode. It also frequents pools and mosses about Greenlaw, and mill ponds in various districts, such as at Townhead farm in the parish of Cockburnspath, Dowlaw in the parish of Coldingham, Foulden West Mains, and Fairneyside near Burnmouth. Mr. Compton-Lundie of Spital has informed me that he has occasionally seen it at his boat pool on the Whitadder near Clarabad, in the parish of Hutton, and I have once or twice observed it at Nabdean mill pond in the same parish. Nowhere in the county can it be seen to greater advantage than on the lake at Duns Castle, which is a beautiful sheet of water sheltered on every side by rising ground and plantations, and having beds of bulrushes and other aquatic plants on its margin. These form favourite retreats and nesting places for the numerous water-fowl, including great numbers of Coots, which may be seen floating at ease on its surface, or diving in search of food.

Mr. John Ferguson informs me that this bird remains at Duns Castle Lake throughout the winter, a part of the water being always kept free from ice for the benefit of the Swans and Geese, which are fed regularly in hard weather when the lake is frozen. He adds that in December 1886 and January 1887, when skating and curling were going on at the lake every day for several weeks in succession, the Coots were very tame, and that sometimes as many as fifty or sixty were seen feeding with the Swans at the edge of the ice. This bird leaves the smaller inland waters and betakes itself to the sea in the beginning of winter, returning again in March.¹

The nest is large, and is strongly built of flags and other water plants, being often placed in a bed of reeds. The eggs, which are from seven to ten in number, are of a stone colour, spotted over with dark-brown.

The food of this bird consists of water insects, worms, and slugs, with portions of various aquatic plants.

In some parts of the country the Coot is used for the table. Yarrell, quoting from Colonel Hawker, says: "They are generally sold for eighteenpence a couple; previously to that they are what is called *cleaned*. The recipe for this is, after picking them, to take off all the black down by means of powdered resin and boiling water, and then to let them soak all night in cold spring water; by which they are made to look as white and as delicate as a chicken, and to eat tolerably well; but without this process, the skin in roasting produces a sort of oil with a fishy taste and smell, and if the skin be

¹ Mr. Hardy, writing under date the 7th of March 1860, notes that "Coots returned to Townhead farm mill pond, where they breed and erect a high and half-floating nest made of rushes and equisetum. In the autumn a shepherd encountered a Coot migrating by the wood border at North Cleugh to the Pease Burn. He caught her, and she bit him severely."—*MS. Notes*.

taken off, the bird becomes dry and good for nothing. A Coot shot in the morning, just after roosting, is worth three killed in the day when full of grass, because it will then be whiter and milder in flavour."¹

¹ Yarrell's *British Birds*, fourth edition, vol. iii. pp. 176, 177.



THE GREAT BUSTARD.

Otis tarda.

*The big-boan'd Bustard then, whose body beares that size,
That he against the wind must runne, e'er he can rise.*

DRAYTON, *Polyolbion*.

ALTHOUGH there is no record of the Great Bustard having been found in Berwickshire since the early part of the sixteenth century, it may not be out of place to refer to it here, for the first British author who gave any account of the bird wrote of it in 1526 as then inhabiting the Merse. This was Hector Boece, who says: "Besides these, we have, moreover, another foule in Mers more strange and uncouth than all these aforementioned, called a Gustard, fully so great as a Swanne, but in colour of feathers and taste of flesh little differing from a Partriche; howbeit these byrdes are not verie common, nayther to be seen in all places; such also is their qualitie, that if they perceive their egges to have bene touched in theyr absence by man's hands (which lie commonly on the bare earth), they forsake those nestes and lay in other places."¹ Mr. Hardy gives the following Latin version of the above from the original *Scotorum Historia* of Boece:—"Præter hæc ayes in Merchia nascuntur Gustardes vernaculo sermone dictæ, colore plumæ ac carne perdicibus non dissimiles, sed quæ olores corporis mole exuperant. Rara est ea avis atque

¹ *The Description of Scotlande*, in Hollinshed's *Chronicles*, first edition, vol. i. p. 10 (1577).

humanum aspectum plurimum obhorrens; nuda humo ova ponit; quæ si ab homine contrectata, aut ejus anhelitu et afflatu vel leviter imbuta senserit (quod facile naturæ beneficio dignoscit) extemplo veluti inidonea ad pullos procreandos relinquens, alio ad ova parienda se confert."

Although it is probable that during the time of the Britons and Saxons Berwickshire was a well-wooded district, yet it appears that a few centuries later, in the reign of William the Lion, its woods, which formerly had been widely spread over the surface of the country, were confined to the sheltered valleys and ravines,¹ the general face of the country being comparatively bare of trees. The wide plain which lies between the Tweed on the south and the Lammermuir Hills on the north, extending to upwards of one hundred thousand acres,² and now known as the Merse, would then be a vast waste of heather mingled with pasture, and interspersed with impenetrable bogs and morasses, the haunt of the wolf³ and the wild boar,⁴ some traditions of which still linger in the county. Here and there on some precipice, or at the side of a marsh, but widely apart, would be seen the square fortlets of the landholders, surrounded by the rude villages which sprang up under their walls. Patches of the drier grounds only would be cultivated by the scanty inhabitants, whose cattle and sheep would browse in the vicinity of their dwellings.⁵ In this wild district the Great Bustard would roam along with the red

¹ See Carr's *History of Coldingham Priory*, pp. 24, 25.

² *Ordnance Gazetteer of Scotland*, by Francis Groome, 1885.

³ *History of the Wolf in Scotland*, by James Hardy, *Hist. Ber. Nat. Club*, vol. iv. p. 291.

⁴ See *Old Statistical Account of Scotland*, 1793, vol. vi. p. 322.

⁵ Mr. John Wilson, late of Edington Mains, in his report on *The Farming in the East and North-Eastern Districts of Scotland*, written in 1878, says at p. 23: "As our grandfathers saw it, the whole country, with the most trifling exceptions, was unenclosed; there was scarcely such a thing as a plantation of trees; there was no artificial drainage, and what tillage existed was restricted to the naturally dry land; the hollow parts were full of bogs, marshes, and stagnant pools."

deer¹ and the roe,² until they finally succumbed to the increase of population in the sixteenth or seventeenth centuries.

¹ A farm near Lauder is called Hartside, and two high hills in that locality are called respectively "North" and "South Hart Law." A ravine in the Lammermuirs, in the parish of Cranshaws, is known by the name of Hind's Cleugh.

² There is a place called Raecleugh, in the parish of Westruther, and another in Langton parish which bears the name of Raecleugh Head.



THE DOTTEREL.

Charadrius morinellus.

*The Dotterell, which we thinke a very daintie dish,
Whose taking makes such sport, as man no more can wish ;
For as you creepe, or cower, or lye, or stoupe, or goe,
So marking you (with care) the apish bird doth doe,
And acting everything, doth never mark the net,
Till he be in the snare, which men for him have set.*

DRAYTON, *Polyolbion*.

THE first notice of this interesting bird as occurring in Berwickshire is in Sibbald's *Scotia Illustrata*, published in 1684, where the author states that it often comes to the Merse: "Morinellus in Mercia frequens. In cibum expetit, ob saporis præstantiam."¹ About seventy years after the publication of the above-mentioned work, Bishop Gibson, in his translation of Camden's *Britannia*, states, with reference to Berwickshire, that "about Bastenrig on the east hand, and the Moristons and Mellerstoun Downs to the west, they frequently take the Dotterel, a rare fowl, towards the latter end of April and beginning of May."² Several notices of this bird as being found in the county occur in the *Old Statistical Account of Scotland*. The Rev. Abraham Ker, who, in 1793, wrote the report on the parish of Nenthorn, mentions that "Dotterels appear in a little flock on the muirs for a few weeks in June."³ Mr. John Renton of Chesterbank, in his account of the parish of Coldingham in 1794, says: "There are only two kinds of birds of

¹ *Scotia Illustrata, sive Prodrômus Historiæ Naturalis, auctore Roberto Sibbald, M.A., Æq. Aur.*, Edinburgh, 1684, fol., p. 19.

² Third edition, London, 1753, vol. ii. col. 1180.

³ *The Statistical Account of Scotland*, by Sir John Sinclair, Bart., vol. vi. p. 337.

passage, the Wood-cock and the Dotterel, seen here; the first frequents the woods, and are few in numbers; the second appears in vast numbers on the heights."¹ The minister of the parish of Mordington, the Rev. George Drummond, writes in 1795: "In the higher grounds of this parish Dotterels are supposed to appear sooner than in any parts of the south of Scotland."² The Reports on Berwickshire in the *New Statistical Account of Scotland* were written in 1834-35, and in them this species is mentioned as occurring in two parishes in the county, Cockburnspath³ and Mordington.⁴

The Dotterel is a bird of passage in Berwickshire, generally arriving from its southern winter quarters in Africa⁵ between the second week of April and the middle of May, and leaving the county for its northern haunts⁶ towards the end of the latter month, a few being known to nest in the Grampians and the English Lake District, while the principal breeding quarters are in the north of Europe. It has been occasionally observed in the county during the month of September on its return journey to the south.

In former times it visited in great numbers the high-lying grounds in the parishes of Abbey St. Bathans, Ayton, Buncle, Cockburnspath, Coldingham, Cranshaws, Earlstoun, Eyemouth, Foulden, Greenlaw, Lauder, Legerwood, Longformacus, Mordington, Nenthorn, and Westruther. It has

¹ *The Statistical Account of Scotland*, vol. xii. p. 57.

² *Ibid.* vol. xv. p. 182.

³ *The New Statistical Account of Scotland* (Berwickshire), vol. ii. p. 300.

⁴ *Ibid.* p. 340.

⁵ Seebohm says it winters in Africa north of the Equator, and that Canon Tristram saw numerous flocks during winter in the hill country of Southern Palestine.—*British Birds*, vol. iii. pp. 30-32.

⁶ Seebohm states that its favourite breeding grounds in the British Islands are in the wildest parts of Scotland on the lonely Grampians in North Perthshire, and on the confines of Inverness-shire; also that it has been found nesting in Ross-shire and the Orkneys.—*British Birds*, vol. iii. p. 30.

of late years, however, been seen only on some of the heights in the parishes of Abbey St. Bathans, Cockburnspath, Coldingham, Cranshaws, Foulden, Greenlaw, Lauder, Longformacus, and Mordington, and that only in small numbers. It does not come to all of these localities every year, but appears at irregular intervals, sometimes a year or two elapsing between its visits. The high grounds in the neighbourhood of Redheugh in the parish of Cockburnspath, Dowlaw in the parish of Coldingham, and Lamberton in the parish of Mordington—all near the sea—are at present the usual resorts of the Dotterel in this county, and here it is generally seen in small flocks of from five to twelve birds. Its favourite haunts in these localities are old leas, newly broken up by the plough and sown with oats, where the numerous stones and turfy clods afford protection to the small beetles, grubs, and other insects upon which it feeds.

On its first arrival it is very tame and unsuspicious, and can easily be approached within gunshot, but after a flock has been fired at several times the birds become much wilder. From thirty to fifty years ago it was in great request by sportsmen in the county and visitors from a distance, not only on account of it being "a very dainty dish,"¹ as old Drayton has it in his *Polyolbion*, but also because it came in at a time when game was out of season. Mr. Turnbull of Abbey St. Bathans informs me that he and Mr. Boyd of Cherry-

¹ Folkard in his *Wild Fowler* says with regard to the Dotterel: "For centuries past it has been highly esteemed as one of the rarest delicacies of the table, consequently eagerly sought after by the fowler, and it appears by the Northumberland *Household Book* (temp. Hen. VIII.) that whilst stints were purchased at twopence per dozen, Dotterels were bought at one penny each—a high price for so small a bird in those days." He thus describes the method of taking Dotterels by lamp or candle light on dark nights: "The fowler proceeds with a lanthorn to their most frequented haunts in the fens, when, by disturbing them, they run along the ground rather than attempt flying, and are thus easily taken with nets which are spread for them. They always run towards the light, so that the fowler fairly entices them to his net."—Second edition, 1864, pp. 307, 308.

trees used to shoot numbers of Dotterels on Shannobank and Godscroft upwards of thirty years ago; and Mr. John Wilson, late of Edington Mains, tells me that a Mr. Anderson, who lived at Cockburn, obtained them on Blackerston and Quixwood about the same time. According to Mr. Bertram, Retreat, they were then frequently killed on Howpark by Mr. William Logan, Ayton; and Mr. John Blackadder, East Blanterne, states that about fifty years ago numbers were shot on the farms of Brockholes and Horsely by Mr. Joseph Hume, Retreat, and his friends. Mr. James Purves, gamekeeper at Foulden, says that about 1857 he sometimes bagged from ten to fifteen brace of Dotterels in a day on Lamberton farm towards the middle of May, when great flocks frequented the newly-sown fields on the skirts of the moor near the Pit Houses. They allowed him at first to go quite near to them when they were sitting in a flock, but after they had been shot at several times they turned very wild and would not let him approach within range, and he had to stalk them from behind dykes and the like to get a successful shot at them. He sometimes got as many as thirty brace during their stay. He had heard an old dyker say that sixty or seventy years ago Dotterels used to visit the high-lying lands on Foulden Estate adjoining Lamberton Moor, and a man named Park, who lived in Horncliffe, was then employed to shoot them for the table of the proprietor, Mr. Wilkie of Foulden, to whom they were sometimes forwarded when he was living in London.

Mr. Hardy, Oldcambus, states that when this species is flying its wings look like those of the Plover, and when a flock rises the birds wheel round and round aloft in the clear air, and then give a dart, circle round, and alight in nearly the same place whence they rose.

In order to keep some record of the past and present haunts of the Dotterel in Berwickshire, the following notes

regarding its resorts in the various parishes of the county have been collected by me, and I take this opportunity of tendering my thanks to the correspondents and others who have so kindly supplied me with the information which they contain. Much of it was obtained in the shape of answers to circulars containing queries about the bird, sent by me to upwards of three hundred farmers in every part of Berwickshire; while I am indebted to my friend Mr. Hardy for a large proportion of the remainder.

PARISH.	Source of information, and date when obtained.	NOTES.
Abbey St. Bathans.	Mr. George Cockburn, Whiteburn, 4th Oct. 1886.	They come about the 15th of May, and do not stay later than the end of that month. Not more than ten in a flock.
	John B. Boyd, Esq. of Cherrytrees, 11th Oct. 1882.	Used to shoot numbers at Abbey St. Bathans about thirty years ago.
	James Hardy, Esq., Oldcambus, 1886.	1856.—A late tenant of Shannobank said they were formerly much more numerous about the place than now. People used to come from a distance to shoot them there. They were very foolish. If you shot one you might have the whole flock, as they wheeled round and round and alighted near where they lost their companion.
	J. Wilson, Esq. of Welnag, 4th May 1886.	A Mr. Anderson, who used to live at Cockburn, was in the habit of shooting them either at Blackerston or Quixwood about thirty years ago.
	John Turnbull, Esq. of Abbey St. Bathans, 1886.	Used to shoot them on Shannobank and Godscroft many years ago. They were not known to cross the Whitadder, but kept always on the north side of that stream.
	Mr. James Shiel, gamekeeper at Abbey St. Bathans, 12th Oct. 1886.	None come to Abbey St. Bathans estate now.

PARISH.	Source of information, and date when obtained.	NOTES.
Abbey St. Bathans— <i>continued.</i>	John Blackadder, Esq., East Blanerne, 30th Oct. 1886.	Very common at Quixwood about fifty years ago. They were shot there by Mr. Joseph Hume, Retreat, and his friends.
Ayton.	Thomas Brodie, Esq., Chesterbank, 29th Sept. 1886.	Dotterels used to come in large flocks to Chesterbank farm about thirty-five years ago. They appeared always at seed-time, but did not remain long on the farm.
Buncle.	Charles Watson, Esq., Duns, 1878.	They were very common in the district about Buncle Wood over twenty years ago. I frequently got the wings for fly dressing from the gamekeeper at Preston. I believe they are now very rare, if not extinct, in the above locality.
	W. Dunlop, Esq., Mayfield, 12th Oct. 1886.	They do not visit this farm now. Small flocks were seen from thirty to fifty years ago.
Cookburnspath.	J. Hardy, Esq., Oldcambus, 1886.	1836, 7th May.—Dotterels seen at Penmanshiel for first time this season. 9th May.—Dotterels peeping about Broad Bog new ground on Penmanshiel Moor. 10th May.—Dotterel shooter, who came from about Lamberton, visited us. He had shot four, and said they leave before Whitsunday. 6th June.—I saw three Dotterels on our lea. I have been told they have been there since the 30th of May. A pair remained long about Blackerston. 1837, 29th April.—Flock of Dotterels near Penmanshiel. Wheatear, said to be a forerunner of this bird, appeared on the 20th of April 1837. 1857, 16th May.—Dotterels on the Black Hill. 1st June.—Still here. A large portion of the Black Hill which was in crop after lea, where not drained and the soil clayey, had the oats completely eaten up by the grub of <i>Tipula oleracea</i>, scarcely any being left. Rooks were feeding on it yesterday and turning up the clods, and to-day I heard Dotterels on it. Long ago the Dotterels used to haunt a portion of this grub-frequented sod when in crop. They were usually found first there by

PARISH.	Source of information, and date when obtained.	NOTES.
Cock-burns-path— <i>continued.</i>	J. Hardy, Esq., Oldcambus, 1886.	the shooters, who came from great distances to obtain them. There were no gamekeepers then in the vicinity. 1875.—Dotterels, although in less numbers than formerly, still frequent the heights of most of the upland farms in the east of Berwickshire bordering the moors. Their favourite resort is old lea ploughed up, where there are clods and stones to protect the glittering beetles that constitute their favourite food. They arrive about the 6th or 7th of May. The flocks are never large, and at first are easily approached. They have now become less wary since they were not interfered with. They were once numerous at Penmanshiel, in the heights above Redheugh, Howpark, and Renton Bell. Again, in the west, they frequented Ecclaw Hill, Blackburn Mill, and some of the high farms round Abbey St. Bathans. About two years since a small returning party of six or seven birds appeared in autumn on Redheugh Hill, out of which two brace were shot. They appeared on Redheugh Hill on the 15th of May 1879. In a letter to me, dated Oldcambus, 19th October 1882, Mr. Hardy says: "The facts about the Dotterel visiting us this year are these: William M'Queen, a mason, who originally came from Lauderdale, and knows the bird, has been building stone dykes for two or three springs on Redheugh and Dowlaw farms near the moors, and I get the earliest intelligence from him. This year he both heard and saw a small flock near Dowlaw on the 12th of April. On the 21st of April John Hay, the rabbit-catcher and gamekeeper here, being in search of Lapwing eggs on a high-lying field near the moor edge, below what is called 'The Big Blake Law,' raised a large flock of Dotterels—between forty and fifty—but when he went back the next week they were gone." The above information was received on the 25th of April. They were thus about a fortnight or three weeks earlier than usual. Last year they were heard near Dowlaw on the 27th of April. Seven birds were seen on 10th May, they still remained on 20th May, and one was seen on 23rd May.

PARISH.	Source of information, and date when obtained.	NOTES.
Cookburnspath— <i>continued.</i>	J. Hardy, Esq., Oldcambus, 1886.	1876, 15th April.—For some years back Dotterels came in the end of September to high fields between Headchester and Daurnae (otherwise Redheugh Hill). A flock of seven noticed last year. 1877, 15th May.—Heard about eight days ago on heights above Redheugh. 1879, 19th May.—A flock is at present feeding on the hill on Redheugh farm above Post Road, not far from Headchesters. They appeared there on the 15th inst.
	Mr. John Bolton, gamekeeper, Dunglass, in letter dated 3rd Dec. 1884.	The Dotterels generally come here about the second week in May, but I have got them in the first week. I have very seldom got them on the moor, but always in the fields adjoining the moor, either in the old grass fields or on old grass ploughed up and sown. They fly in flocks, and have a peculiar sort of whistle. Many a time I have heard them before I saw them. They stay only a few days here. I got several in September 1869, which is the only time I have ever seen them here in the autumn.
	Arthur Hardy, Esq., Penmanshiel, 1st Dec. 1886.	They used to come about middle of April, and remain about three weeks. Six to ten in a flock. I have not seen any for the last two seasons.
	Wm. Allan, Esq., Bowshiel, Nov. 1884.	They used to frequent the farm of Bowshiel about twenty years ago, and also visited the farm of Blackburn, where Mr. Davidson killed numbers with his gun. Edmondean was another resort. Mr. Hay of Spott was in the habit of shooting them seventy years ago.
Coldingham.	Robert Cowe, Esq., Oldcastles, July 1885.	About thirty-six years ago Dotterels in flocks of fifteen or twenty came regularly to Dowlaw farm in spring, and the Dunglass gamekeepers used to shoot them there.
	James Hardy, Esq., Oldcambus, 1886.	1840, 1st May.—Was at Dowlaw Dean and heard the Dotterel had come to some of the places thereabouts. 1860, 21st and 24th May.—Dotterels at Dowlaw. The Stirling Fauld, near the Soldier's Dyke at Dowlaw, is a locality which this bird frequents.

PARISH.	Source of information, and date when obtained.	NOTES.
Coldingham— <i>continued.</i>	James Hardy, Esq., Oldcam-bus, 1886.	1881, 27th April.—Dotterel heard in high grounds at Dowlaw. 7th May.—Flock of seven seen. 30th May.—Still remained. 23rd May.—One seen. 1882.—Mr. Weatherly of Park used to shoot Dotterels at Howpark Hill. 12th April.—William M'Queen saw and heard a small flock on Dowlaw. 1884, 23rd April.—William M'Queen saw a pair at Dowlaw flying westward. 1886, 27th April.—William M'Queen saw one Dotterel to-day on an oat field near the Outer Moor at Dowlaw.
	James Bertram, Esq., Retreat, Sept. 1883.	Up to twenty-five or thirty years ago Dotterels were seen in flocks of from fifteen to twenty on Howpark. ¹ They frequented the old grass land, and came about the end of April. They left before the term (26th May). Mr. W. Logan shot them at Howpark sometimes.
	John Blackadder, Esq., East Blanterne, 30th Sept. 1886.	Very common every spring about fifty years ago on Brockholes and Horseley farms. Mr. Joseph Hume, Retreat, and his friends sometimes shot them there.
Cran-shaws.	H. H. Craw, Esq., Rawburn, 5th Oct. 1886.	The shepherds report that Dotterels are seen in spring and autumn, but they are not plentiful, about fifteen being in a flock.
Earlston.	James Hardy, Esq., Oldcam-bus, 1886.	Mr. W. Brockie, in a notice of the rare birds of Berwickshire and East-Lothian in the <i>Border Treasury</i> , pp. 587-590, says: "That curious bird, the Dotterel, is a summer visitant. It may be seen in flocks in the month of May for about a fortnight in the upper parts of both counties (East-Lothian and Berwickshire) on the skirts of the Lammermuir Hills from Innerwick, Oldhamstocks, and Abbey St. Bathans, to Earlston, Lauder, Channelkirk, and Fala. It loves to settle and feed on newly-ploughed moors. It is easily shot, and is excellent eating."

¹ On 11th October 1882 Mr. W. B. Boyd showed me at Faldonside a beautiful specimen of the male Dotterel in excellent preservation, which had been shot at Howpark by the late Nichol Milne, Esq. of Faldonside, on the 3rd of May 1881.

PARISH.	Source of information, and date when obtained.	NOTES.
Eye-mouth.	James Hardy, Esq., Oldcam-bus, 1886.	Captain Bell, of the Berwickshire Militia, who lived at Linthill House, near Eye-mouth, in the beginning of this century, notes in his diary :—"1802, 8th May.—Saw eight Dotterels this day on some ploughed land at Linthill."
Foulden.	H. H. Craw, Esq., Foulden West Mains, 5th Oct. 1886.	I have occasionally seen Dotterels on this farm, but they are rarely observed, and do not stay with us.
Green-law.	Mr. W. Smith, gamekeeper, Duns Castle, Oct. 1886. Mr. Thos. Smith, gamekeeper, Marchmont, 15th Oct. 1886.	A few Dotterels are seen in spring on Bed-shiel farm. A few are seen almost every spring on the farms of Greenlaw Dean and Hally-burton, from five to twelve birds being in a flock.
Lauder.	James Hardy, Esq., Oldcam-bus, 1886. George M'Dougal, Esq., Blythe, 30th Oct. 1886. Robert S. Bruce, Esq., Thirlestane, 12th Oct. 1886.	1842, 29th July.—Dotterels come to the neighbourhood of Blythe Edge and the moors on the Blythe and Boundreigh waters every year about Whitsunday. Information got from Lauderdale forester. The shepherds say they have seen them in the spring, but not often. A few Dotterels sometimes seen.
Leger-wood.	Mr. John Jamieson, steward, Rumbleton Law, 9th Oct. 1886.	William Cairns, Gordon, says that Dotterels used to come to Boon about twenty years ago.
Longformacus.	Mr. Wm. Duns, Duns, 20th May 1886.	Thomas Hill, gunsmith, Duns, used to shoot Dotterels about Dronshiel and that locality about the month of April fifty years ago. They were plentiful in those

PARISH.	Source of information, and date when obtained.	NOTES.
Longformacus— <i>continued.</i>	Mr. Wm. Duns, Duns, 20th May 1886.	days, and it was a regular practice every year for some of the gunners about Duns to go to shoot them, much the same as people go to the "Crow shooting" at the present time.
	John Blackadder, Esq., East Blarney, 30th June 1886,	Very common at Blackerston about fifty years ago.
	Mr. W. Smith, gamekeeper, Duns Castle, 11th Oct. 1886.	A few Dotterels are seen on Kettleahiel in spring.
Mordington.	Jas. Mein, Esq., Lamberton, 28th Oct. 1886.	The Dotterel is here nearly every spring. Five were seen on the 18th of May 1881.
	Mr. Jas. Purves, gamekeeper, Foulden, 11th Oct. 1886.	On the 26th of May 1858 ten brace of Dotterels were shot at Mordington.
	Mr. Jas. Purves, gamekeeper, Mordington, 11th Oct. 1886.	Dotterels visit the moor on Lamberton farm in April and May. The largest number which I have seen in a flock is seven. I find by the Game Book that seven were shot in a field on Lamberton, known by the name of Heathery Howes, on the 12th of May 1868; and again on the 9th of May 1872 seven were killed in the same field. On the 12th of April 1884 two were obtained at Lamberton.
	Mr. John Nairn, dyker, Mordington, 7th Aug. 1884.	Saw Dotterels in the Camp Field on Lamberton farm in April last. They frequented the rushy part of the field.
West-ruther.	Messrs Clark, Kirklandhill, East-Lothian, 20th Oct. 1884.	Occasionally shot a dozen Dotterels in a season on the farm of Harelaw, near Westruther, about twenty-five years ago. The Spottiswoode gamekeeper used to shoot them on the same farm.
	Mr. John Young, gamekeeper, Spottiswoode, 11th Sept. 1886.	No Dotterels visit any farm on the estate of Spottiswoode now; but I believe about thirty years ago they were plentiful on Westruther Mains farm, near Houndalaw.

THE GOLDEN PLOVER.

YELLOW PLOVER, WHISTLING PLOVER, GREY PLOVER,¹*Charadrius pluvialis.*

The Plover, The Plover.

*From the shore
The Plovers . . . scatter o'er the heath,
And sing their wild notes to the listening waste.*

THOMSON, *Spring*.

THE Golden Plover is plentiful on the Lammermuirs in spring, summer, and the early part of autumn, when its plaintive note gives an additional charm to the wild scenery of the hills.

In October and November great flocks² may be seen associated with Peewits on the grass fields in certain parts of the Merse—the neighbourhood of Whitsomehill in the parish of Whitsome, and Whitelaw in the parish of Edrom, being two favourite localities. When the flocks take wing the Golden Plovers are generally mixed with their congeners for a short while, but they soon use their long, curved, sharp-pointed wings in rapid flight, and, separating from their slow companions, mount high in the air, where they wheel round and round, occasionally uttering their well-known note, and again alight in the field from whence

¹ The Golden Plover is sometimes called the Grey Plover, from its grey colour when at a distance. The true Grey Plover is *Squatarola helvetica*.

² It is probable that our native Golden Plovers receive additions to their numbers in autumn in the shape of immigrants from the north of Europe; for at that season great flocks are seen passing over Heligoland and the lighthouses on the coasts of this country.

they arose. On the setting in of hard weather, this bird leaves the inland districts and frequents the neighbourhood of the sea-coast, where it generally remains more or less until spring, when it returns to the moors to breed, and may again be heard

Wild-whistling o'er the hill.

BURNS.

Its nest is generally placed in a slight hollow of the ground amongst heather, and is lined with a little dry grass. The eggs, which are three or four in number, are of a yellowish-brown colour, spotted and blotched with brownish-black.¹

The food of this species, when inland, consists of worms, slugs, and insects; and on the sea-coast of small molluscs of various kinds.

The Golden Plover has long been considered a great delicacy for the table, and we find in Dunbar's *Dirige to the King bydand our lang in Stirling*, that His Majesty is invited to return to Edinburgh—

To eat cran, pertrick, swan, and pliver,
And every fisch that swyms in river,
To drink with us the new fresch wyne
That grew upon the river Ryne,
Fresch fragrant Clarits out of France,
Of Angiers and of Orliance.²

The price of this bird was fixed by the Scottish Parliament in the reign of Queen Mary (1551) at "four pennies."

The word Plover is derived from the French Pluvier,³ a name which Rolland says this bird bears, because it arrives in flocks in the rainy season of the year.⁴ In some parts of Berwickshire its arrival in autumn is considered by

¹ While walking over Harelaw Moor, near Westruther, on the 24th of April 1885, I found a nest of the Golden Plover with four eggs, which were neatly placed in it with their small ends together, thus enabling the bird to cover them conveniently.

² Sibbald, *Chron. Scot. Poet.*, vol. i. p. 237.

³ Latin *pluvialis*, rainy.

⁴ *Faune Populaire de la France*, tome ii., "Les Oiseaux Sauvages," p. 346.

the country people to be the sign of approaching stormy weather.¹

Its spring notes are said to be thought by the farm labourers in some parts of Scotland to resemble the words "pleugh weel, shave weel, harrow weel."²

Plover's Cairn, which is situated about half a mile south-west of Twinlawford on the march between the parishes of Westruther and Lauder, and is 1230 feet above the level of the sea; and Plovering Haugh, in the parish of Lauder, have apparently got their names from this bird.

In summer the adult male and female have the throat, breast, and under parts of the body black. After the autumn moult the under parts are white, mottled with brown on the breast and flanks.

¹ Note from Mr. Andrew Balsillie, Dykehead, 25th July 1887.

² This is given (comme de M. Walter Gregor) by Rolland, and it is explained by him that "shave" means "sow"; but perhaps the word may be retained as it stands without being considered an unnecessary or superfluous advice.



THE RINGED PLOVER.

RING DOTTEREL, SAND LARK, SANDY LAVEROCK, SANDY LOO,
DULWILLY, STONEHATCH, STONE PLOVER.

Ægialitis hiaticula.

..... the Plover fondly tries
To lure the sportsman from her nest,
And fluttering on with anxious cries,
Too plainly shows her tortured breast;
Oh let him, conscious of her care,
Pity her pains, and learn to spare.

SHENSTONE.

THE sea-coast of Berwickshire, which consists chiefly of precipitous rocks with very little sandy beach, is not suitable for the Ringed Plover, which, on that account, is but rarely seen. It is, however, occasionally observed at the sea-side, and also, though very seldom, along the banks of our rivers. Two specimens are recorded as having been observed on the Tweed near Coldstream by the President of the Berwickshire Naturalists' Club, when the Club met there on the 4th of May 1842;¹ and a Ringed Plover is also mentioned as having been noticed on the Leader by Mr. Walter Simson, Lauder.²

This pretty bird is resident all the year in the neighbouring county of East-Lothian, where the sea beach is flat.

¹ *Hist. Ber. Nat. Club*, vol. ii. p. 4.

² *Ibid.* vol. vii. p. 305.



THE LAPWING.

PEWIT, PEESEWEEP, TUCHIT, GREEN PLOVER.

Vanellus vulgaris.

The Peesewweep,¹ The Teuchit.²

*And here the lonely Lapwing whoops along,
That piercing shrieks her still-repeated song,
Flaps her blue wing, displays her pointed crest,
And, cowering, lures the peasant from her nest.
But if where all her dappled treasure lies
He bend his steps, no more she round him flies;
Forlorn, despairing of a mother's skill,
Silent, and sad, she seeks the distant hill.*

LEYDEN, *Scenes of Infancy.*

DURING the spring, summer, and autumn months the Peesewweep is numerous all over the county; but on the approach of severe weather in winter it migrates southwards to milder

¹ So named from its well-known cry. Mr. Hardy likens the call of the Peesewweep to "Pear-weep," the *r* being burred, more or less distinctly.

² Teuchit—the Lapwing, probably so named from its crest: French "toquet," the cap of a child. It is termed "tuquheit" by Birrell in his "Passage of the Pilgrimer." Watson's *Collection of Poems*, part ii. p. 27.

The Tuquheit and the Sterling than
Togidder with the Pelican
Flew in ane randell richt;
The Plot and the Papingo
With Goldspink, I as thame go,
Syne laich thay down did licht.

LEYDEN'S *Complaynt of Scotland.*

The word "tuquheit" occurs in Holland's *Houlat*, written about 1445. The cry of the bird is said in the *Complaynt of Scotland* to be "theuis-nek:" "The teuchitis cryit theuis-nek, when the piettis clatterit."

Dr. Henderson of Chirnside gives in his MS. the following verse of an old song which relates to localities in the neighbourhood of Chirnside:—

O meet me by the Tuchit yetta,
Or by the Kaeter Well,
And we will sit amang the gowans
Not bonnier than thysel.

localities, and does not usually return to the lower grounds of Berwickshire until about the end of February or beginning of March, when its well-known note, heard for the first time in the season, is always welcome. The bird generally reappears among the hill farms on the Lammermuirs about the beginning of April; and if bad weather sets in at that season, old people call it a "Teuchit storm,"¹ on account of its occurring about the same time as the arrival of the Teuchit or PeesewEEP. A similar term is said to be applied to a storm taking place about the period when the bird departs in autumn.²

In the nesting season it is seen scattered over the county in pairs. When the corn fields as well as the hedge-rows and woods are becoming green, and all nature is rejoicing at the approach of summer, the PeesewEEP with its rounded wings, as it flies here and there over the land by the road-sides, now rising in the air and anon diving down almost to the ground, all the while uttering its peculiar cry, is a constant feature in the rural landscape, for at this delightful season

The Lapwing lilteth o'er the lee
With nimble wing she sporteth.

Leader Haughs and Yarrow.

On the approach of autumn it assembles in great flocks and frequents the grass and turnip fields, where it may be seen resting, or running about in search of worms, snails, and insects, its beautiful crest and graceful attitude being all the while displayed to advantage. The birds at this season are often very restless, and keep flying in broad,

¹ Mr. Hardy says in his *MS. Notes*: "April 1, 1858.—Wind north, frosty, ground covered with snow. Old people say it is a 'Teuchit storm.' This occurs usually in April, about the time when the PeesewEEP makes its appearance amongst the hill farms."

² Mr. Hardy's *MS. Notes*.

scattered bands from field to field, or, congregating in a vast flock, they mount high in the air, and after circling round and round with the Golden Plover,

Their front now deepening, now extending,
Their flank inclining, wheeling, bending,
Now drawing back, and now descending,¹

they by degrees alight at some favourite haunt in the neighbourhood.

The nest of the PeesewEEP is often found in spring when the farming operations of that busy season are in progress, and is frequently destroyed by the harrow or the roller before it is observed. It is generally a shallow depression in the ground, lined with a little dry grass or other suitable material. On the Lammermuirs a very bare spot is sometimes selected. In describing a nest found at the side of Moss Maw, near Penmanshiel and Harelawside march, Mr. Hardy says: "Not a blade of grass or tussock of carices waved around the exposed habitation. The young ones, clothed only with down, 'paddy hair' as it is called, sat huddled together in pairs, one in each pair having its neck laid across that of the other. The parents screamed most piteously overhead as long as I was in search, making their flight and loudest cry in the direction where the nest did not lie. As I drew near, the cries redoubled and became more earnest, and the flight of the old birds approached closer to the ground." Sometimes

Amid the marsh's rushy skirts, her nest
Is slightly strewn; four eggs, of olive hue,
Spotted with black, she broods upon:
 She, if or dog,
Or man, intrude upon her bleak domain,
Skims, clamouring loud, close at their feet, with wing
Stooping, as if impeded by a wound.

GRAHAME, *Birds of Scotland*.

¹ Sir Walter Scott, *Marmion*.

The eggs are highly esteemed as luxuries for the table, and Mr. Howard Saunders, in the fourth edition of Yarrell, says that the earliest "fetch such fancy prices as 15s. a-piece, and a leading West End poulterer recently informed the editor that if he were assured of having the first ten eggs, he would not hesitate to give £5 for them. As the supply increases the value rapidly falls, until it reaches 4s. 6d. per dozen, which is the average London price in the season."¹

As the PeesewEEP, when nesting, has a habit of flying and screaming round any intruder upon her domain, this, in Covenanting times, often led to the discovery of poor fugitive Presbyterians in the moors and mosses of the hills by the soldiers who were in search of them. On that account the bird acquired a bad name amongst the country people² which is thus alluded to by Grahame in his *Birds of Scotland* :—

Ill-omened bird ! oft in the times
When monarchs owned no sceptre but the sword,
Thou, hovering o'er the panting fugitive,
Through dreary moss and moor, hast screaming led
The keen pursuer's eye ; oft hast thou hung,
Like a death flag, above the assembled throng,
Whose lips hymned praise.

Some remnant of this ill-feeling towards the bird seems still to linger in parts of the county, as may be gathered from the following account of the PeesewEEP given by a shepherd at Godscroft to Mr. Hardy :—"When near their nests they jouk down and rin away the contrair way ; they are very

¹ Yarrell's *British Birds*, fourth edition, vol. iii. p. 284.

² See *Tales of a Grandfather*, second series, p. 238. Tannahill says in his *Soldier's Return*—

The PeesewEEP's scraighin' owre the spunkie-cairn !
My heart bodes ill.

The bird seems, however, to have borne a bad character long before Covenanting times, for Chaucer, in his *Assembly of Fowles* (1561), calls it

The false Lapwing ful of trecherye.

wily. They are nasty yelpin craturs and joost deave ye wi' their din. Ah! they're ill-set craturs. They frighten a' the sheep. They're as guid's a doug; whenever they see yin by itsel, they're on the tap on't. Whenever they see a hare they chase it through the middle o' the hirsle, and the sheep a' fear'd o' them, rin as 'twere frae a doug. I've seen me kill them when I fand them, although it was'na richt,¹ joost for the noise they make. A craw daurna come near them. They play the hero wi't a'thegither, for they fa' on't and buffet it, and the craw has naething for't but joost to make off." Another herd, when alluding to localities frequented by this bird, said: "About Aikenga, Peeseweeps are scarce. Gowkscraft's King o' the Peeseweeps." It used to be considered a sign of bad weather in spring when the Peeseweep was observed flying about in flocks on the lower grounds, as may be seen from the following entries in Captain Bell's diary:—

"1813, *April 4th*.—Saw a flock of Green Plover near Eyemouth, and small birds sitting in trees at Linthill chirping in afternoon—a sign of bad weather. *April 13th*.—Flock of Green Plover yesterday morning flying high about 10 A.M.—a sign of bad weather at this season, as they should be paired before this."

There are several popular rhymes and sayings in Berwickshire about the Peeseweep, of which Mr. Hardy has been good enough to furnish me with the following:—

Peeseweep! wallop away,
Cauld feet in a frosty day.

Another version is:—

Peeseweep! wallop away,
Harries my nest in a rainy day.

¹ Poor bird! where'er the roaming swain intrudes
On thy bleak heaths and desert solitudes,
He curses still thy scream, thy clamorous tongue,
And crushes with his foot thy moulting young.

LEYDEN, *Scenes of Infancy*.

The word "Peeseweep" is sometimes heard in the county as descriptive of a weak, poor-looking creature. For instance, a weak calf has been heard to be described as "just a thin speeder of a thing, just a hungry peeseweep of a cratur."

The Peeseweep grass is *Luzula campestris*.¹

¹ *Botany of the Eastern Borders*, by Dr. Johnston, p. 200.



THE OYSTER CATCHER.

SEA PIE, SEA PIET, PIANET, MUSSEL PICKER.

Hæmatopus ostralegus.


The Sea Piet.

*The seamew, seapye, gull, and curlew, here doe keepe,
 As searching every shole and watching every deepe,
 To find the floating fry, with their sharpe piercing sight,
 Which suddenly they take by stouping from their height.*

DRATTON, *Polyolbion*.

THE coast of Berwickshire is so precipitous that it is not suited to the habits of the Oyster Catcher, and on that account the bird is not much seen on the shores of the county. Mr. Hardy records that it is sometimes noticed in the neighbourhood of Redheugh and Siccar Point in spring and autumn.¹ It is fond of frequenting sandy bays, with banks of shingle, where it feeds on molluscs and marine insects. Mr. John Thomson has informed me that an Oyster Catcher was seen at Mertoun in December 1881. Sir William Jardine records that a specimen was killed at Dryburgh.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 110; also vol. ix. p. 404.



THE GREY PHALAROPE.

COOT-FOOT.

*Phalaropus fulicarius.**Far away*

*To either hand, the broad, curved beach stretch'd on ;
And I could see the slow-paced waves advance,
One after one, and spread upon the sands,
Making a slender edge of pearly foam
Just as they broke.*

ATHERSTONE.

THIS pretty bird, which is a little larger than a common Sandpiper, is a very rare visitor to Berwickshire. The only recorded instance of its having been found in the county is that of a male which was shot at Girrick Pond, near Nenthorn House, on the 19th of November 1875. It was alone, and had frequented the pond for several days when it was killed.¹

This species breeds in the circumpolar regions, and its reddish plumage in summer presents a striking contrast to its delicate grey colour in winter.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 502.



THE WOODCOCK.

Scolopax rusticula.

*Oft at this season, near an oozy spring,
 O'erhung by alder boughs, the Woodcock haunts;
 (Sure harbinger, when thus so early come,
 Of early winter tedious and severe);
 There he imbibes his watery food; till, scared
 By man and dog, upward, on pinion strong,
 He springs, and o'er the summits of the grove,
 Flies far, unless, flashing, the quick-aimed tube
 Arrest his flight, and bring him lifeless down,
 With his long bleeding bill sunk in the marsh.*

GRAHAME, *British Georgics*—"November."

THE Woodcock is found in small numbers in most of the woods and plantations of Berwickshire during the late autumn, winter, and early spring months, and in some instances a few have been known to remain in the county through the summer to breed, the nest and eggs having been found in one or two localities.

With the exception of those which stay to nest, the whole of the Woodcocks which are seen in our woods during the shooting season leave for their breeding quarters in the northern parts of Europe in March and April; while it has been observed that those which breed in the county disappear towards autumn, having probably migrated southwards.¹ The autumnal flights of this species from the north generally arrive in Berwickshire about October and November. In some years the birds are much

¹ Colonel Brown of Longformacus has informed me that the Woodcocks which stay during summer in the woods about the Watch Water leave early in autumn. He says that in the neighbourhood of Longformacus the autumnal flights appear earliest on Cranshaws Hill.

more plentiful than in others,¹ which may depend on the severity or otherwise of the weather in the north of Europe, and also on the influence of the prevailing winds during the period of migration. Mr. Selby of Twizell House, Northumberland, the well-known ornithologist, says, with regard to the migration of the Woodcock: "I have found that these birds always come over in the greatest bodies in hazy weather with little wind, and that blowing from the north-east." He adds that "the first flights, which seldom remain longer than for a few days and then pass southwards, consist chiefly of females; whilst, on the contrary, the subsequent and latest flights, which continue with us, are principally composed of males."²

Woodcocks generally make their first appearance in autumn in the neighbourhood of the sea-coast about Lamberton,³ East Castle, and Redheugh,⁴ where they sometimes drop into hedges and turnip fields on their arrival,⁵ being exhausted by their long flight; but they soon spread inland and take up their quarters for the season in their usual haunts. Some woods, amongst which may be mentioned the Grange Wood in the parish of Coldingham; Buncle Woods in the parish of Buncle; Edington Hill Wood⁶ in the

¹ Dr. Johnston in his *M.S. Notes* mentions 1852 as a year when Woodcocks were unusually plentiful in Berwickshire. Yarrell also refers to great numbers being found that year in Norfolk.

² Yarrell's *British Birds*, fourth edition, vol. iii. pp. 321, 322.

³ Woodcocks are often found in the early part of the season, poor, weak, and exhausted, probably from their long flight across the German Ocean.—*Old Statistical Account of Scotland*, Mordington Parish, vol. xv. p. 182.

⁴ The first cold, misty east wind used to bring the Woodcocks to Redheugh, and amongst the turnips at Oldcambus East Mains. They were exhausted when they arrived. The gamekeeper usually finds them early on Dowlaw Braes.—Mr. Hardy's *M.S. Notes*.

⁵ They are sometimes found in very unusual places on their first arrival. Mr. Alexander Leitch, Fairneyside, near Ayton, has informed me that about eight o'clock on the morning of the 13th of November 1884 he found a Woodcock in a lambing shed at Fairneyside, and it escaped through a hole in the roof.

⁶ Dr. Stuart records that the gamekeeper at Edington Hill informed him on the 18th January 1886 that 18½ couple of Woodcocks were killed in Edington Hill Wood during the season 1885-86.—*Hist. Ber. Nat. Club*, vol. xi. p. 241.

parish of Chirnside; and the Moor Plantation near Whitchester in the parish of Longformacus, are favourite haunts of this bird, and in these it is usually found in greater numbers during the shooting season than elsewhere.

One or two Woodcocks may be generally found during the winter months in the woods about Paxton, where they appear to have certain favourite retreats. I have seen them oftenest in the Well Mire Wood, the Crow Dean Wood, and the Old Heronry Wood; but they also resort to the plantations on Nabdean Farm. During the severe snowstorm in the end of December 1874, Woodcocks in numbers frequented the woods at Paxton. They were generally found about the sides of the burns in the plantations, where the ground was comparatively free from frost, and where they searched under the fallen leaves and in the soft earth for worms and insect food. At the beginning of the severe weather the Cocks, on being flushed, flew off very rapidly, but after the storm had continued for a week or two they seemed to get weak and rise with reluctance from their haunts, flew slowly, and alighted at a short distance from the place where they rose.¹ The burn which runs through the Well Mire Wood and falls into the Whitadder never freezes in the hardest frost; and as the ground along its course is soft, it is easily penetrated by the bill of the Woodcock, and is one of their favourite resorts when snow lies on the ground and the frost is severe. The Old Heronry Wood is a romantic and beautiful dean through which a small stream meanders before it joins the Tweed a short distance to the west of Paxton

¹ On the 17th December 1884 my friend, the Rev. Thomas Marjoribanks of Prestonkirk, told me that during the severe frost of January 1881 Woodcocks were seen haunting all the small springs in the neighbourhood of East Linton, and the boys were throwing stones at them. When curling on the Tyne he noticed the birds continually flying over the rink on their way to and from the springs, and they were so weak in their flight that the curlers threw their brooms at them, and two were killed in this way. They flew just like bats.

House. The banks on each side of the rivulet appear to have been originally planted with silver, scotch, and spruce fir, but of these only a few giants now remain, towering above their neighbours of a younger generation to the height of upwards of one hundred feet. When a storm of snow occurs with continued frost, the winter sun melts the icy covering on spots exposed to his rays along the sheltered southern slopes of the dean, and here the Woodcock may be occasionally found during the day, turning over the fallen leaves and dead herbage in search of food. In mild weather it sits concealed in the woods, and at night resorts to swampy places and marshes in the neighbourhood of its haunts to feed.

No bird is more highly prized by the sportsman than the Woodcock, not only on account of its variable flight, which tries his skill with the gun, but also from its well-known reputation as a luxury for the table. The uncertainty when and where the bird will rise adds a further zest to the sport, as it is frequently flushed unexpectedly, and makes off amongst the trees with the speed of a Sparrow Hawk.

Right up he darts amongst the mingling boughs;
 But bare of leaves they hide not from my view
 His fated form, and ere he can attain
 Th' attempted height, with rapid flight to cleave
 The yielding air, arrested by the shot,
 With shatter'd wing revers'd and plumage fair
 Wide scatt'ring in the wind, headlong he falls.

VINCENT, *Fowling*.

When the covers in the neighbourhood of Legerwood and Chapel were young, excellent sport was sometimes got there with Cock, as many as twenty or thirty couple being occasionally killed in a day's shooting.¹ In some years

¹ Mr. Patterson, Ancrum Woodhead, informed me on the 27th October 1887 that, about forty years before that time, he, in one day's shooting at the end of a

heavy bags are made in the Dunglass Woods near Cockburnspath, 1864 being remarkable in this respect, when forty-seven couple were got during the season. Only fifteen couple were obtained there in 1891-92.¹ On the 16th of November 1875 seven couple were bagged in the Whitfield covers on Ayton Estate.² Colonel Brown of Longformacus tells me that on the 8th of November 1876 eight couple were shot in Watch Cover.³ Seven couple were procured in the Harelaw Craigs Wood on Duns Castle Estate in a day's shooting in the winter of 1875.⁴ In the Spottiswoode home covers four couple were brought down on the 15th of December 1887;⁵ and as many were got on the 21st of November 1890 in the Ferneyrig covers, in the parish of Eccles.⁶ Five Cock were shot in the covers at Paxton, in the parish of Hutton, on the 15th of November 1887; and Mr. Macbraire of Broadmeadows has informed me that one day about 1864 he killed six at Tweedhill over a steady old pointer.

The Woodcock is an early breeder, generally making its nest, which consists of a slight hollow in the ground lined with dry grass and leaves, about the outskirts of the woods. The eggs, which are four in number, and are yellowish white, spotted with grey and reddish brown, are usually found in the month of April, but sometimes later. Writing under date the 31st of May 1885, Mr. Hardy says: "A pair of Woodcock are breeding this year in the Oak Wood above Nesbit Haugh, near Penmanshiel

snow-storm, got to his own gun 21½ couple of Cock in the young plantations on Legerwood Farm, chiefly round the Legerwood and Whitelaid marches. He has known as many as 30 couple killed in a day on Chapel.

¹ Mr. John Bolton, gamekeeper, Dunglass, Cockburnspath, 8th February 1892.

² Mr. Hugh Fraser, late gamekeeper at Ayton Castle, December 1891.

³ Information from Colonel Brown on 10th March 1887.

⁴ Mr. W. Smith, gamekeeper, Duns Castle.

⁵ Mr. J. Young, gamekeeper, Spottiswoode, 17th December 1891.

⁶ Mr. George Landles, gamekeeper, Ferneyrig, 22nd December 1891.

Tunnel¹ They had four eggs, but one was broken by the discoverer of the nest. *June 4th.*—They have left their nest with an addled egg and some egg-shells in it, taking with them two hatched young." A paragraph in the *Berwickshire News* of the 21st of August 1884 states that "a few days ago a young Woodcock was found in Duns Castle Woods under circumstances which showed that it had been bred there. In the spring of 1886 a Woodcock's nest with four eggs was got in these plantations; and another containing the same number of eggs was discovered in the Peely Braes Wood, near Duns Castle, by Mr. William Smith, gamekeeper there, on the 3rd of April 1890, who informed me that from the appearance of the eggs at the time when they were found incubation had only recently begun, and that they were hatched in fifteen days.

It is now well known that in the evening the Woodcock carries its young between its legs and pressed against its breast with its bill, from the dry places in the woods where they are hatched, to soft swampy spots in the neighbourhood, where they can feed.

Externally the female cannot be distinguished from the male bird. The peculiar markings on the first quill feathers are not constant, and are thought to be indicative of age rather than of sex.²

The average weight of a Woodcock is twelve ounces; young birds are much lighter, being seven or eight ounces.³

A popular saying sometimes heard on the Borders is

¹ Mr. Abraham Mack, Abbey St. Bathans, told me on the 5th of July 1886 that he found a Woodcock's nest near the side of Penmanshiel Wood in the summer of 1827. It had two eggs, and was on a dry knove amongst some stumped heather near some birch bushes. He saw the old bird sitting on the nest several times.

² See *The Field*, 9th January 1886.


³ *Ibid.*

that "one Swallow does not make a summer nor one Woodcock a winter."¹

In the reign of Queen Mary the Scottish Parliament fixed the price of the "woodde-cokke" at "four pennies."²

¹ *Borderer's Table Book*, vol. vii. p. 215.

² *Laws and Acts of Parliament made by King James I. and his Royal Successors*, by Sir Thomas Murray of Glendook, Kt. and Bt., 1681.



THE GREAT SNIPE.

DOUBLE SNIPE, SOLITARY SNIPE, WOODCOCK SNIPE.

Gallinago major.

And long-bill'd Snipe, that knows approaching rains.

WILSON, *Lock Winnoch.*

THIS bird is rarely seen in Berwickshire. A specimen was shot by the Earl of Haddington in a dry grass park on the farm of Lightfield, near Mellerstain, in the autumn of 1865;¹ and another was killed by Mr. Stow Compton-Lundie in a field at Spital House, in the parish of Hutton, about the same time.² Mr. Kelly records that an example was got by Mr. Scott, gamekeeper, Thirlestane Castle, in 1870;³ and Mr. George Low told me in November 1882 that his brother, the Hon. Lord Low, saw a Great Snipe on Ellemford ground a few years previously.

It is known to be a visitor to the British Islands while on its way to its southern winter quarters, its arrival generally taking place between the middle of August and the middle of October.

It may be distinguished from the Common Snipe by its greater size, and by the under parts being more profusely and closely barred. Seebohm says that the chief distinction lies in the tail; in the adult Great Snipe the terminal half of the four outside tail feathers on each side is pure unspotted white, whilst in the Common Snipe it is chestnut-buff, with a sub-terminal dark-brown bar.

¹ Turnbull's *Birds of East-Lothian*, p. 48.

² Information from W. Compton-Lundie, Esq. of Spital, 10th February 1886.

³ *Hist. Ber. Nat. Club*, vol. vii. p. 523.

THE COMMON SNIPE.

MOOR OR MIRE SNIPE, HEATHER BLEATER, BLITER OR BLUTTER.

Gallinago cœlestis.

The Mire Snipe, The Heather Blutter.

*Amid these woodless wilds, a small round lake
 I've sometimes marked, girt by a spongy sward
 Of lively green, with here and there a flower
 Of deep-tinged purple, firmly stalked, of form
 Pyramidal—the shores bristling with reeds,
 That midway over wade, and, as they bend,
 Disclose the water lily dancing light
 On waves soft-rippled by the July gale,
 Hither the long and soft-billed Snipe resorts.*

GRAHAME, *Birds of Scotland.*

IN former times when reedy pools, bogs, and mires abounded all over the county, the Snipe would be much more plentiful than it is now; for agricultural improvements and drainage have left it very few swampy spots on which to rest the sole of its foot. It is, however, still found during the autumn in considerable numbers in suitable places, such as about Legerwood Loch, Lurgie Loch,¹ and Redpath Bog, and on the wet moors and mosses of the hills²—Harelaw Moor, in the parish of Westruther, having been a favourite

¹ Mr. Black, Girrick, says that this loch or bog, which is dry in summer, is much frequented by Snipe in autumn and winter, when he has seen as many as fifty or sixty upon it in a day. The site is covered with natural birch and rough hill grass.—Notes from Mr. Black, 12th January 1888.

² Mr. Walter Elliot, Hollybush, informed me on the 16th of August 1887 that there is a bog on the march between Ellemford and Harehead Farms where Snipe are very plentiful in August and September. As many as fifty may be put up in walking over it.

resort until it was drained. Although a few Snipe breed in suitable localities throughout the county, yet it is probable that most of those which we see during the shooting season are visitors from the northern parts of Europe, which have joined our native birds; for this species is occasionally seen on migration at the lighthouses on the Farne Islands and Isle of May in autumn, and again in spring when it returns northwards.¹

There is no better sport with the gun than Snipe shooting when the birds are fairly plentiful, but, unfortunately, this is seldom the case in Berwickshire. The "Scape, scape" of the game as it rises and makes rapidly off with its zig-zag flight is always a pleasing sound in the sportsman's ear, and the first Snipe which falls to the gun in youth, like the first Woodcock, is long remembered. In the Grouse shooting season it is occasionally killed in small numbers in the Lammermuirs, and sometimes rises before Partridge shooters in damp turnip fields in the Merse. On these occasions the "pallat-pleasing snite," as old Drayton calls it in his *Polyolbion*, gives variety to the bag, and forms an agreeable addition to the table afterwards.

During severe frost and snow in winter the bird is very often pressed for food, and may be seen frequenting the sides of brooks, ditches, and open drains by road sides, or even close to houses and villages. It is then much tamer than usual, and does not fly far when disturbed. It is likewise found about the sea-side in autumn and winter. In March and April, according to the season, the Snipe begins to make a peculiar humming or bleating sound when on the wing.² The bird soars high up in the air, and the humming

¹ See *Reports on the Migration of Birds*, 1879-86.

² Mr. Hardy in his *M.S. Notes* writes: "1840, *March 16th*.—Snipe bleating this morning at Penmanshiel. This is an early year. 1836, *April 19th*.—Snipe piping to-day in the air. 1843, *June 16th*.—Snipe bleating to-day."

is heard when it is descending rapidly.¹ There is considerable difference of opinion amongst ornithologists regarding the origin of the sound, but the greatest weight appears to be attached to the theory that the sound is caused by the vibration of the feathers of the wings during the descent of the bird.² Mr. Hardy says that people in the Lammermuirs call the bird the "Mire Drum," on account of the peculiar noise which it makes in the air:—

Oh, how I love the moorland scene of spring
Beneath the smile of morning's ruddy glow,
The whir of heath-cock and the curving wing
Of snipe high booming o'er the marshy flow.

This species has often been found breeding in the neighbourhood of Penmanshiel. A nest discovered there by Mr. Hardy, in a bog, was made of withered sprits (*Juncus articulatus*) and a few grasses. It had four eggs, and their tips were placed inwards around the centre of the nest.³ It also rears its young occasionally amongst the herbage by the side of Dowlaw Mill Pond, and Colonel Brown has informed me that the nest is frequently found in the moors about Longformacus.

. . . . here her house she forms,
Here warms her fourfold offspring into life.

GRAHAM, *Birds of Scotland*.

The eggs are yellowish or greenish white, spotted towards the larger end with several shades of brown.

The food of the Snipe consists of worms and insects, which it procures by boring in moist or swampy ground with its long bill.

¹ Mr. Hardy in his *MS. Notes* writes: "1863, April 16th.—Two days ago at Penmanshiel Moss, Snipe were circling round the moor, now rising aloft, then descending humming."

² Yarrell's *British Birds*, fourth edition, vol. iii. pp. 344, 345.

³ The nest was found very late in the season, namely, on the 17th of July 1845.
—Mr. Hardy's *MS. Notes*.

THE JACKSNIPE.

JUDCOCK, JID.

Gallinago gallinula.

*For I mine own gain'd knowledge should profane,
If I would time expend with such a snipe,
But for my sport.*

SHAKESPEARE, *Othello*, Act i. Sc. 3.

THE Jacksnipe is a much smaller bird than its common congener,¹ and generally arrives in the county from its breeding grounds in the northern parts of Europe in small numbers towards the end of September or in October. It remains with us throughout the winter and early spring until March or the beginning of April, when it leaves for the arctic regions, where it spends the summer.

In its general habits the Jacksnipe resembles the Common Snipe, and is fond of frequenting marshy places where the herbage is rough. Here it sits closely concealed when not feeding, and is often difficult to put up, even with the assistance of a good dog. When it rises from the ground its flight is slow, zig-zag, and wavering, and on this account it is sometimes missed by the sportsman who thinks it is sure to fall to his gun. I have occasionally seen five or six shots fired at a specimen which, with short flights, kept moving from one part of the bog to another, and rising each time close to the shooter's feet. The Jacksnipe does not utter any cry when it is flushed, and although it is a

¹ From its small size as contrasted with the *Whole*, or Common Snipe, it is called the *Half Snipe* in Norfolk.—Swainson's *Folk-Lore of British Birds*, p. 169.


very small bird, it is considered a delicate morsel for the table; hence the old French quatrain :—

Le bécasseau ¹ est de fort bon manger,
Duquel la chair resueille l'appetet,
Il est oyseau passager et petit,
Et par son goust fait des vins bien juger.

During severe weather in winter, when its usual haunts are frozen and covered with snow, it may be seen frequenting the sides of open drains and ditches in search of its food, which consists of insects of various kinds.

There is no reliable record of this species having bred in the British Islands.

¹ It is so called by the game-dealers in Paris.—E. Rolland, *Faune Populaire de la France*, tome ii. p. 358.



THE DUNLIN.

PURRE, STINT, SEA SNIPE, PLOVER'S PAGE, SEA LARK,
RED-BACKED SANDPIPER, OX BIRD, OX EYE.

Tringa alpina.

*The puet, godwit, stint, the palate that allure,
The miser and doe make a wastefule epicure.*

DRAYTON.

THE precipitous coasts of Berwickshire are not suitable for the Dunlin, which loves sandy flats projecting into the sea and the mud banks found at low water in the estuaries of rivers, where it feeds in great flocks during autumn and winter. Although most of the birds which compose these flocks migrate in spring to the north of Europe to breed, many betake themselves at that season to wild moorlands in various parts of Scotland, where they rear their young. After the nesting season is over, the birds which have bred in this country are joined at the sea-shore by great flocks which have returned from colder regions.

Although there is no record of the nest of the Dunlin having been found in Berwickshire, yet the presumption is that the bird has bred on the moors about Longformacus, for Colonel Brown has informed me that on the 16th of July 1885 he shot a Dunlin on swampy, mossy ground, high up, near where the "Grey Mare" and the "Grey Mare's Foal" (two detached boulders) lie on the moor. The nest of this species is usually placed amongst short heather, or under a tuft of grass, and is sometimes difficult to find. The eggs, which are four in number, vary considerably in colour—from pale green to pale buff, spotted with two shades of reddish-brown.

THE PURPLE SANDPIPER.


Tringa striata.

*The Sandpipers,
A tiny flock, innumerable, as round
And round they flew, bewailed their broken ranks.*

DELTA, *The Fowler.*

THE Purple Sandpiper is occasionally seen during winter frequenting the low, tide-covered rocks on some parts of the coast of Berwickshire, including Greenheugh Point, near Oldcambus, where Mr. Hardy says he has observed a small flock popping up and down close to the edge of the sea, like so many mice at play. At ebb-tide it searches amongst the sea-weed on the rocks for small marine creatures of various kinds, and when the tide is flowing in it seems to be fond of feeding close to the edge amid the splashing spray.

This species usually makes its appearance on the coast in October, and departs in May for its breeding grounds in the north of Europe.



THE RUFF.

Machetes pugnax.

*Of flesh of birds—roast, grilled, or fried;
Of hare or rabbit, woodcock, snipe;
Of partridge, pheasant, plover, widge,¹
Of larks for breakfast, or for supper,
(On these I love to cram and stuff).*

There's nothing nicer than a fattened ruff.

FOLKARD.

THIS interesting bird was formerly plentiful in the eastern counties of England, where it bred in great numbers, but, owing to drainage and other causes, it is now rarely seen there in the nesting season. It is, however, observed in small flocks on spring and autumn migration.

There are very few recorded instances of the occurrence of the Ruff in Berwickshire. Mr. Charles Watson, Duns, mentions that a female was shot near Burnmouth in October 1873,² and Dr. Stuart of Chirnside, writing on the 11th of September 1876, says: "Two rare birds made their appearance at Edington Mains Mill Pond the other day. Mr. Wilson's groom shot one, but the other escaped. Mr. Wilson sent the bird to Dr. Duns of the New College, Edinburgh, who made it out to be the Reeve, the female of the Ruff. I should also mention that the bird which escaped was a young bird, much lighter in the plumage than the one shot. The Reeve was observed to be feeding it with insects from the pond."³ Mr. Andrew Brotherston, bird-stuffer, Kelso, states that, on the 22nd of September

¹ The ancient name of the Lapwing.

² *Hist. Ber. Nat. Club*, vol. vii. p. 127.

³ *Ibid.* vol. viii. p. 196.

1881, he received two specimens in winter plumage from Lennel, near Coldstream.¹ In these cases the birds appear to have been on autumn migration from their breeding grounds in the north of Europe to their winter quarters in the countries south of the Mediterranean.

Mr. Robert Gray remarks that the Ruff is found in small flocks on the shores of the Firth of Forth,² and on the muddy parts of the estuary of the Tyne—chiefly in September—when its stay is short and its movements uncertain.³

During the breeding season the males have a singular addition to their usual plumage in the shape of long feathers on the neck and sides of the head, which form a frill or ruff—hence the name of the bird—and at this time their plumage varies greatly in colour.

The Ruff is polygamous, and desperate fights occur in spring amongst the males. When so engaged they used to be caught with clap-nets in the fens in great numbers.

It has been held in high estimation for the table, and Folkard, writing in 1864, says: "At the present day the price paid for fattened ruffs is often as much as *four guineas* per dozen, almost as expensive as ortolans, and they are considered by some gastronomes as equally delicious. They are fattened for the table with bread and milk, hempseed, and sometimes boiled wheat, but if expedition is required sugar is added. This latter method of feeding makes them perfectly fat in a fortnight."⁴

¹ *Hist. Ber. Nat. Club*, vol. ix. p. 562.

² *Ibid.* vol. vii. p. 465.

³ *Ibid.* vol. viii. p. 52.

⁴ H. C. Folkard, *The Wild Fowler*, pp. 313, 314.

THE COMMON SANDPIPER.

SANDY LAVEROCK, SAND LARK, WATER LAVEROCK, SAND SNIPE,
SUMMER SNIPE, KILLIELEEPSIE, KITTIE-NEEDIE,
WILLY-WICKET, WEET-WEET.

Totanus hypoleucus.

The Sandy Laverock.

*Along the river's stony marge
The Sand-lark chants a joyous song.*

WORDSWORTH.

ABOUT the end of April or beginning of May this pretty bird returns from its winter quarters in Africa to the sides of the Tweed, Whitadder, Blackadder, Leader, Eye, and other waters in the county, where it breeds in considerable numbers throughout the summer, departing southwards again in September.

Shortly after its arrival it may be seen in pairs haunting the gravelly edges of the streams, and flitting from stone to stone along their winding courses. The angler, as he wanders by the river side amongst the beautiful woods and wild flowers which border many of his favourite pools, loves to hear the joyous song of the Sandpiper, which, intermingled with the rippling sound of the water, falls pleasingly upon his ear. If his basket be well filled, contentment reigns in his breast as he rests upon some dry grassy turf for a few minutes whilst recalling to mind the delightful words of old Isaac :—

“I'll tell you, scholar, when I last sat on this primrose

bank, and looked down those meadows, I thought of them, as Charles the Emperor did of the city of Florence, 'that they were too pleasant to be looked on, but only on holidays,' as I then sat on this very grass I turned my present thoughts into verse, 'twas a wish, which I'll repeat to you :—

I in these flowery meads would be :
These crystal streams should solace me ;
To whose harmonious bubbling noise
I with my angle would rejoice."

The "Sandy Laverock's" nest is looked upon by the boys of the county as "rare," being somewhat difficult to find. It is often placed amongst the herbage not far from the margin of the water, in a slight hollow scraped out by the bird and lined with a little dry grass. The eggs, which are four in number, are reddish-white, spotted with brown.



THE GREEN SANDPIPER.

Totanus ochropus.

. *birds of passage piping up and down.*

TENNYSON.

ONE morning about the middle of September 1877 the gamekeeper at Paxton House, while walking with his gun in the Wester Grass Park, near my house, heard a shrill whistle over his head, and, looking up, saw two birds like Snipes flying rapidly towards the Tweed at a considerable height in the air. He fired at them, when one fell, which he brought to me, and I found it to be a beautiful specimen of the Green Sandpiper. Mr. Hardy records a male shot near Chirnside on the 1st of May 1876;¹ and, writing under date the 22nd of August 1877, says: "After a continuation of wet weather several temporary pools were formed in the dean at Oldcambus, which were frequented by Wild Ducks; and the restless Redshanks, leaving the sea-side, circled round the margins. To one of the loneliest also a Green Sandpiper resorted for a few days. It appears to delight in quiet tarns and remote watercourses, where it can pick up worms undisturbed. This is the character of the situations in which hitherto I have surprised this occasional autumnal visitant."² It was observed at Oldcambus on the 17th of July 1879.³ Mr. George Bolam, in a letter to me dated the 25th of August 1884, writes: "It may interest you to know that yesterday Mr. Evan Sanderson

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 196.


² *Ibid.* vol. viii. pp. 528, 529.

³ *Ibid.* vol. ix. p. 401.

and I saw a Green Sandpiper on the Whitadder near Clarabad Mill." Mr. James Purves, gamekeeper at Mordington, has informed me that he has twice shot this species on that estate, the first instance being in a bog at the "Lang Belt" plantation, and the next in a ditch leading to Mordington Mains upper damhead. Mr. Andrew Brotherston, bird-stuffer, Kelso, mentioned to me on the 19th of March 1885 that, about the middle of August 1884, three examples were shot on a pond on the march between the farms of Lochton, in the parish of Eccles and Harpertown. Mr. John Thomson, Maxton, tells me that a specimen was shot near Ninewells in the second week of January 1891.¹

The Green Sandpiper is very erratic in its movements, and is a visitor to the British Islands on spring and autumn migration.

¹ Letter dated the 29th of January 1891.



THE COMMON REDSHANK.

SEA SNIPE, POOL SNIPE, SAND COCK, RED-LEGGED SNIPE.

Totanus calidris.

The Sea Snipe.

*The rede-schank cryit my fut, my fut.*¹

COMPLAYNT OF SCOTLAND.

THE Redshank is found during the autumn, winter, and spring months on some parts of the coast of Berwickshire, such as the neighbourhood of Oldcambus, where Mr. Hardy occasionally sees small flocks about Greenheugh and Siccar Point from about the beginning of July until the end of April.

Although the great majority of the Redshanks are migratory, and leave our shores in spring for their breeding grounds in the northern parts of Europe, returning again in autumn, yet many remain in Great Britain throughout the summer and rear their young in suitable localities. Mr. Gray says that a few pairs breed in the Lammermuirs.² Mr. Tweedie, Swinton Public School, kindly sent to me a note on the 8th of April 1889, saying that a pair of Redshanks had again returned to a field of tussocky grass on the farm of Swinton Hill, lying immediately to the

¹ Leyden, in his Glossary to *The Complaynt of Scotland*, makes out the "rede-schank" to be the Fieldfare; but I cannot see how the Fieldfare can be the bird referred to, as its legs are dark-brown, and not red. The Redshank was known by the same name as at present several hundred years ago, at the time when the *Complaynt* was written (1513-42), and is frequently mentioned in the household books of the 5th Earl of Northumberland, circa 1512, and of the L'Estranges of Hunstanton circa 1527.

² *Hist. Ber. Nat. Club*, vol. viii. p. 51.

south of the village, where it was supposed they had bred in the previous year; and shortly afterwards he showed to my wife the nest containing four eggs, which she sketched on the spot.

The Redshank generally breeds in wild, marshy places, and the nest is but a slight depression in the ground, lined with a little dry grass. It lays four eggs, somewhat like those of the Lapwing in general appearance, though they have a lighter ground colour and redder spots. It is very noisy when the nest is approached.¹ The food consists of worms and small aquatic creatures of various kinds.

A rock called "Redshank's Rock," on the coast, a little distance to the north of Coldingham Shore village, has apparently derived its name from this bird.

¹ On approaching its nesting ground in the field on Swinton Hill Farm I observed that the birds became very noisy, and flew round about me uttering loud calls. Occasionally they alighted on the top of the hawthorn hedge and sat there for a short time.



THE GREENSHANK.

GREEN-LEGGED HORSEMAN, GREATER PLOVER,
GREENSHANK SNIPE.

Totanus canescens.

*The wandering flocks, expelled from northern shores,
In varied forms pursue their trackless way,
Courting the genial aspect of the south,
Whilst iron winter holds his despot sway.*

T. HUGHES.

As there are no suitable haunts for the Greenshank on the coast of Berwickshire, such as mud-flats, slakes, or marshes, it is very seldom seen, only two instances of its occurrence in the county being recorded. In March 1871 a specimen was shot by Mr. James Trotter, gamekeeper, Paxton House, as it rose from a large ditch which runs through Paxton North Mains Farm and joins the Whitadder at Clairvale Wood. Mr. Andrew Brotherston, bird-stuffer, Kelso, informed me that a female of this species was killed at Lochton, in the parish of Eccles, in August 1884.

This bird is generally found on the coasts of the British Islands when it is passing to or from its principal breeding grounds in the northern parts of Europe, although a few nest in the north of Scotland. It is frequently seen on the shore about Holy Island from August to October, where it is shy and wary. It is larger than the Redshank, and its legs are olive-green. The food consists of worms, insects, crustaceans, and other small marine animals. It is an excellent bird for the table.


THE BLACK-TAILED GODWIT.

*Limosa ægocephala.**The Godwits running by the water's edge.*

JEAN INGELOW.

LIKE the Ruff, the Black-tailed Godwit was in former times plentiful in the fen districts of England, where it bred ; but it is now known there only as a migrant in spring, while passing to its breeding grounds in the north of Europe, and in autumn on its return southwards. It is very rarely seen in Berwickshire, the only instance of its occurrence in the county known to me being that of a specimen which was shot at Dowlaw, near Fast Castle, by Mr. William Cowe about 1864, and which is preserved in the collection of Mr. Peter Cowe, Lochton. The Godwit was accounted a great dainty for the table, and birds fattened on bread and milk were, in the time of Pennant, sold for 5s. each. It is classed along with the Ortolan by Cowley in the following lines :—

Nor Ortolans, nor Godwits, nor the rest
Of costly names that glorifie a feast,



THE COMMON CURLEW.

WHAUP, WHAAP, STOCK WHAAP, WHITTERICK.

*Numenius arquata.**The Whaup.**Wild as the scream of the Curlew,
From crag to crag the signal flew.*SCOTT, *Lady of the Lake.**Ye Curlews calling thro' a clud.*BURNS, *Elegy on Captain Matthew Henderson.*

THE Curlew is usually associated in our minds with the heaths and mosses of the Lammermuirs,¹ where from spring to autumn it may be seen flying in wide circles round the moors uttering its well-known call. Although the peculiar cry from which the bird derives its English name has an eerie and melancholy sound to some ears, yet to others it is very pleasing.² The late Mr. Hewitson says: "I have never traversed the lone wild heath, deserted, except by the feathered race, and at a moment in which I have felt the

¹ It is plentiful on Coldingham Moor.—J. Bowhill, 1st April 1886. It abounds on the moors and mosses around Spottiswoode and in the Earlstoun district. It also frequents the east end of the moss at Legerwood Loch, and Corsbie Bog, near the Tower.—W. Lockie, 28th July 1886.

² The Rev. John Sheppard, minister of the Parish of Muirkirk, in Ayrshire, relates that: "A country gentleman from the West of Scotland, who lived in a parish very similar to Muirkirk, both in soil and climate, being occasionally in England for a few weeks, was one delightful summer evening asked out to hear the Nightingale, his friend informing him at the same time that this bird was a native of England, and never to be heard in his own country. After he had listened with attention for some time, upon being asked if he was not much delighted with the Nightingale, 'It's a' very gude,' he replied in the dialect of his own country, 'but I wadna' gie the wheeple of a Whaup for a' the Nightingales that ever sang.'"—*Old Statistical Account of Scotland*, vol. vii. p. 601.

solitary dreariness of the scene, that the wild cry of the Curlew, so much in accordance with all around me, has not come like the voice of a companion to my ear, and produced a delightful feeling of gratitude to that Being who has thus adorned with life and beauty the most sterile and least interesting of His works; and I have thought how great would be the void in the creation were we deprived of this one branch of His glorious productions.”¹

In the solitudes of the Lammermuirs the cries of the various birds which are found there—the oft-repeated “Peese-weep” of the Lapwing, the “Cok, cok, cok” of the Grouse, and the plaintive whistle of the Golden Plover—are drowned by the clamour of the Whaup when the wanderer intrudes upon its domain, reminding one of the lines of Leyden:—

How wild and harsh the moorland music floats,
When clamorous Curlew scream with long-drawn notes.

Mr. Hardy in his *MS. Notes* says: “At Penmanshiel Curlews call about six o’clock in the evening and carry on much later. Their first note is like “Powit, powit,” quickly pronounced—usually twice. When sailing or rising up and down it is “Powit,” slowly repeated, or the repetition of “Pööt-po-oit, po-oit.”

In Berwickshire and in other counties of Scotland this bird is called the “Whaup.” This seems to be an ancient name, for we find the Scottish Parliament in the time of Queen Mary (1551) enacting “that the wylde-meit and tame meit underwritten, be sald in all tymes cumming of the prices following:—the Quhaip, vl. d.” Jamieson in his *Scottish Dictionary* gives “Quhaip, Quhaup, Whaup,” as signifying a Curlew, and he also gives “Quhaip, Quhaup,” as

¹ *Eggs of British Birds*, vol. ii. p. 322.

the name of "a goblin or evil spirit, supposed to go under the eaves of houses after the fall of night, having a long beak resembling a pair of tongs, for the purpose of carrying off evil doers;" and he adds, "This goblin appears to have borrowed its name from the Curlew." The habit which this species has of flying about in the grey dark of evening, uttering its somewhat eerie cry, has doubtless associated the bird with goblins, witches, and the like. Sir Walter Scott in his *Black Dwarf* makes Hobbie Elliot say: "What needs I care for the Mucklestane-Moor ony mair than ye do yoursell, Earnscliff? To be sure, they say there's a sort of worricows and lang-nebbit things about the land, but what need I care for them?"

An amusing anecdote in connection with the Curlew is related by a gentleman in Berwickshire who had employed a village carpenter to fit up a glass case for a collection of stuffed birds in a room of his house. Going one morning to see how the work was proceeding, the carpenter, pointing to a number of birds which were standing on the floor at the opposite side of the room, said: "They're some funny-looking birds owre there. Now what d'ye ca' that yin wi the lang neb?" "Oh," said the gentleman, "that is a Curlew." "Oh aye," remarked the carpenter, "I mind when I was at the schule learnin, 'The Curlew tolls the knell of parting day.'" Dr. Henderson in his *Popular Rhymes of Berwickshire*¹ says that the people on the Lammermuirs are called "Lammermoor Whaups," as distinguishing them from the inhabitants of the lower districts.

The Curlew is found on the shores of Berwickshire about Oldcambus during autumn, winter, and early spring. It generally leaves the coast about the middle of March for

¹ *Popular Rhymes of Berwickshire*, p. 29.

the Lammermuirs, where it breeds, and towards the end of July it begins to return to the sea-side. As numbers of this species are seen passing the lighthouses¹ on the coasts of England and Scotland during spring and autumn on migration, it is probable that our Berwickshire birds receive additions to their numbers from these in spring, and that some of those which are bred in this county leave us in autumn for more southern regions, their places being filled up by the autumn migrants from the Highlands of Scotland or more northern climes.

The nest of the Curlew commonly consists of a slight hollow amongst short grass, heather, or rushes, lined with some dry bents or other similar material. The eggs, which are large and pear-shaped, are three or four in number, olive green, blotched and spotted with olive brown, and are generally placed in the nest with their small ends together.

The food of this bird when on the moors in summer consists of worms and insects,² while on the coast in winter it picks up sandworms and other small marine creatures.

On the ground the Curlew generally walks about in a stately manner, and as it is very wary and difficult to approach, I have seldom succeeded in stalking it. When in a flock the birds sometimes fly in the shape of an arrow-head, with a few of them straggling behind.

It is an excellent dish for the table when young and feeding on the moors. In the *Eclogues* of Alexander Barclay,³ which were written a few years after the battle of Flodden, the poet, referring to the dainty meats at that date, says a shepherd at court must not think to get "swanne nor heron,


¹ They frequently strike the lanterns of the lighthouses at night.

² Mr. Hardy in his *M.S. Notes*, dated the 9th of July 1842, says: "Lauderdale forester's opinion was that Whaups were no nice in their feeding, and eat snails and worms and they kind o' things."

³ Sibbald's *Chron. Scot. Poet.*, vol. ii. p. 426.

curlew nor crane," and he again includes it in the following list of delicacies :—

The crane, the fesaunt, the pecocke and curlewe,
The partriche, plover, bittorn, and heronsewe,
Seasoned so well in licour redolent,
That the hall is full of pleasant smell and sent.



*Q. S. M. The Curlew's Nest
1892.*

THE WHIMBREL.

LITTLE WHAUP, LITTLE CURLEW, TANG WHAUP, MAY FOWL,
HALF CURLEW, CURLEW JACK.

Numenius phæopus.

A bird of passage / gone as soon as found.

POPE.

THIS bird is very rarely seen in Berwickshire, there being only one instance recorded of its occurrence in the county. This was in the neighbourhood of Lambden, in the parish of Greenlaw, a fine specimen of a male having been shot there in the beginning of September 1874.¹

The Whimbrel much resembles the Curlew in its general appearance and habits, but it is considerably smaller in size, as its East-Lothian popular name of Little Whaup indicates.

Mr. Robert Gray says it is a well-known bird on the Dunbar coast in autumn when on migration southwards.² Seebohm says that, so far as is known, the only breeding places of the Whimbrel in the British Islands are in the Orkneys and Shetlands and the north of Sutherlandshire.³

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 287

² *Ibid.* vol. viii. p. 51.

³ Seebohm, *British Birds*, vol. ii. p. 100.



THE BLACK TERN.

STERN, SCARE CROW, BLUE DAB, CAR SWALLOW,
CLOVER-FOOTED GULL.

Hydrochelidon nigra.

*We hold our course o'er the deep, or the land,
O'er the swelling tide or weed-grown strand.*

ELIZA COOK, *Song of the Seagulls.*

THE only precise record of the occurrence of this bird in the county is by the late Dr. George Johnston, who, in his *MS. Notes*, kindly placed at my disposal by his daughter Mrs. Barwell Carter of The Anchorage, Berwick-on-Tweed, states that a Black Tern was taken at Springhill, near Coldstream, on the 9th of May 1851, the information regarding its capture having been communicated to him by Miss Anne Hunter.

This species formerly bred in great numbers in the eastern counties of England, but is now only a visitor to the British Islands on spring and autumn migrations.¹

Mr. Robert Gray says that it is rare on the Dunbar coast, only one or two examples having been shot there.²

¹ Yarrell's *British Birds*, vol. iii. p. 517.

² *Hist. Ber. Nat. Club*, vol. viii. p. 55.



THE COMMON TERN.

PICTARNIE, TARNEY, TARRET, PICKET, SPURRE, SCRAYE,
KIRMSU.

Sterna fluviatilis.

The Sea Swallow.

*We are safe and joyous when mad waves roll,
We sport o'er the whirlpool, the rock, and the shoal;
Away on the winds we plume our wings,
And soar the freest of all free things.*

ELIZA COOK, *Song of the Seagulls.*

THE Common Tern, which is a summer visitor to the shores of Scotland, is occasionally seen on the Berwickshire coast from May to September, where it may be easily distinguished from the Gulls by its smaller size and forked tail.

I have sometimes observed it near St. Abb's Head, whither it probably came from the Farne Islands, where it breeds in considerable numbers. The food, of this species consists chiefly of the fry of fishes, sand eels, and crustaceans.



THE LITTLE GULL.

PIGMY GULL, LITTLE MEW.

Larus minutus.

*Not down the breeze more blithely flew,
Skimming the wave, the light sea-mew.*

SCOTT, *Lord of the Isles.*

THERE are only two instances on record of the occurrence of the Little Gull in Berwickshire, and both of these were at Coldingham Loch. Mr. Hardy, in some notes on this bird, which are given in the *History of the Berwickshire Naturalists' Club*, says: "Mr. Andrew Wilson writes to me that a specimen of this rare occasional winter visitant was procured at Coldingham during the stormy weather in the end of December 1869, and is now in his collection."¹ In the same publication Mr. Andrew Brotherston, bird-stuffer, Kelso, writes: "I saw an immature specimen of this beautiful little Gull on the 16th of August 1877 at Coldingham Loch. All the time I was at the loch—about an hour—it was flying gracefully about, busy catching insects, frequently lifting them from the surface of the water, and only occasionally alighting for a few seconds. In its manner of flight it resembled the Sea Swallow, especially at a distance; indeed, the first sight I got of it I thought it was one of those birds. But on a nearer approach—and it came very near, not being in the least shy or afraid—the square tail showed the difference at once. The Little Gull in the collec-

¹ *Hist. Ber. Nat. Club*, vol. vi. p. 84.

tion of the late Mr. Wilson of Coldingham, and which was in similar plumage, was obtained at the same place."¹

This species is an irregular visitor to the shores of the British Islands on migration and in winter. In summer it feeds chiefly on insects, which it catches on the wing, and in winter it picks up small marine creatures of various kinds by the sea-shore.

Like our own well-known Black-headed Gull, the Little Gull nests in large colonies on lakes and marshes, its best-known breeding quarters being near Lake Ladoga, in Russia.

¹ *Hist. Ber. Nat. Club.*, vol. viii. p. 522.



THE BLACK-HEADED GULL.

PICMAN, PICTARNIE, PICKMIRE, PEWIT GULL, LAUGHING GULL,
BLACK-CAP GULL, BLACK-CAP, HOODED MAW, RED-
LEGGED GULL, MIRE-CROW, SEA-CROW.

Larus ridibundus.

The Pickie, The Pickiemaw, The Pictarnie,
The Peg-bitnet.

*Perfytelie thir Pikmawis, as for priowris,
With thar party habitis, present tham thar.*

HOLLAND'S *Houlat*, circa 1453.

"What do you see extraordinary about that bird, Hector? It's but a seamaw."
"It's a Pictarnie, Sir," said Edie.

SCOTT, *Antiquary*.

OWING to the drainage of many of the pools and marshes which formerly abounded in Berwickshire, the breeding quarters of the Black-headed Gull in the county have been considerably reduced in numbers since the beginning of this century, but several nesting stations still remain. Of these the most important are the Everett Moss, in the parish of Legerwood, and Bemersyde Loch, in the parish of Merton. The Everett Moss, which is also known as the Pickie Moss, Dowie Den Moss Loch, or Legerwood Loch, is situated about a mile to the north of Legerwood, where, on looking eastwards from the rising ground near the road, it may be seen lying in a hollow in the foreground, with the top of old Corsbie Tower peering above the trees a mile further in the same direction, and Home Castle in the distance keeping watch over the Merse. The

loch, which extends to about twelve acres, is surrounded by flat marshy ground on the north and west; whilst a fir wood of considerable size forms its southern boundary. In summer the surface is almost completely covered with sedges, rushes, and other aquatic plants, through which broad lines of open water appear winding about. Here the Black-headed Gull finds a congenial breeding place, and on approaching the loch during the nesting season it may be seen on the wing in immense numbers¹ wheeling round and round in circles over the swamp, while little can be heard but its incessant cackling screams. The nests, which are placed amongst the rough herbage of the loch, are so numerous that it is said that upon one occasion as many as sixty dozen of eggs were taken in a night by people from the neighbouring farms, who sold them to the district carrier for 4d. per dozen. The eggs vary in number from two to three, and are greenish olive-brown, blotched with dark umber. The Gulls generally begin to return to the loch from the sea-side,² where they have spent the autumn and winter months, about the end of February or beginning of March, and nesting operations commence in May. The young, which are distinguished by grey marks on their plumage, may be seen on the wing with their parents in July, and towards the end of that month, or in the beginning of August, the loch is deserted by the Gulls, which then leave their breeding quarters and frequent the sea-shore until the following spring. I have been favoured by Mr. John Thomson with the following account of Bemersyde Loch, which, as already mentioned, is another breeding station of the Black-headed Gull in

¹ Mr. James Smail, referring to the Gulls at Legerwood Loch, says: "When startled from their nests they are so numerous that they rise on the wing like a white cloud."—*Hist. Ber. Nat. Club*, vol. viii. p. 105.

² Mr. Hardy says that about Oldcambus the Black-headed Gull leaves the coast in March and begins to return about the middle of July.—*M.S. Notes*.

Berwickshire :—" From time immemorial water-fowl have found a congenial haunt in Bemersyde Loch. In the summer time this stretch of swampy ground at the present day hardly merits the name of loch, for by drainage its dimensions have been gradually reduced until it has become a boggy hollow, the greater portion of which is covered by a luxuriant growth of sedges, reeds, rushes, and many other water-loving plants. The spaces of open water are very insignificant. In winter it attains greater proportions, and, rising to a considerable height, forms a pretty sheet of water. It lies in the northern portion of the parish of Mertoun and close to the Third, where, in former days, stood a peel tower in which members of the ancient family of Haig were wont to reside. Not far off were the towers of Brotherstone, Whitrig, and Sandyknowe, the last only remaining. The loch lies in a hollow where the properties of Mertoun and Bemersyde join, and on more than one occasion it had been the cause of strife and bitter feeling between the proprietors of the two estates until 1678, when it was divided between Dryburgh and Bemersyde. This division continued for two hundred years, but in 1879, by an amicable arrangement between Mr. Erskine and Colonel Haig, the latter purchased the half of the loch severed in 1678; thus the entire loch, as it now exists, belongs to Bemersyde. Judging from the conformation of the ground the loch must have been formerly of very considerable extent and depth. The first drainage operations were most probably carried out during the lifetime of Anthony Haig, the 18th laird of Bemersyde. Drainage has in more modern times greatly reduced its level and contracted its boundaries; still there are yet over fifty-five acres partially covered with water or liable to complete submersion. It is a favourite breeding haunt of the Black-headed Gull, and about fifteen hundred pairs

annually resort thither to rear their young. They are seldom disturbed. Large numbers of Wild Ducks, Water Hens, Coots, Snipes, and Lapwings nest there; Herons are frequent visitors, and the Bittern is a tradition. In winter the loch is the haunt of immense flocks of wild-fowl, including the Wigeon, Teal, Wild Duck, Pochard, Golden-Eye, and Goosander; Wild Geese visit it, and Swans have been occasionally seen and oftener heard. Whitrig Bog, on Lord Polwarth's estate, is close at hand, and with the exception of the Gulls it has always a share of the birds above noted."

During spring, when ploughing and sowing operations are in progress, the Black-headed Gull is frequently seen in the neighbourhood of its haunts, following the ploughmen in large flocks to pick up any grubs and worms which may be turned up.

An' whan the year smiles, an' Lav'rocks sing,
 My man Jock an' me shall be doin' o't;
 He'll thrash, an' I'll toil on the fields in the spring,
 An' turn up the soil at the plowin' o't.
 An' whan the wee flow'rets begin then to blaw,
 The Lav'rock, the Peasweep, an' skirling Pickmaw,
 Shall hiss the bleak winter to Lapland awa,
 Then we'll ply the blythe hours at the sawin' o't.¹

In the summer months the Black-headed Gull is often seen frequenting the Tweed in small flocks, and it is also observed on the Leader. Mr. Hardy, in his interesting account of a meeting of the Berwickshire Naturalists' Club, which was held at Ednam on the 30th of May 1883, says with reference to Birgham: "The celebrated historical haugh stretches away in a spacious open plain bounded and encircled by the broad Tweed, whose waters, flashing in the sunlight, are skimmed by the Black-headed Gulls, engaged in the pursuit of minnows or water insects, their lively forms finely relieved

¹ *Poems, chiefly in the Scottish Dialect*, by Andrew Scott, Bowden, 1811.

against the brightness.”¹ It may also be observed haunting the streams immediately below Coldstream Bridge in search of prey, where its sprightly and graceful motions lend additional beauty and interest to the lovely scenery. Mr. Lockie remarks that it frequents the Leader about Earlston.

This species appears to be omnivorous, but its chief food consists of earthworms, grubs, wire-worms, insects, crustaceans, molluscs, and small fish.

During the winter the head of this Gull is white, streaked with grey, and there is a patch of grey before the eye and behind the auricles. In March the head and upper part of the neck become dark-brown, making the bird look as if it had a black cap on its head; hence several of its local names. Both Yarrell and Seebohm state that the feathers of the head actually change colour in spring, and do not moult. Mr. Andrew Brotherston, bird-stuffer, Kelso, says: “That it is the result of moulting, in some cases at least, I am thoroughly satisfied. On the 15th of March 1876 I examined the head of an adult male, in which the change was nearly completed, only a few scattered white feathers were left, all of which were old and easily detached, so much so that, excepting a few at the base of the bill, they came off when I was skinning the bird. The black feathers, on the contrary, were all young, new, and in various stages of growth, some fully developed, others just appearing. I examined several examples of the same species in March 1877, all of which showed unmistakable signs of moulting on the head, and also on the rest of the body, excepting the large feathers.”²

The late Dr. Colville Brown of Berwick writes on the 9th of April 1879: “For the last three years I have closely watched the change of colour in the Black-headed Gull, and I am now quite convinced this proceeds from moulting and

¹ *Hist. Ber. Nat. Club*, vol. x. p. 253.

² *Ibid.* vol. viii. p. 187.

not from the feathers altering in hue. This happens earlier or later, just as the spring is early or late. In 1877 I observed many Gulls with the brown tinge quite as distinct in the end of January as I did this year at the end of February, and precisely in the same way does the weather affect their departure from the sea-side to their inland haunts. In warm springs they go away early; in cold they remain three or four weeks later with us. Some individuals put on their dark head-dress earlier than others, and these are the first to take their departure. The moult itself begins on the occiput, and spreads over the top and sides of the head; and the slaty-black feathers behind the eye are also shed, and replaced by the sooty-black feathers common to the whole head.”¹

Mr. Robert Gray mentions that an albino Black-headed Gull of pure spotless white was shot near Cockburnspath in 1874.² Amongst former breeding quarters of the Black-headed Gull in the county, which are now deserted, the following may be mentioned: Billie Mire,³ the “Hen Poo”⁴

¹ *Hist. Ber. Nat. Club*, vol. viii. p. 531.

² *Ibid.* vol. vii. p. 466.

³ Mr. Alexander Nisbet, rabbit-catcher, Chirnside, informed me on the 22nd of May 1886 that he was born at Blanterne in 1819, and that Mr. John Allan, Billie Mains (father of Mr. John Allan of Peelwalls), had frequently told him that when he (Mr. John Allan, sen.) was a boy he used sometimes to wade into the water at Billie Mire for Picmaws' or Pickies' eggs. This would be about the beginning of this century.

⁴ Mr. William Duns, Duns, told me on the 20th of May 1886 that, down to about 1835, thousands of Pictarnies used to frequent the “Hen Poo” in the breeding season; and that about 1825, when St. Mary's Cottage at the north end of the lake was being built, the workmen engaged at the cottage used to place a long ladder between the edge of the water and the islands on which the Gulls had their nests for the purpose of procuring the eggs, which they ate. The islands were completely covered with the nests, and great baskets of eggs were collected and brought to Duns. Some years after this the late Mr. Hay caused fires to be kept burning on the islands during the nesting time of the Gulls, and this had the effect of completely driving the birds away. Mr. Hay did this because he disliked the great noise which they made by their screams when they were flying in clouds over the lake. It must have been subsequent to 1842 when the Gulls were banished, for I find Mr. Hardy in his *M.S. Notes* writing in June of that year as follows: “At this period the Pickies or Pictarnies built in abundance on one island in the ‘Hen Poo’ at Duns Castle, and that the eggs were taken by using a boat to reach the island.”

at Duns Castle; Dogden Moss,¹ in the parish of Greenlaw; Corsbie Bog,² on the borders of the parishes of Legerwood and Gordon; and Redpath Bog, in the parish of Earlston.³

There is a field on Shannobank Farm, near Abbey St. Bathans, called the "Gull Mire," and as it has the appearance of having been a swamp at one time, it was probably a breeding place of the Black-headed Gull formerly before it was drained.

¹ On the 24th of April 1886 the farm steward at Harelaw, near Westruther, mentioned to me that before the Dogden Moss was drained great numbers of Black-headed Gulls used to breed there every year. He had seen them twenty years ago. This Moss is mentioned by the late Dr. Henderson in his *Popular Rhymes of Berwickshire*, p. 68:—

Lift one, lift a',
Baith at back and fore wa';
Up and away wi' Langton House,
And set it down in Dogden Moss.

² "Corsbie Moss was once the haunt of the Black-headed Gull, but has been deserted since it was drained."—*Hist. Ber. Nat. Club*, vol. ix. p. 236.

³ Mr. Brownlie, Haugh Head, Earlston, wrote to me on 27th October 1887: "An old man named Sandy Boyd, who lives at Redpath, says that when he was a boy the bog there used to be white with Pickiemaws. This would apply to fifty years ago."



THE COMMON GULL.

SEA-MAW, MEW OR MALL, SEED BIRD, GREEN-BILLED GULL.

Larus canus.

The Gull Maw.

*Moor, moor the barge, ye gallant crew !
 And, gentle ladye, deign to stay !
 Rest thee in Castle Ravensheuch,
 Nor tempt the stormy firth to-day.*

*The blackening wave is edged with white :
 To inch and rock the sea-mews fly ;
 The fishers have heard the Water-Sprite,
 Whose screams forebode that wreck is nigh.*

SCOTT, *Lay of the Last Minstrel.*

DURING the autumn, winter, and spring months the Common Gull occasionally comes in flocks from the sea-coast to the interior of the county, where it frequents land which is being ploughed, and grass fields, feeding upon worms and grubs. Its sudden appearance inland in large flocks is, however, looked upon by the country people as a sure sign of an approaching storm of wind and rain, and this has given rise to the following rhyme which is sometimes repeated by children in Berwickshire, as well as other parts of Scotland :—

Sea Gull, Sea Gull, sit on the sand,
 It's never good weather when you're on the land.

Dr. Henderson of Chirnside, in his *Popular Rhymes of Berwickshire*, mentions the following curious superstition : Maggie Shaw's Crockie is a broad, flat stone, about a mile to the north of Eyemouth. This stone was placed over the

remains of an old woman who hanged herself, and who, in the shape of a white Sea-Maw, is said to be frequently seen at night—sitting on the

“glitty stane,
Green wi’ the dew o’ the jaupin’ main.”

“Cold blows the stormy wind,
The waves are rushing loud;
The moon is in the wane—
No star looks through the cloud;
High on yon bare, cold rock,
Old Maggie sits alane;
Ilk night at twal o’clock,
She sits upon the stane.”

The Common Gull does not breed upon any part of the Berwickshire coast at the present time.

The well-known ornithologist, P. J. Selby, mentions in a “Notice of the Birds observed in the neighbourhood of St. Abb’s Head on 18th July 1832,” which was read to the members of the Berwickshire Naturalists’ Club on the 19th of September in the same year, that “this bold headland is also the great breeding station of *Larus Canus*, or the Common Sea-Maw; it affects the upper ledges and recesses of the precipices, and was observed in great numbers, but so shy as not to be approached within gunshot. The *Larus rissa*, or Kittiwake, is also numerous, but does not breed in company with the other, selecting in preference the small projecting angles, which barely admit of room for the reception of their eggs and young.”¹ In a paper on “Observations on the Birds observed in the neighbourhood of Cockburnspath in April and those at St. Abb’s Head in June 1833,” read to the same Club on the 17th of July 1833, Selby again repeats the statement that the Common Gull then bred at St. Abb’s Head, for he says: “This species [the Herring Gull—*Larus argentatus*] had not been observed during our

¹ *Hist. Ber. Nat. Club*, vol. i. p. 19

excursion in July 1832, having taken its departure from those haunts previous to our visit, the Common Gull (*Larus Canus*), which breeds in great numbers on the rock to the south of the Head, being the only species then visible.”¹

Mr. Archibald Hepburn, in his “Notes on some of the Mammalia and Birds found at St. Abb’s Head,” writes: “On the 20th of June last [1851], accompanied by my friend, Mr. Robert H. Broughton, I hired a boat at Coldingham Shore to visit St. Abb’s, for the purpose of procuring specimens of birds and making observations on their habits and distribution along the coast. No Common Gulls (*Larus Canus*) breed about the Head, but there is a most extensive colony on the Ernesheugh, about two miles to the westward; their nests are placed on the grassy ledges; and although these birds abound on the eastern shores of East-Lothian and Berwickshire throughout the year, yet this is the only breeding place known to me in the south-east of Scotland.”²

Mr. Howard Saunders, in vol. iii. of the revisal of Yarrell’s *British Birds*, 1882-84, pp. 613, 614, says with reference to the breeding of the Common Gull (*Larus Canus*) on the coasts of England: “During the summer the ‘common’ species are either the Herring Gull or the Kittiwake; and, without making any dogmatic assertions, the editor can safely say that during the past twenty years in which his attention has been given to the question, he has failed to obtain any proof whatever of the nesting of *Larus Canus* on any part of the English coast. Nor is the evidence satisfactory as to the asserted nesting of this species in the cliffs of St. Abb’s Head, or, indeed, in any precipitous cliffs whatever, in the ordinary acceptation of the words. The Common Gull selects, as a rule, the comparatively low shores of small islands, either on the sea-coast or up the arms of the sea; and it is also partial to grassy islands in lochs; but although

¹ *Hist. Ber. Nat. Club*, vol. i. p. 21.

² *Ibid.* vol. iii. p. 75.

its nests may be found on broken ground, or even on small crags, yet flat surfaces are far more to its taste." Mr Seebohm, in his *British Birds*, vol. iii. p. 317, states that "the Common Gull (*Larus canus*) is intermediate in its habits between the inland and marine species; it breeds indifferently on an island off the coast or on the cliffs of the mainland, and is equally satisfied with an island on an inland lake, or the banks of a mountain tarn." The fact that the Common Gull (*Larus canus*) is not found breeding on any part of the Berwickshire coast at the present day does not prove that Mr. Selby and Mr. Hepburn—two well-known and experienced ornithologists—were wrong in their statements as to its breeding about St. Abb's Head in 1832 and 1851, for, like the Kittiwake, which formerly nested there in large numbers, and is not now found breeding on any part of the Berwickshire coast, it may have deserted that locality as a breeding station. Mr. Hepburn states distinctly that, when he visited St. Abb's Head on the 20th of June 1851, there was "a most extensive colony of *Larus Canus* on the Earnsheugh, about two miles to the westward," and that "their nests are placed on the grassy ledges."¹

On the 27th of September 1887 I wrote to Mr. Hepburn on the subject, and on the 4th of October following he replied: "I beg to assure you that I adhere to the accuracy of the statements contained in the article on 'Some of the Mammalia and Birds found at St. Abb's Head,' *Hist. Ber. Nat. Club*, vol. iii. p. 75, and I may add that I always found Dr. Johnston a faithful and attentive editor of the papers submitted to the Club; also, that the Common Gull was a frequent visitor to my native fields in the interior of East-Lothian; that the Herring Gull was common along the sea-shore, and several pairs bred on the Bass Rock, and I had in my early days three pets of this species."

¹ *Hist. Ber. Nat. Club*, vol. iii. p. 75.

THE HERRING GULL.

GULL MAW, WILLIE GOW, CAT GULL, SILVERY GULL.

Larus argentatus.

The Gull Maw, The Common Gull.

*Bold-winged sea-bird ! why so lonely straying
 Far from thy rocky home,
 Round which the wild sea-breezes still are playing
 Above the ocean foam ?*

*Say ! dost thou hail from yonder cliffs so hoary—
 From yon rude caverned halls,
 Where strong Fast Castle, famed in olden story,
 Still lifts its ruined walls ?*

WALTER CHISHOLM.¹

THIS Gull is more plentiful on the sea-coast of Berwickshire than any other kind, and is found there at all seasons of the year. It is, however, to be seen in the greatest numbers about St. Abb's Head, where its harsh, cackling cries fill the air during the breeding season.²

Proceeding round the sea-coast from Lamberton on the eastern boundary of the county to the Cove, towards Cockburnspath on the western limit, the first breeding station of the

¹ Mr. Walter Chisholm in his boyhood resided for some years at the upland farm of Dowlaw, near Fast Castle, and here, at the early age of twenty-one, he died on the 1st of October 1877. His poems, edited by Mr. William Cairns, formerly of Oldcambus, are published by Mr. Thin, Edinburgh.

² Mr. Archibald Hepburn, in his "Notes on Birds found at St. Abb's Head," *Hist. Ber. Nat. Club.*, vol. iii. pp. 74, 75, says, with regard to the cries of the Herring Gull: "their hoarse guttural cackle resembling Kaak-ka-kaak, varied only by a sharp loud scream like 'Pee-ul,' filled the air." Mr. Hardy, in his *M.S. Notes*, compares the cries of some Gulls of this kind, which he heard at Fast Castle on the 12th of June 1877, to those of a cat.

Herring Gull which we reach is a high rock on the shore, about a mile north of Burnmouth village, called the "Gull Rock." Here a considerable number breed, and a few nests are found at Bleak Heugh, a rocky precipice about half a mile further north. There are no colonies of this Gull between Bleak Heugh and the Lighthouse on St. Abb's Head, but on the rocks below the Lighthouse there are a few scattered nests, and we next find it rearing its young on the Cleaver Rock. A short distance further west is Foul Carr, a great precipitous rock standing out in the sea near the part of the Head called the Rampart, and here we find the principal breeding quarters of the Herring Gull on the Berwickshire coast. A fine view of the western slope of the top of this rock with its turfy ledges, where the gulls have their nests, and where they are seen sitting in numbers during the breeding season, may be had from the edge of the cliff immediately to the north-east of the ruins of St. Abb's Nunnery. From this point I have frequently watched them with a binocular as they sat on their nests or tended their young, and from it the vignette at the end of this article was taken on the 20th of July 1887. About a hundred yards westwards the Little Channeler Rock juts out into the sea, and there another colony of this species is found breeding. Immediately to the north-west of the Little Channeler stands the lofty rocky island of Skelly, forming the most northern point of Berwickshire, with Flot Carr adjoining it. On the northern precipices of both of these rocks the Herring Gull nests. Passing the pretty little harbour of Petticowick and Broadhaven Bay we reach West in Thirle Bay, where on the grassy ledges of the Ravensheugh and Thrummie Carr a few more nests of this bird are observed. Further to the west on the rocks below the Uilystrand Brae and at Snuffiehole Stells more occur, also at Maw Carr. Before reaching the Brander Cliffs, where

there are some more nests, we pass the Moor Baits¹ and Dowlaw Burn Foot, where a few nests are seen on the rocks between the Standing Man and the Big Byrips. We now reach the ruins of Fast Castle,² where on looking westward on a clear day the view is magnificent, embracing the Bass, North Berwick Law, and the adjoining coast of East-Lothian. The situation of the castle is very lonely, and around its decaying walls the only sounds now to be heard are the constant beating of the waves on the rocky coast,

Mix'd with the seafowl's shrilly moans.

SCOTT.

Rounding the point at Fast Castle we see the Black Mask Rock with a number of Herring Gulls' nests upon it, and still keeping westwards we pass Geddes' Haven and the Little Rocks, and then we reach the Gull Rock and Maw Craig, near the mouth of the Wolden Lee Burn, the most westerly breeding places of the Herring Gull on the Berwickshire coast.³ This point is about three-quarters of a mile to the west of Fast Castle.

The nest of the Herring Gull is formed of grass and moss, and the eggs, which are generally three in number, are light olive-brown or greenish, blotched and spotted with dark umber. Many years ago the eggs of this and other Gulls

¹ Mr. Robert Darrie, fisherman, Coldingham Shore, informed me, on the 29th of June 1887, that this was such a favourite spot for fishing for codlings that the following rhyme is sometimes heard amongst the fishermen:—

Come ye soon, or come ye late,
Ye'll a codlin get at Moor's Bait.

² Here the Princess Margaret, daughter of Henry VII. of England, slept on the night of the 1st of August 1502, when on her way to Edinburgh from Lamberton Kirk, where she had been betrothed to James IV. of Scotland. About a hundred years later the gloomy fortress was the scene of dark plots in connection with the Gowrie Conspiracy, for here Logan of Restalrig resided. Fast Castle is the "Wolf's Crag" of *The Bride of Lammermuir*.

³ This Gull is, however, occasionally found breeding further westwards. Mr. Hardy notes, under date 30th June 1886: "A Herring Gull's nest was found yesterday by Professor Lebour's pupils on rocks near Siccar—between it and Redheugh."

were eagerly sought after by some of the fishermen on the Berwickshire coast, but now they do not appear to go often on egging expeditions. Mr. Hardy notes that about forty years ago "the fishers at Burnmouth went twice a week in 'Gull time' round the rocks which the Gulls frequent to get their eggs. They sometimes got as many as eighty or ninety in a morning, and found them quite as edible as hen eggs. About the above-mentioned time a very adventure-some boy named Kerr—son of William Kerr, fisherman, Burnmouth—was killed by falling from a steep yellow-coloured rock called Dunkirk, on Fairneyside Farm. He was hung round with eggs in handkerchiefs, and had a bonnetful also, when the portion of the rock he held by proved treacherous and down he fell on the black rocks below and was killed. The only expression his three companions heard was 'ae Johnnie.' Some time before this two boys were killed at St. Abb's Head by falling over the rocks when in search of Gulls' eggs. The first notice which the mother of one of them got of the accident was from the children who had gone with him to the Head coming home crying."

The food of the Herring Gull consists of fish, crustaceans, star-fishes, and other marine creatures.¹ It likewise feeds upon dead fish and other garbage cast ashore by the waves, and also eats eggs. Mr. Hardy has known it to feed upon the fragments of a bottle-nosed whale which had been carted to the fields at Oldcambus for manure; also under date 1st September 1868, he writes: "At present when the sea is rough the Herring Gulls are sitting on the oat stubble, and sometimes I see them seated on the stooks. At Siccar

¹ Mr. Robert Gray writes: "I have repeatedly observed that on the Berwickshire coasts and elsewhere Herring Gulls, and especially young birds, feed to a great extent upon star-fishes. One of which I shot on the 11th of September vomited, when it fell, ten specimens of *Asterias rubens*, two of which measured nearly three inches across the rings."—*Hist. Ber. Nat. Club*, vol. vii. p. 466.

Point, where they sit on the rocks, amongst their droppings are large quantities of oat husks, mixed here and there with mussels and limpets and shells of *Purpura lapellus*; they seem to feed much upon limpets, and hence frequent the rocks where these are found."

This Gull derives its common name from its habit of following shoals of herrings, whose presence off shore is indicated by its hovering over them in flocks, and every now and then dropping to the water and capturing a fish, reminding us of the following lines of Charlotte Smith:—

And hosts of sea-birds, clamouring loud,
Scent with wild wing the welcome shoal,
Swift o'er the animated current sweep,
And bear their silver captives from the deep.

Captain Norman, R.N., of Cheviot House, Berwick-on-Tweed, has favoured me with the following interesting note: "While walking along the cliff edge between Burnmouth and Eyemouth on the 16th of August 1887 my attention was arrested by the large number of Gulls which were clustered at intervals along the coast. I suspected that these birds marked the position of the fixed nets for salmon, and that they were waiting for the appearance of an inshore shoal of herring, which turned out to be the case. Taking my station, binocular in hand, above the site of one of the nets, I awaited the course of events. I had not long to wait, for in a few minutes the water seemed quite alive with silvery herrings, whose passage along shore had been interrupted by the curtain of the net, or that part of it with which the salmon first come into contact, and which turns their course. The Gulls became very much excited, and were soon in the midst of the shoal by hundreds."

In winter and spring this species is occasionally seen in the interior of the county, where it frequents the grass fields and ploughed land to search for worms and grubs. Its

appearance in numbers in the inland parts is considered to be an indication of the approach of tempestuous weather, as mentioned by Grahame in his *British Georgics* :—

No sign of gathering storm, both wind and rain,
Is surer than the sea-fowl's inland flight.

Sir David Lindsay, in his *Complaynt of Scotland*, also alludes to this Gull foretelling stormy weather, for he says :
“The Swannis murnit because the gray goul mau pronosticat
ane storme.”

The Herring Gull is sometimes kept as a pet in gardens, and Mr. Hardy relates that “one which belonged to Mr. William Calder, Gunsgreen, used to go down to the water Eye to wash itself and then returned. A boy in Ayton kept one for a long time, and it used to fly daily to the Eye to wash itself, returning on buoyant wing to the heart of the village. Boys about Oldcambus sometimes catch Gulls by placing a worm on a fishing-hook with a long string attached to the hook.”



THE LESSER BLACK-BACKED GULL.

YELLOW-FOOTED GULL.

Larus fuscus.

The Gull Maw.

*As wave meets wave within some rocky bay,
 When varying currents hold their whiten'd way;
 When the shrill sea-mew with unwearied cries,
 Skimming the sea with restless pinion, flies;
 When deep'ning clouds foretell the wintry gale,
 And the gaunt mariner clews up the sail.*

SCAFFE'S *King Coal's Levee*, p. 35.

THIS species is seen in small numbers on the coast of Berwickshire at all seasons of the year, and a few pairs breed on the Cleaver Rock, Foul Carr, and other precipices about St. Abb's Head in company with the Herring Gull. It occasionally visits the Tweed and the Whitadder¹ in winter and spring. It feeds chiefly upon small fishes and dead animals thrown on shore by the tide.

The nest is made of dry grass, and contains two or three eggs, which vary in colour from yellowish-grey to olive-brown, with spots of purplish-grey and dark-brown.

The feet of this Gull are yellow; hence the proverb: "As yellow as a gull's fit."

¹ On the 4th of April 1887 I observed a pair of Lesser Black-backed Gulls sitting on the gravel at the junction of the Dye and the Whitadder,



THE GREAT BLACK-BACKED GULL.

BLACK-BACK, CARRION GULL, GULL MAW.

Larus marinus.

Gull Maw.

*The sea-birds shriek above the prey,
O'er which their hungry beaks delay.*

BYRON.

THIS large Gull is occasionally seen on the Berwickshire seaboard, chiefly in the neighbourhood of St. Abb's Head, but it is not found breeding on any part of the coast of the county at the present time. Mr. Archibald Hepburn, in his "Notes on some of the Birds found at St. Abb's Head in June 1851," says: "The boatman informed me that a single pair of the Great Black-backed Gull (*Larus marinus*) breeds annually on the Flood Carr,¹ adjoining the Skelly Rock. The Bass can likewise boast of one or two pairs of these noble birds."² About 1855 Mr. Wilson of Coldingham gave Mr. Hardy a list of birds which were then found at St. Abb's Head, and in it this species is mentioned as frequenting that locality, but seldom nesting there.

The large size, black back, and loud harsh cry of this Gull easily distinguish it from any of its congeners. Its flight is very powerful, and it seldom allows itself to be approached within gunshot, being very wary. It feeds on fish, carrion, and garbage thrown on shore by the tide; it is also very destructive to eggs, and robs the nests of Guillemots and other birds.

¹ Called also Flot Carr.

² *Hist. Ber. Nat. Club*, vol. iii. p. 74.

THE GLAUCOUS GULL.

BURGOMASTER, GOLDEN MAW.

Larus glaucus.

*Not swiftly—but as fly
The sea-gulls, with a steady, sober flight.*

BYRON, *Don Juan.*

DURING winter this large Gull is frequently seen on the coast of Berwickshire, but generally in immature mottled plumage, in which stage, Mr. George Bolam remarks, that, even at a distance, it may be distinguished from the young of the Great Black-backed and other Gulls by its steady, soaring flight.¹ A young bird was shot at Eyemouth on the 19th of December 1882.²

The Glaucous Gull breeds in the arctic regions, and is only a winter visitor to the British Islands. It is a greedy and voracious bird, and feeds largely upon carrion and garbage of all kinds. It frequently robs other Gulls of their prey.

¹ *Hist. Ber. Nat. Club*, vol. ix. p. 170.

² *Ibid.* vol. x. p. 200.



THE KITTIWAKE GULL.

BLACK-FOOTED KITTIWAKE, ANNET, TARROCK.

Rissa tridactyla.

The Kittiwake, The Cirlee.

*Above, around, in cloudy circles wheel'd,
Or sailing level, on the polar gale
That cool with evening rose, a thousand wings,
The summer nations of these pregnant cliffs,
Play'd sportive round, and to the sun outspread
Their various plumage, or in wild notes hail'd
His parent-beam.*

MALLET, *Amyntor*.

THIS beautiful Gull formerly bred in great numbers on the high precipitous rocks at St. Abb's Head, but does not now nest on any part of the Berwickshire coast. Mr. John Renton of Chesterbank, who in 1794 wrote the report on the parish of Coldingham for the *Old Statistical Account of Scotland*, says, with regard to the sea-fowl which were then found in that parish: "There is also a prodigious number of sea-fowls known by the name of Scouts and Kittiwakes, with a mixture of Sea Gulls, that arrive in the spring yearly upon the high and inaccessible rocks on the south side of St. Abb's Head. They breed incredible numbers of young, and when the young are ripe, but before they can fly, the gentlemen in the neighbourhood find excellent sport by going out in boats and shooting great numbers of them; when they are killed or wounded they fall from the rocks into the sea, and the rowers haul them into their boats. Their eggs are pretty good, but their flesh is very bad, yet the poor people

eat them. They leave the rocks about harvest, and none of them are ever seen here before the next spring.¹ Selby, in his "Account of the Birds observed at St. Abb's Head on the 18th of July 1832," which appears in the first volume of the *History of the Berwickshire Naturalists' Club*, remarks that: "The *Larus rissa* or Kittiwake is also numerous, but does not breed in company with the other [*Larus canus*], selecting in preference the small projecting angles, which barely admit of room for the reception of their eggs and young."² The next notice of the Kittiwake on the Berwickshire coast is by Mr. Archibald Hepburn, who, in his "Notes on some of the Mammalia and Birds found at St. Abb's Head on the 20th of June 1851," says: "Next to the foolish Guillemot, the Kittiwake (*Larus tridactylus*) is by far the most numerous bird about the Head. Unlike the other species of gull found here, they showed no preference for the tufts of grass growing on the precipices, but built their nests in crevices or ledges of rock, sometimes solitary or in small colonies, which again were occasionally distinct from, and at other times intermingled with, the nests of the Guillemot. This gull derives its name from its well-marked cry, 'Kitty-week,' sharp stress being laid upon the last syllable when the bird is angry or alarmed."³ Macgillivray, writing in 1852, mentions St. Abb's Head as one of the principal breeding stations of the Kittiwake in Scotland.⁴ About 1855 or 1856 the late Mr. Andrew Wilson of Coldingham gave to Mr. Hardy, Oldcambus, a list of the birds which were then found breeding at St. Abb's Head, and in it this species is mentioned as nesting at Skelly, Foul Carr Rib, and the Rampart. About 1857 Mr. Hardy submitted the list to Mr. Francis Purves, who was well acquainted with the birds at

¹ *The Statistical Account of Scotland*, by Sir John Sinclair, Bart., vol. xii. p. 57.

² *Hist. Ber. Nat. Club*, vol. i. p. 19.

³ *Ibid.* vol. iii. p. 74.

⁴ *History of British Birds*, vol. v. p. 518.

St. Abb's Head, and in commenting upon it Mr. Purves noted that "the Kittiwake has deserted the Skelly and Foul Carr Cove or Rib, and now chiefly resorts to the Ramparts. This is since they were so much tormented by the large Newcastle steamboats calling in and firing at them. They are also fewer in number." Under date August 1857, Mr. Hardy writes in his *MS. Notes*: "Kittiwake dwindling away at St. Abb's Head; this is supposed to be on account of their being so much shot at by the London and Leith steamers." On the 11th of August 1886, when I was on a visit to St. Abb's Head for the purpose of marking on the twenty-five inch Ordnance Survey Map of the coast the breeding stations of the various birds which are found there, Mr. Robert Thorburn, fisherman, Coldingham Shore,¹ informed me that the Kittiwake reared its young numerously on the perpendicular precipices of the Cleaver Rock long ago, but that none had bred about St. Abb's Head for the last twenty years. It would thus appear that between 1857 and 1866 the Kittiwake gave up nesting there.


This species is now found in small numbers on the coast of Berwickshire during the winter and early spring months,² and is occasionally seen on the Tweed, but it is not observed in the inland districts of the county frequenting the grass fields or ploughed land, like the Common and the Herring Gulls. Its great breeding stations in the vicinity are the Bass Rock and the Farne Islands, where it arrives in vast numbers in spring. After the nesting

¹ Mr. Thorburn told me that he was seventy-seven years old, and had fished about the Coldingham coast all his life; also that he had accompanied the "Sappers and Miners," when they surveyed the coast at St. Abb's Head about 1857, to tell them the names of the rocks. He appeared to be well acquainted with the breeding places of the birds about the Head.

² Mr. Hardy notes under date 25th March 1874: "A number of Kittiwakes associated in a party with Common Gulls on the Pease Sands."—*Hist. Ber. Nat. Club*, vol. vii. p. 279. Also on 21st December 1874: "Kittiwake seen passing on the sea banks."—*Ibid.* vol. vii. p. 282.

season most of the birds proceed southwards, only a few remaining to spend the winter, but it is supposed that the latter are supplemented by others migrating from the north.

The food of this Gull consists chiefly of small fishes and other soft marine animals.



THE POMATORHINE SKUA.

Stercorarius pomatorhinus.

*From the frozen north, where Winter's hand
With sway despotic and untam'd locks up
The shrinking world; o'er the wide ocean borne
On vig'rous wing, pour forth the feather'd tribes
Diverse and strange.*

REV. JOHN VINCENT, *Fowling.*

IN the autumn months this visitor from the arctic regions is occasionally seen on the coast of Berwickshire, where, in the middle of October 1879, great numbers were observed, as well as on the shores of Northumberland, many of them being shot for preservation as specimens. The Pomatorhine Skua has a rapid flight, is bold and rapacious, and frequently robs Gulls of their prey. It breeds in the polar regions.



THE ARCTIC, OR RICHARDSON'S SKUA.

TEASER, SKAIT BIRD, DIET BIRD, DIRTY ALLAN.

Stercorarius crepidatus.

*Ignorant elf, ape, owl yrregular,
Skaldit skaitbird, and common skandelair;
Wansukkit funlin, that Nature made ane Yrle,
Baith John the Ross and thow sall squeil and skirle,
Gif eir I heir ocht of your making mair.*

THE FLYTING OF DUNBAR AND KENNEDY, circa 1508.

THE Arctic, or Richardson's Skua is sometimes seen on the coasts of the county during the autumn and winter months, being a visitor from the north. A mature male was shot by Mr. Cotesworth on the farm of Whitefield, near Cowden Knowes, on the 12th of November 1874,¹ this being the only instance of the bird having been found in any inland district of Berwickshire. This Skua occurred in unusual numbers from Coldingham to Cramond in the winter of 1874-75,² when, as recorded by Mr. Hardy, a male and a female were shot at Coldingham Shore.³

Richardson's Skua may be distinguished from the Pomatorhine Skua by its smaller size, and narrow, pointed, central tail feathers. Like that bird, it has a powerful and rapid flight, resembling that of a Hawk, and is a great robber of Gulls and Terns, which it chases until they drop their prey. It likewise feeds upon the eggs and young of other birds, and garbage thrown up by the tide.

Its principal breeding quarters are in the arctic regions.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 288.² *Ibid.* vol. vii. p. 261.³ *Ibid.* vol. vii. p. 517.

THE LONG-TAILED, OR BUFFON'S SKUA.

Stercorarius parasiticus.


*When the ocean rolls the proudest,
Through the foam the sea-bird glides.*


SCOTT.

DURING the storms of the autumn of 1879 great flocks of Skuas visited the coasts of England and Scotland, amongst which were considerable numbers of this species, an example being shot at Eyemouth in November of that year. It was a mature bird, and had the central feathers seven inches longer than the other plumage of the tail¹

The Long-tailed Skua resembles Richardson's Skua in its general habits, and may be distinguished from the latter by its smaller size and longer central tail feathers. It breeds in Lapland and other northern regions.

¹ *Hist. Ber. Nat. Club*, vol. ix. p. 169.





THE RAZOR-BILL.

COMMON AUK, MARROT, SCOUT, SEA CROW.

Alca torda.

The Coulter Peb.

*The billows burst, in ceaseless flow,
Upon the precipice below.**The steepy rock, and frantic tide,
Approach of human step denied.*

SIR WALTER SCOTT.

SELBY, writing on the birds observed at St. Abb's Head on the 18th of July 1832, says: "Upon the ledges of the rocks the Guillemots (*Uria troile*) and Razor-bills (*Alca torda*) were seen in great numbers, ranged in order, tier above tier, and looking at a distance like armies of pigmies; these upon the least alarm utter their peculiar curring kind of note, which, when mixed with the screams of the Sea Gull and Kittiwake, and heard from a distance, or softened by the murmurs of the waves, produces a wild though not disagreeable species of concert well according with the nature of the scenery which surrounds them."¹ Mr. Archibald Hepburn, in his "Account of the Birds found at St. Abb's Head on the 20th of June 1851," remarks that: "The Razor-bill (*Alca torda*) is pretty common, but not nearly so abundant as I had anticipated from the numbers found on the Bass; indeed, they did not appear to be so numerous as the Herring Gulls. They generally frequented

¹ *Hist. Ber. Nat. Club*, vol. i. p. 19.

loftier ledges than the Guillemot cared to occupy, and that in little parties, separately, or mixed with other species, and occasionally a solitary bird might be seen tenanted a snug cranny."¹ In a list of birds which frequent St. Abb's Head, given to Mr. Hardy in 1855 or 1856 by the late Andrew Wilson of Coldingham, it is stated that the "Coulter Neb" (*Alca torda*) then nested at the Rampart, Skelly, and Foul Carr Cove; and comments on this list in 1857 by the late Mr. Francis Purves show that it was then found on all parts of the Head.

From the above statement it would appear that the subject of our notice was formerly much more plentiful at St. Abb's Head than it is at the present time, when it is found breeding in small numbers only, along with colonies of Guillemots, on the ledges of the high precipitous rocks which run into the sea near the ruins of the ancient nunnery. When I visited this haunt in the end of June 1886, very few Razor-bills were to be seen, whilst the ledges were covered with hundreds of Guillemots. In size, colour, and habits, this species resembles these birds, and it returns to its nesting places in spring about the same time. Its single egg, which is usually deposited on the bare rock, is smaller and more oval than that of the Guillemot, and is white, blotched, and spotted with reddish-brown. During autumn and winter the Razor-bill is found off the coast of the county, where it feeds on small fishes and crustaceans. It swims with great ease, and is an expert diver.

Mr. Hardy, writing on the effects of the severe winter of 1878-79, mentions that in February 1879 numbers of dead Razor-bills were found washed ashore near Oldcambus.²

¹ *Hist. Ber. Nat. Club*, vol. iii. p. 73.

² *Ibid.* vol. ix. pp. 126-339.

THE COMMON GUILLEMOT.

FOOLISH GUILLEMOT, WILLOCK, MURRE, MARROT, SCOUT,
SKIDDAW, SCUTTOCK, SEA HEN.

Uria troile.

The Scout,¹ The Marrot.²

*The baron hath the landward park; the fisher hath the sea;
But the rocky haunts of the sea-fowl belong alone to me.*

MARY HOWITT, *Song of the Sea-Fowler.*

THE magnificent promontory of St. Abb's Head, where the dark sea-girt rocks tower to a vast height above the restless waves below, is the favourite haunt of the Common Guillemot in Berwickshire. Here it may be seen during the breeding season in closely-packed colonies on the rocky ledges of the gloomy precipices, which are whitened by the mutings of countless generations of sea-fowl. When a boat approaches the bottom of the cliffs, and the birds are alarmed, vast numbers dash headlong from their eggs towards the sea, their harsh chattering screams, mingled with the clamorous cries of Gulls and other sea-fowl, reminding us of the following quaint description by old Dunbar:—

The air was dirkit with the fowlis
That come with yawmeris, and with yowlis,
With skryking, skryming, and with scowlis,
To tak him in the tyde.

¹ Scout's Croft, near Coldingham; Scout Cave, on the coast south from Eyemouth; and Scout Point, near Gungreen, have evidently derived their names from this bird.

² So called by the Cove fishermen.—J. Hardy.

Proceeding round the coast from Lamberton on the east to Cockburnspath on the west, the first colony of Guillemots which we reach is at Whiteheugh, immediately to the north of the village of Coldingham Shore. Here multitudes of birds are seen on the whitened ledges of the overhanging cliff, sitting erect in rows, and so closely wedged together that every available space seems to be occupied by them. As we draw near, their loud, hoarse, curring notes, which they appear to utter in concert from time to time, have a peculiar but not unpleasing effect upon the ear, and are in keeping with the wild nature of the surrounding scenery. When heard on a calm summer night, as the shades of darkness are beginning to creep over the rocky coast, the discordant screams of the innumerable sea-fowl, now swelling loudly along the face of the cliff and again dying away in the distance, produce a weird and fearful sound which clings to the memory, and reminds the listener of the stories of the gibbering hobgoblins, witches, and warlocks of the past, who,

wi' monie an eldrich screech and hollow,

frightened the ancient inhabitants of the county.

On passing from the Whiteheugh towards St. Abb's Head a small breeding station of this species is seen on the cliffs immediately to the east of the Lighthouse, and after rounding the Head considerable colonies are found on the Cleaver Rock, Foul Carr, the precipices at the Ramparts, Skelly, and Flot Carr. There is also a nesting place on the face of the steep cliff which looks towards the west, between West Hurker and Petticowick Harbour.¹ When we reach

¹ James Melville in his *Autobiography* mentions the spring of delicious water which still exists at Petticowick. Describing his flight in an open boat towards Berwick in June 1584, to escape from his persecutor Arran, he says: "It fell dead calm about the sun drawing laigh. Coming under the Craig, we rowed in within a pretty little howe betwixt the Main and the Head, where, easily going a-land, we refreshed us with cold water and wine, and, returning to our boat, slept the dead



Broadhaven Bay a small colony is seen on the rocks there, and another at the Raven's Heugh; further on at Thrummie Carr we find another occupying the most westerly breeding place of the Guillemot on the coast of Berwickshire.

Dr. Johnston of Berwick, in his address to the Berwickshire Naturalists' Club on its first anniversary meeting held at Coldstream, 19th September 1832, referring to a visit of the Club to St. Abb's Head in July of that year, remarks that: "Many of the rocks are insulated, of a pyramidal form, and soar to a great height. The bases of most are solid, but in some pierced through and arched. They are covered with the dung of innumerable flocks of birds which resort here annually to breed, and fill every little projection, every hole which will give them leave to rest. Multitudes were swimming about, others swarmed in the air and stunned us with the variety of their croaks and screams. Kittiwakes, Sea-mews, and Black-headed Gulls, Guillemots, Auks, and Corvorants are among the species which resort hither."¹

In his "Notes on some of the Birds found at St. Abb's Head on the 20th of June 1851," Mr. Archibald Hepburn states that: "The Guillemot (*Uria troile*) breeds in countless thousands; ledge above ledge was crowded with birds sitting on their solitary egg laid on the bare rock, and at the report of a gun the birds would waddle to the edge: springing downwards with outstretched legs to break their fall, they sped away on rapid pinion to the open sea. On approaching the base of one of the stupendous cliffs a large flock of these birds, which were reposing on a rocky shelf a foot or two above the water, dashed into the sea; some

of the night, but needed none to wake us, for soon be the daylight appeared there was sic a noise of fowls on the craig and about us, because of their young anes, that we were almost pressed to launch out."—Melville's *Autobiography*, pp. 169, 170.

¹ *Hist. Ber. Nat. Club*, vol. i. pp. 5, 6.

fluttered along the surface ere they acquired an impetus for flight; others swam about the boat in the most confiding manner, and delighted us all with their graceful movements."¹ He likewise refers to the Guillemot as being more numerous than any other kind of bird at the Head, and the Kittiwake Gull standing next to it in numbers.² An interesting paper on "St. Abb's Head and its Bird Life" was read to the Natural History Society of Glasgow by Mr. Harvie-Brown on the 26th of April 1881, who, in alluding to his own observations on the occasion of a visit to the Head on the 25th of July 1880, remarks that "The Guillemot must be much scarcer now than in Hepburn's time."³

Judging from the above records, and from what I have noticed during the last few years when occasionally visiting St. Abb's Head in the breeding season, as well as from information obtained from old fishermen who have frequented the Head all their lives, it would appear that the Guillemot has greatly diminished in numbers within the last thirty or forty years. It is difficult to account for this decrease satisfactorily, but probably it may have proceeded from various causes, amongst which may be mentioned the vast quantities of Guillemots' eggs which were formerly taken by the fishermen,⁴ and also the marked increase of the Herring Gull, whose nest-robbing propensities are well known.

¹ *Hist. Ber. Nat. Club*, vol. iii. p. 73.

² *Ibid.* vol. iii. p. 74.

³ *Proceedings of the Natural History Society of Glasgow*, 26th April 1881.

⁴ Mr. Robert Thorburn, fisherman, Coldingham Shore, who is seventy-eight years old, and has fished in the neighbourhood of St. Abb's Head all his life, told me on the 11th of August 1886, when he accompanied me to the Head, that, about forty years ago, he took as many as 180 Guillemots' eggs off Foul Carr in one day, and that he sold the eggs for 1d. each. The eggs of the Guillemots, which occupy the ledges of the precipitous cliffs at the Ramparts, appear to be taken at present by men or boys descending with ropes to the nests, for I have frequently observed strong wooden stakes firmly driven into the ground on the top of precipices to which ropes had evidently been hitched. Mr. Hardy's *M.S. Notes* bear that about 1837 Guillemots' eggs were sold at 4d. per dozen.

This species lays a single egg on the bare rock, and incubation lasts about a month; the eggs vary greatly in colour, scarcely two being exactly alike, but they are generally either bluish-green, blotched or streaked with dark reddish-brown or black, or white with similar markings. The eggs are very good for the table, and also are said to be used for clarifying wine, and for the preparation of patent leather.¹

After the breeding season is over—about the beginning of August—the birds leave the cliffs at St. Abb's Head with their young for the open sea, where they are seen dispersed during autumn and winter. They return to the rocks in March, and begin to lay in May.


The Guillemot flies with a rapid motion of the wings and at great speed, and, when it returns from the sea to the nesting ledges, curves upwards in its flight as it approaches the rock, and thus alights gently. Its flight is straight, and it is a very expert diver. Mr. Seebohm gives the following interesting account of its aquatic gambols in the salt-water tanks at the Brighton Aquarium: "Using their wings much after the manner that a fish does its fins, they progress through the water, darting hither and thither with great rapidity. In swimming the Guillemot uses its legs as a motor, but in diving the wings alone are used. The whole body of the bird is covered with a mass of air-bubbles, and it leaves a train of these bubbles behind it, glistening like silver and pearls, which adds much to the beauty of the performance. Sometimes the descent of the bird is perpendicular, sometimes in an oblique direction, and its progress under the water is made apparently as easily as through the air; even more so, turning and gliding about with ever graceful movements, and sometimes hovering over a morsel

¹ Yarrell's *British Birds*, fourth edition, vol. iv. p. 71.

of food like a tern. The Guillemots at the Aquarium rarely stay under the surface more than half a minute, but in the open sea I have known them remain down for a much longer time."¹

The Ringed Guillemot which is found at St. Abb's Head is distinguished from the Common Guillemot by having a white ring round the eye. Formerly it was considered to be a distinct species, but ornithologists now look upon it as only a variety of the common bird.

¹ *History of British Birds*, 1888-85, vol. iii. p. 392.



THE BLACK GUILLEMOT.

GREENLAND DOVE, DOVEKY, SEA TURTLE, LITTLE GUILLEMOT,
SPOTTED GUILLEMOT, TYSTIE.

Uria grylle.

The Turtle Dove.

*I gaze upon the stormy, troubled ocean,
I hear her crested waves
Waking, as in they roll with restless motion,
The echoes of her caves.*

*Like armed hosts, impatient for the battle,
They swell with deafening roar;
Then hurl their force, with thunder, crash and rattle,
Upon the sounding shore.*

WALTER CHISHOLM.

ON the 19th of June 1839 the Berwickshire Naturalists Club met at Coldingham under the presidency of the Rev. Thomas Knight, Vicar of Ford, who, in his address to the members delivered at the anniversary meeting held at Milfield on the 18th of September of that year, records that there was exhibited at the Coldingham meeting above mentioned "a living specimen of the *Uria grylle* or Black Guillemot, which had been shot two days previously at St. Abb's Head."¹ Although this species is not now found breeding at St. Abb's Head, it appears from Mr. Hardy's *MS. Notes* that in 1857 two or three pairs frequented the rocky precipices there, and that it formerly nested at Tookey and Horsecastle Coves, which are situated to the south of the Head. He also mentions "that some time before the above


¹ *Hist. Ber. Nat. Club*, vol. i. p. 182.

date a Mr. Pratt, son of a lawyer in Berwick, shot two 'Turtle Doves'¹ at St. Abb's Head, and there have not been any seen there since."

The Black Guillemot is now seldom seen off the coast of Berwickshire. Mr. Gray, writing in 1883, says: "A few pairs still linger in the vicinity of the Isle of May, in the Firth of Forth, where an occasional nest may yet be taken."² It is much smaller than the Common Guillemot, which it resembles in its habits, being about the size of a Puffin. In summer the plumage is wholly black, with the exception of a white patch on the wing, and in winter it is more or less mottled with white.

¹ Black Guillemots.

² *Hist. Ber. Nat. Club*, vol. x. p. 199.



THE LITTLE AUK.

COMMON ROTCHE, LITTLE ROTCHE, LITTLE GUILLEMOT,
SEA DOVE.

Mergulus alle.

*The time and sêssoun bitter, cauld and pale
Thay schort dayis, that clerkis clepe Brumale:
Quhen brym blastis of the northyn art
Ouerquhelmyt had Neptunus in his cart,
And all to schaik the levis of the treis,
The rageand stormes ouerwelterand wally seis.
Ryveris ran rede on spate with watter broun,
And burnis harlis all thare bankis down.*

GAWIN DOUGLAS, *Description of Winter*, 1512.

AFTER severe storms this winter visitor to our coasts is occasionally found far inland in a wasted condition, being driven there by the violence of the wind. Writing under date the 27th of January 1860, Mr. Hardy mentions in his *MS. Notes* that one of the Penmanshiel foresters had brought to him a Little Auk which he had found on the railway, wounded below the wing. Probably it had struck against a telegraph wire in its flight. Mr. Kelly relates that a specimen was caught at Harryburn House, near Lauder,¹ which is about twenty-five miles from the sea; and Mr. Wood, lately farmer at Foulden Bastle, informs me that on the 29th of December 1876 he shot a specimen of this bird which flew out of a plantation on Foulden Estate, near "The Camps," the weather having been very stormy for a week or two before that time. Mr. Hardy records that an

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 304.

example was caught near Duns in November 1875;¹ and the gardener at Abbey St. Bathans lately showed me a specimen which he had picked up dead near the Saw-Mill there in winter, about 1881. This bird was more than usually numerous on the coast in the autumn and winter of 1878.²

The Little Auk measures only about eight inches in length. It breeds within the Arctic Circle.³

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 517.

² *Ibid.* vol. viii. p. 502.

³ It is stated in Turnbull's *Birds of East-Lothian*, p. 32, that the Little Auk breeds at St. Abb's Head, but this is a mistake.



THE PUFFIN.

SEA PARROT, COULTER NEB, POPE, GULDER HEAD,
TAMMY NORIE,¹ MULLET, BOTTLE NOSE.

Fratercula arctica.

The Tammie Norie.

*Yonder peopled rocks,
To whose wild solitude, from worlds unknown,
The birds of passage transmigrating come.*

MALLET.

MR. ROBERT GRAY says that the Puffin is a migratory bird, and all those bred on the Bass disappear early in September, by which time, however, or very soon afterwards, they are replaced by other flocks from arctic waters.²

Although this species is found off the coast of Berwickshire at all seasons of the year, it does not appear to breed at St. Abb's Head now; but in former times a few pairs nested there. Mr. Selby, in his "Notice of Birds observed in the neighbourhood of St. Abb's Head on the 18th of July 1832," remarks that the Puffin "also finds appropriate holes wherein to deposit its eggs. It does not appear, however, to be very numerous, as only two or three individuals were

¹ "Norwegian *noere* signifies *puellus*, *homuncio*—the boy, or mannikin."—Jamieson, *Scot. Dict.* Chambers, in his *Popular Rhymes of Scotland*, says that the following couplet is repeated jocularly when a young man refuses to salute a rustic coquette:—

Tammie Norie o' the Bass
Canna kiss a young lass.

He adds that it is also customary to call a stupid-looking man a Tammie Norie.—*Popular Rhymes of Scotland*, new edition, p. 190.

² *Hist. Ber. Nat. Club*, vol viii. p. 54.

seen during the excursion."¹ Writing of a visit to St. Abb's Head on the 20th of June 1851, Mr. Archibald Hepburn says regarding this bird that "only about a dozen pairs annually build in crevices in the Foul Carr."² In 1855 and 1857 Mr. Hardy noted from local information that three or four pairs then nested at St. Abb's Head.


In an interesting paper on "St. Abb's Head and its Bird-Life,"³ Mr. Harvie-Brown includes the Puffin in a list of species at the end of the paper, but he does not say that he saw it breeding when he visited that well-known haunt of sea-fowl on the 25th of July 1880.

This bird flies very swiftly and is an expert diver, using its wings when under water in the same way as in the air. Its food consists of small fishes, molluscs, and other marine animals.

¹ *Hist. Ber. Nat. Club*, vol. i. p. 19.

² *Ibid.* vol. iii. p. 74.

³ Read to the Natural History Society of Glasgow, 26th April 1881.



THE GREAT NORTHERN DIVER.

RING-NECKED LOON, GREATEST SPECKLED DIVER, IMMER OR
EMBER GOOSE, GUNNER, NAAK, COBBLE, SEA HERDSMAN.

Colymbus glacialis.

*The Divers were many, and various in hue ;
Of the Northern, the Imber, Black-throated a few.
By tribes hyperborean their pelts often sought,
Into robes warm and flexible are frequently wrought.*

JENNINGS.

THE Great Northern Diver is an autumn and winter visitor to the coasts of Berwickshire, where it is occasionally seen, and where its weird and melancholy cry is sometimes heard amidst the booming of the waves when storms have lashed the sea into fury and the rocky shores are whitened with spray.

Mr. Hardy says that a specimen of this bird was found by the Cove fishermen in the nets on the 23rd of September 1856, and that it is considered rare on that part of the coast.¹ He records that an immature bird was found dead on the shore near Oldcambus on the 1st of April 1875.² Mr. William Patterson, late farmer at North Berwick Abbey, has informed me that his father, who was tenant at Edington Mill, on the Whitadder, about the beginning of this century, shot a Great Northern Diver on the mill cauld there when it was all frozen over except a small part in the centre. He had observed the bird frequently diving, and got his gun to try to shoot it, but it was not easy to get within gunshot,


¹ Mr. Hardy's *MS. Notes*.

² *Hist. Ber. Nat. Club*, vol. vii. p. 484.

as the sides of the cauld were bare and afforded little or no concealment. He, however, waited until the bird dived, and then ran forward within range of the hole in the ice. When the Diver came up it had a large trout in its bill, and he shot it quite dead. A new difficulty then presented itself to him, namely, how he should get the bird which he had killed, for he was afraid to venture on the ice lest it should break, the water being very deep. His anxiety to secure the specimen was so great, however, that it overcame his fear, and he went cautiously towards the hole, trying the strength of the ice as he proceeded with the butt of his gun, and by this means he succeeded in securing the specimen. The Rev. Thomas S. Goldie, minister of Coldstream, writing in 1834, records that "a gentleman some years ago succeeded in killing a Great Northern Diver" in that parish.¹ In August 1884, Mrs. Greet of Birch Hill, Norham, kindly showed me a stuffed specimen of this bird which had been shot on the Tweed there in February 1865.

Its food consists of fish and crustaceans.

¹ *New Statistical Account of Scotland*, vol. ii. (Berwickshire), p. 206.



THE RED-THROATED DIVER.

RAIN GOOSE, SPECKLED DIVER, RED-THROATED LOON,
SPRAT LOON.

Colymbus septentrionalis.

*They carol not, but wail from off the deep
In piteous accents of impatient grief,
And some, like spirits hardened by despair,
Joy in the savage tempest.*

FABER, *Sir Launcelot.*

THE Red-throated Diver, which is seen off the coast of Berwickshire in the autumn, winter, and early spring months, is called the Rain Goose in the north of Scotland, where its wailing cry is thought to prognosticate wet and stormy weather, during which it is frequently heard.¹ It is sometimes found on the Tweed and the Whitadder. So long ago as 1793 we find the Rev. Thomas Mill, minister of Ladykirk, recording in the *Old Statistical Account of Scotland* that Speckled Divers sometimes resort to the Tweed in severe winters;² and I have known two instances of its occurrence on that river near Paxton within the last seventeen years. Mr. William Patterson has informed me that he obtained for his collection a fine specimen of this bird killed on the Whitadder near Preston about thirty years ago. An example was caught near the village of Hutton in

¹ "Rain Goose—the Red-throated Diver (*Colymbus septentrionalis*, Linn.), thus denominated because its crying is thought to prognosticate rain." Shet. Caith.—Jamieson, *Scot. Dict.* Folkard in his *Wild Fowler* says the cry sounds like "Kakeerah! kakeerah!"

² *Old Statistical Account of Scotland*, vol. viii. p. 74.

November 1876.— It was unable to fly, and had apparently been driven inland by the stormy weather.

The Red-throated Diver in breeding plumage has a patch of reddish chestnut on the throat, which disappears in winter. It feeds on fish, molluscs, and crustaceans, and in diving uses its wings under the water in the same way as when flying. It breeds as far south as Jura, and in Iceland, and other northern parts of Europe.

Although the Black-throated Diver (*Colymbus arcticus*) has been procured at the mouth of the Tweed,¹ I have no record of its occurrence in Berwickshire.

¹ *Hist. Ber. Nat. Club*, vol. i. p. 255.



THE GREAT CRESTED GREBE.

CRESTED DOUKER, TIPPET OR SATIN GREBE,¹ GAUNT, CAR GOOSE,
GREATER LOON, GREY OR ASH-COLOURED LOON.

Podiceps cristatus.

*Thou cream-faced Loom !
Where gotst thou that goose look ?*

SHAKESPEARE, *Macbeth*, Act v. Sc. 3.

DURING the autumn, winter, and spring months the Great Crested Grebe is occasionally found off the shores of the county in small numbers. Mr. Hardy mentions that of late years it has been noted as an annual winter visitor, and that it was very numerous in 1879, when some were seen lingering on the coast as late as the 3rd of May.² He adds that in the spring of 1880 it was observed for the last time in the season on the 22nd of March, and reappeared on the 20th of December following.³ In 1881 it left the coast on the 29th of April, and was not noticed in the autumn of that year; only two or three examples were seen in the spring of 1882.⁴ The smooth, silky breast of this Grebe is used for making ladies' muffs, and on this account the bird is frequently pursued by men with guns in a boat, when it dives with such rapidity that it can be shot only after a long chase.

¹ "From the glossy, silky white skin of the breast being used by furriers for cape trimmings and tippetts."—Swainson's *Folk-Lore of British Birds*, p. 215.

² Mr. G. Bolam records that he saw a specimen in 1881 as late as 30th May on the Tweed near Berwick Bridge.—*Hist. Ber. Nat. Club*, vol. x. p. 395.


³ *Hist. Ber. Nat. Club*, vol. ix. p. 391.

⁴ *Ibid.* vol. ix. p. 552.

Seebohm says that it has not hitherto been known to breed in Scotland, but that it nests in some parts of England and Ireland.¹

It feeds generally on fish, frogs, and aquatic insects, and numbers of its feathers are usually found mixed with the food in its stomach on dissection.

¹ Seebohm, *British Birds*, vol. iii. p. 455.



THE RED-NECKED GREBE.

GREY-CHEEKED GREBE.

Podiceps griseigena.

*Now up, now downe againe, that hard it is to prove,
Whether under water most it liveth, or above.*

DRAYTON.


THE Red-necked Grebe is sometimes seen on the coast of Berwickshire during the winter months, and occasionally in the inland parts of the county, generally in severe weather. Mr. Hardy mentions that a specimen which was shot at the Harbour Pier, Coldingham Shore, on the 10th of December, 1875, in winter plumage, was added to Mr. Wilson's collection;¹ and Mr. Gray records that a beautifully marked bird was killed at Coldingham on the 14th of February 1879.² Mr. J. Logan Mack, Coveyheugh House, has informed me that Mr. Andrew Caverhill, Crichness, sent to him a Red-necked Grebe on the 2nd of February 1881, which was killed on the Lammermuirs during a snowstorm by a shepherd, who knocked it down with a stick. Mr. Compton-Lundie of Spital kindly presented to me a fine specimen of a male in immature plumage, which was shot on the Whitadder at Clarabad mill cauld on the 2nd of February 1888.

This species is considerably less than the Great Crested Grebe, while, like that bird, it dives with great facility. It feeds on fish and aquatic insects.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 517.

² *Ibid.* vol. viii. p. 502.

Although the Slavonian Grebe (*Podiceps auritus*) is doubtless a frequenter of our shores from autumn to spring I have no record of any example of this bird having been obtained in Berwickshire.



THE EARED GREBE.

THE BLACK-NECKED GREBE.

Podiceps nigricollis.

*Birds, small and great, of endless shapes and colours,
Here flew and perch'd, there swam and dived at pleasure;
Watchful and agile, uttering voices wild
And harsh, yet in accordance with the waves
Upon the beach.*

MONTGOMERY.

ALTHOUGH this is the rarest of the five species of Grebes found in the British Islands, Mr. Robert Gray states that it seems to occur regularly every winter in suitable localities alongshore between Berwick-on-Tweed and Belhaven,¹ which includes the whole of the Berwickshire coast. Mr. Andrew Brotherston, bird-stuffer, Kelso, informed me on the 19th of March 1885 that, some time previous to this date, a specimen was shot on Lithtillum Loch, which is situated on the march between the parishes of Coldstream and Eccles. This is the only instance with which I am acquainted of the bird having been got in the county, but an example killed on the Tweed near Berwick in March 1881 is in my collection. The Eared Grebe may be distinguished from the Slavonian by the former having the bill slightly recurved, while in the latter it is straight. In its habits and food this bird resembles its congeners.

¹ *Hist. Ber. Nat. Club*, vol. vii. p. 465.

THE LITTLE GREBE OR DABCHICK.

DIPPER, DIVER, DIEDAPPER, DIVEDAPPER, DOUCKER, LITTLE
DOUCKER, BOMETIE, MITHER O' THE MAWKINS.

Podiceps fluviatilis.

The Dipper.¹

*Upon this promise did he raise his chin,
Like a dive-dapper peering through a wave,
Who, being look'd on, ducks as quickly in.*

SHAKESPEARE, *Venus and Adonis*.

THE Little Grebe is a permanent resident in the county, being found in spring, summer, and autumn on the lakes and ponds where it breeds; and in winter on rivers and along the sea-coast when its other haunts are covered with ice.

It is a very expert diver,² and its habits are lively and engaging, especially during the nesting season, when the young may be seen floating about on the surface of the water, their parents coming up from beneath at short intervals to feed them. Mr. Hardy notes that it arrived at Townhead Pond, where it breeds, on the 8th of April 1882,³ and that it leaves that resort in the autumn. Mr. John Thomson wrote to me on the 3rd of May 1886 that it nests regularly at Mertoun, and at Hullidean Mill Pond,

¹ Mr. W. Lockie, Spottiswoode, gives this as the local name of the bird in that locality.

² Mr. Black, farmer at Girrick, in the parish of Nenthorn, tells me that he has frequently shot at this Grebe on the Eden, but without success, as the bird always dived before the charge reached it.

³ Mr. W. Evans, Edinburgh, has informed me that he saw the Little Grebe on Townhead Pond on the 22nd of April 1886.

Bemersyde. Mr. W. Lockie says it is met with in considerable numbers on Legerwood Loch, and that in winter it frequents the bogs about Westruther and Spottiswoode. The Mill Pond at Foulden New Mains, according to Mr. Millican, is also a favourite resort. I have sometimes observed it on Nabdean Mill Pond, and on the Tweed at Paxton in the winter and early spring months. Mr. A. Kelly, Lauder, relates that "Mr. Scott shot a pair of Little Grebes in January 1875 in St. Leonard's Cauld. When he first came in sight of them they were standing on a broad hemming of ice enclosing the water, but this was only momentary, as both plunged into the water and reappeared in the same place, and this action was repeated over and over again. They were feeding, he thought, on the spawn of trout.¹ He crept nearer them under cover of the branches to get within shot. Perceiving that they were watched, they instinctively kept in the water, only occasionally putting up their beaks for air in the current—the ice preventing them from getting under shelter of the willows and other strong herbage at the sides. Many years before that date Mr. Simson, Lauder, obtained a specimen from the same place."² Mr. Kelly adds that this bird is very uncommon in his neighbourhood. The Rev. George Cook of Longformacus has informed me that Mr. Smith of Whitechester shot two examples on the Dye in 1879. Dr. Stuart relates that a specimen was found dead at the side of the Whitadder, near Blannerne, after the ice broke up in December 1879.³

¹ Mr. Brotherston, bird-stuffer, Kelso, writing on the effects of the severe winter of 1878-79, says that the Little Grebes were found to be in good condition, and that, in addition to the remains of aquatic insects and their larvæ, one had a quantity of salmon roe in its stomach.—*Hist. Ber. Nat. Club*, vol. viii. p. 538.

² Mr. A. Kelly, "On some of the Birds of Lauderdale."—*Hist. Ber. Nat. Club*, vol. vii. pp. 305, 306.

³ *Hist. Ber. Nat. Club*, vol. ix. p. 407.

The Little Grebe is seldom seen on the wing, and its awkward gait on land is thus alluded to by Pope:—

As when a dab-chick waddles through the copse
On feet and wings, and flies, and wades, and hops.

The nest, which is rather large and flat, is composed of aquatic plants, and is generally placed amongst reeds, rushes, or other coarse herbage with little attempt at concealment; the eggs, which are from four to six in number, are white when first laid. They soon, however, become stained, and of a dirty yellow colour, for the bird generally covers the eggs with decaying water weeds on leaving the nest.

The food of this species, which it mostly obtains under the surface of the water, consists of small fishes and aquatic insects of various kinds. Quantities of feathers are frequently found in its stomach.



THE STORM PETREL.

MOTHER CAREY'S CHICKEN, STORMY PETREL, LITTLE PETREL,
STORM FINCH, WITCH OR WATER WITCH, MITTY,
SPENNY, SEA SWALLOW.

Procellaria pelagica.

The Stormy Petrel, The Mother of Carey Chicken.

*O'er the deep! o'er the deep!
Where the whale, and the shark, and the swordfish sleep!
Outflying the blast and the driving rain,
The Petrel¹ telleth her tale in vain!
For the mariner curseth the warning bird,
Who bringeth him news of the storm unheard.*

B. CORNWALL.

THE Rev. John Turnbull of Eyemouth mentions that in particular states of the weather this bird is seen at no great distance from the coast;² and Mr. Hardy notes that it was seen at Coldingham Shore on the 7th of January 1861.

It is sometimes driven inland during very stormy weather, and as instances of this it may be mentioned that the occurrence of a specimen at Oxton, six miles north from Lauder, is recorded by Mr. Kelly,³ and another, which was got at Cranshaws, in the Lammermuirs, many years ago, was stuffed by Mr. W. Duns, Duns.

¹ The Petrel is so named from the French *pétrel*, a diminutive of *Pêtre*, i.e., Peter; and the allusion is to the apostle walking on the Sea of Galilee. Whilst skimming along the waves its legs hang down, and the feet seem to touch the water, presenting the appearance of walking.—Swainson's *Folk-Lore of British Birds*, p. 211.

² *New Statistical Account of Scotland* (Berwickshire), vol. ii. p. 322.

³ *Hist. Ber. Nat. Club*, vol. vii. p. 306.

Mr. Gray, writing of the effects of the storm of the 14th of October 1881,¹ on bird-life in the Firth of Forth, after alluding to the various sea-fowl which had been driven by the violence of the hurricane to take shelter near the coasts, says: "Simultaneously there appeared large numbers of Storm Petrels, many of which were blown some distance inland, where they were captured—records of the birds having been caught or otherwise dispersed having reached me from Dunbar and the Lammermuirs. The main body, however, remained in the Firth eight or ten days, during which time the birds frequented for the most part the lee side of Inchkeith, quite near to the anchored ships that had been forced there for shelter. A lesson, indeed, might have been derived from their presence by the captains of ocean-going steamers, several of whom, impatient of delay, had set sail—in some cases oftener than once—only, however, to return, partially disabled, to their former anchorage. The Petrel, actuated no doubt by an unerring instinct, wisely remained under shelter; and I would venture to say that in any future case, when these birds are seen under such circumstances, much expense might be saved by masters of wind-bound vessels if they quietly remained at their anchorage until the Petrels let them know when it was time to leave. I commend this observation to my friend Mr. Buchan, the excellent Secretary of the Scottish Meteorological Society, as

¹ During this terrible and disastrous storm, when the sea, lashed into unprecedented fury by the hurricane, overwhelmed upwards of one hundred and fifty fishermen, with their boats, from the villages on the sea-coast of Berwickshire, the Storm Petrel was seen at various places along the shore. Mr. Campbell-Noble of Coldingham has informed me that during the height of the tempest a boat, belonging to Alexander Wilson of Coldingham Shore, was driven with some others round by St. Abb's Head. When the boat was in momentary peril of being dashed to pieces on the rocks as it was rounding the most dangerous part of the Head, and the men were lying on the deck with their arms through the bulwarks, a "half-lang" lad, named Thomas Wilson (John's Tam), stretching out his legs, touched one of the men, and said, "Geordie! yonder's a Stormy Petrel!" The man, apparently looking upon this remark as most untimely, was heard to reply, "Stormy Petrel! If I could get at ye, I would Stormy Petrel ye."

a means of increasing the interest, if not the importance, of future weather forecasts." ¹

The Storm Petrel is about the size of a Sparrow, and is one of the smallest web-footed birds. It breeds on various parts of the coasts of Great Britain and Ireland, and feeds on small fishes, crustaceans, and molluscs.

¹ *Hist. Ber. Nat. Club*, vol. x. pp. 85, 86.



MIGRATION OF BIRDS IN BERWICKSHIRE.

*Birds, joyous birds of the wandering wing !
Whence is it ye come with the flowers of spring ?*

HEMANS.

*. Wild birds that change
Their season in the night, and wail their way
From cloud to cloud.*

TENNYSON.

FOR many years past the Migration of Birds has attracted the attention of ornithologists, and although much information has been collected regarding it since the days of Gilbert White, whose delightful work on the Natural History of Selborne is a perennial source of pleasure to all lovers of Nature, yet much has still to be obtained before the subject can be fully elucidated, and removed from the region of conjecture.

We find that with the approach of the cold weather in autumn certain species of birds, such as the Swallow, leave the county for southern climes, whilst somewhat later in the same season, others, like the Wild Goose, come here from northern regions and take up their abode with us for the winter. With the return of the genial weather in spring the former appear here again in their usual haunts, whilst the latter fly away to the north to spend the summer in Lapland or Siberia. These are true migrants, as distinguished from birds of passage, such as the Dotterel, which only visits the county for a short time in spring on its way northwards to its nesting grounds, and again in autumn on its way southwards to its winter quarters. In addition to the true migrants and this bird of passage, we have partial migrants like the Thrush and the Redbreast, the majority of which pass southwards in winter and return

in spring—a comparatively small number remaining with us during the winter months.

Speaking generally, scarcity of food and unsuitability of climate appear to be the chief causes of migration, and it is probable that they have been the origin of the habit, for birds have the means of moving rapidly across sea and land from one part of the surface of the earth where the conditions do not meet their requirements to another where they find what they want. Thus Siberia, which, during the short warm summer of that latitude, affords an ample supply of food and a suitable climate to the multitude of birds which migrate thither from their southern winter quarters to breed, is deserted by them on the approach of winter, when the land becomes deeply covered with snow and all the rivers and lakes are ice-bound. With the advent of summer the snow and ice disappear and the birds return to find abundance of food and a congenial climate for the rearing of their young.

It is believed that in comparatively recent geological times Great Britain was connected by dry land with the continent of Europe, and that the birds on their passage across the North Sea still follow the old coast lines of the connecting ground, although these have for ages been covered by the water. Geological changes usually take place very slowly, and it is probable that many thousands of years elapsed before the dry land which connected Britain with the continent of Europe finally disappeared under the surface of the sea. During the period when the land was slowly sinking it may be supposed that there would be long tracts of it stretching into the sea on both sides, with a series of islands between them, and that the migratory birds would naturally travel along the coast as far as they could and then fly from island to island until they reached the opposite side. When the islands finally disappeared

under the waves, the birds would continue to take the same route as before, but would extend their flight from shore to shore. The Mediterranean Sea is also crossed by several stretches of submerged land which formerly connected Europe with Africa, and it is found that the principal routes taken at the present time by migratory birds when crossing that sea are over these stretches.

It is probable that, owing to the causes above mentioned, certain species of birds have migrated to a greater or lesser extent ever since they appeared in any considerable numbers on the surface of the earth, and that a hereditary tendency to migrate in autumn and spring has become a part of their nature, in the same way as a hereditary tendency to point game has become a part of the nature of a well-bred pointer, for a young dog of this kind which has never seen game will often point it on the first occasion on which the dog is taken into the field.

Birds while on migration fly very high in clear weather, when, doubtless, they can see a great extent of the surrounding country. That they are guided on their journey by experienced leaders who have migrated in previous years, and who thus know the landmarks to guide them on their way, is very probable. It is not likely that the young intuitively know the route to be taken on migration any more than a young untrained homing pigeon knows the direction in which to fly to reach its cote, when it is conveyed a long distance away from its native haunt. A homing pigeon is gradually trained to return from long distances by taking it away from its dovecot for short distances in the first place, and increasing these by degrees to enable it to become acquainted with the landmarks of the intervening country. Many homing pigeons are lost if they are flown during foggy weather, thus showing that they are guided in their flight

by looking on the earth beneath them. When birds on migration are overtaken by a very dark night or a fog they descend from their high line of flight towards the surface of the sea or land, and it is on these occasions that they are seen flying round about the lighthouses in a state of apparent bewilderment. On this account it has been thought that dark nights and hazy weather are favourable for migration, but there is nothing to support this view, except that on these occasions the birds are seen at the lighthouses on the coast. In clear weather they doubtless fly both during the day and night at such an immense height that they are not visible to the unaided eye. With the help of a telescope, however, they have been observed migrating at a height of about four miles above the surface of the earth and travelling at a rate of about forty miles an hour. At this speed and with a favourable wind they could cross the widest part of the North Sea in about eight or nine hours, and from the coast of Holland to England in about one-third of that time. Birds on migration seldom fly either directly against or with the wind, but generally within three or four points of it.

It is supposed that during hazy weather, with dark nights, when birds on migration fly low, they enter Berwickshire by two routes—one being across the Tweed from the adjoining county of Northumberland, where the sea-board is low, and the other from the neighbouring county of East Lothian, where the shore has little elevation. The sea-coast of Berwickshire is very lofty and precipitous, and on a dark night the high black cliffs probably appear like a barrier to the birds while they are approaching the land from the German Ocean and flying at no great height above the waves. They consequently continue their flight along the open sea towards the Firth of Forth, on reaching which numbers of them doubtless spread over the low grounds

of East Lothian, whence a portion of them ultimately find their way to Berwickshire over the Lammermuirs, or along the land which skirts the sea in the neighbourhood of Cockburnspath.

It has been observed that while thousands of birds are seen on migration at the lighthouses on the Farne Islands and the Isle of May, where the adjoining coasts are low, very few, if any, have been noticed at the lighthouse on St. Abb's Head, where the coast is very high. In clear weather it is probable that the birds pass directly from above the German Ocean into the interior of Berwickshire, and there descend from their lofty flight. In apparent support of the above views with regard to the routes by which birds on migration enter the county, it may be mentioned that the recorded dates of the first arrivals in Berwickshire of some of the typical migrants as given in the following tables have been compared with the corresponding dates of their first appearances at the Farne Islands and the Isle of May, and it has been found that in some years the birds were observed in Berwickshire before they were noticed at either of these stations, while in other years they were seen at the Farne Islands or the Isle of May before they were noticed in this county.



TABLE OF ORNITHOLOGICAL OBSERVATIONS made in Berwickshire from 1799 until 1887, including the earliest, latest, and average dates of the arrival and departure of migratory birds.¹

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
TRUE MIGRANTS.						
<u>Birds which arrive in spring and leave in autumn.</u>						
PASSERES.						
TURDIDÆ.						
RING OUZEL (<i>Turdus torquatus</i>)						
Arrives in spring	1860	1886	13	15th Feb. 1872	22nd May 1884	7th April.
Sings	1876	1884	3	22nd Mar. 1876	7th May 1884	8th April.
Has young	1877	1883	3	16th April 1883	16th June 1877	7th May.
Leaves in autumn	1867	1883	4	20th Oct. 1883	22nd Nov. 1867	11th Nov.
SYLVIIDÆ.						
WHEATEAR (<i>Sociola cænanthe</i>)						
Arrives in spring	1886	1886	23	28th Feb. 1876	4th May 1886	9th April.
Nests	1877		1	7th April 1877		
Has young	1882		1	19th June 1882		
Leaves in autumn	1868	1886	10	6th Aug. 1878	14th Oct. 1879	7th Sept.
WHINCHAT (<i>Sociola rubetra</i>)						
Arrives in spring	1887	1887	10	7th April 1872	15th May 1884	21st April.
Leaves in autumn	1868	1884	2	1st Sept. 1884	12th Oct. 1883	30th Sept.
REDSTART (<i>Phœnicurus ruticilla</i>)						
Arrives in spring	1860	1887	17	24th April 1872	17th May 1883	2nd May.
Nests	1860		1	19th May 1860		
Has young	1874		1	28th June 1874		
Leaves in autumn	1872	1883	4	6th Sept. 1878	8th Nov. 1872	28th Sept.
WHITETHROAT (<i>Sylvia ruft</i>)						
Arrives in spring	1867	1887	16	1st May 1874	22nd May 1886	11th May.
Sings	1876	1881	2	5th May 1876	21st May 1881	13th May.
Leaves in autumn	1873	1886	10	15th Aug. 1873	18th Oct. 1884	8th Sept.
BLACKCAP (<i>Sylvia atricapilla</i>)						
Arrives in spring	1849	1887	10	18th April 1876	22nd May 1880	4th May.
Sings	1874	1881	2	23rd April 1874	30th April 1881	27th April.
Leaves in autumn	1863	1884	2	17th Sept. 1884	27th Sept. 1863	22nd Sept.
GARDEN WARBLER (<i>Sylvia saltatoria</i>)						
Arrives in spring	1879	1884	2	22nd May 1884	25th May 1879	23rd May.
Leaves in autumn	1883	1884	2	17th Sept. 1883	17th Sept. 1884	17th Sept.

¹ For voluminous notes of the arrival and departure of migratory birds in Berwickshire from 1799 until 1887, from which this Table and the Calendar which follows it have been chiefly prepared, I am indebted to the kindness of my friend Dr. James Hardy, of Oldcambus. I have also to thank my brother, Mr. Frank Muirhead, for the great assistance which he has given to me in the preparation of the Table and the Calendar.

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
TRUE MIGRANTS—continued.						
PASSEGRES—continued.						
CHIFFCHAFF (<i>Phylloscopus collybita</i>) Arrives in spring	1874	1887	6	23rd Mar. 1883	23rd April 1874	9th April.
WILLOW WREN (<i>Phylloscopus trochilus</i>) Arrives in spring Leaves in autumn	1836 1857	1887 1884	26 9	4th April 1883 15th Aug. 1879	9th May 1885 29th Sept. 1881	23rd April. 6th Sept.
WOOD WREN (<i>Phylloscopus sibilatrix</i>) Arrives in spring Sings Leaves in autumn	1874 1875 1882	1887 1887 1883	11 4 2	24th April 1874 8rd May 1875 8rd Aug. 1882	22nd May 1880 30th May 1883 10th Sept. 1883	10th May. 17th May. 21st Aug.
EDGE WARBLE (<i>Aeroccephalus schenobanius</i>) Arrives in spring Leaves in autumn	1842 1884	1884	9 1	9th May 1881 1st Sept. 1884	23rd June 1842	20th May.
GRASSHOPPER WARBLER (<i>Aeroccephalus scirpaceus</i>) Arrives in spring Note heard	1876 1876	1888 1888	2 2	28th May 1888 28th May 1888	9th June 1876 9th June 1876	8rd June. 8rd June.
MOTACILLIDÆ.						
THREE PIPIT (<i>Anthus trivialis</i>) Arrives in spring Leaves in autumn (last seen)	1879 1887	1887	5 1	30th April 1887 27th Oct. 1887	18th May 1885	8th May.
MUSCICAPIDÆ.						
SPOTTED FLYCATCHER (<i>Muscicapa grisola</i>) Arrives in spring Leaves in autumn	1881 1881	1886 1884	5 2	19th May 1881 27th Aug. 1881	25th May 1883 1st Sept. 1884	22nd May 29th Aug.
HIRUNDINIDÆ.						
SWALLOW (<i>Hirundo rustica</i>) Arrives in spring Flocks Leaves in autumn	1800 1857 1832	1887 1885 1885	43 4 23	11th April 1808 10th Aug. 1857 11th Sept. 1881	11th May 1850 21st Sept. 1884 9th Oct. 1874	26th April. 30th Aug. 25th Sept.
MARTIN (<i>Chelidon urtica</i>) Arrives in spring Flocks Leaves in autumn	1836 1857 1836	1886 1880 1885	30 4 13	21st April 1874 21st Aug. 1880 11th Sept. 1881	14th May 1877 29th Sept. 1876 9th Oct. 1874	8rd May. 4th Sept. 24th Sept.
SAND MARTIN (<i>Cottia riparia</i>) Arrives in spring Flocks Leaves in autumn	1840 1876 1886	1887 1880 1885	14 2 9	24th Mar. 1884 15th Sept. 1880 11th Sept. 1881	15th May 1877 29th Sept. 1876 9th Oct. 1874	25th April. 22nd Sept. 22nd Sept.
CYPSELIDÆ.						
SWIFT (<i>Cypselus apus</i>) Arrives in spring Leaves in autumn	1849 1873	1885 1885	13 7	11th May 1883 5th Aug. 1881	30th May 1883 12th Sept. 1879	15th May. 22nd Aug.
CAPRIMULGIDÆ.						
NIGHTJAR (<i>Caprimulgus Europæus</i>) Arrives in spring Note heard Nests	1837 1837 1839	1886 1843 1883	8 2 1	8th May 1848 27th May 1837 27th July 1839	5th June 1886 8rd July 1848	17th May. 14th June.

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
TRUE MIGRANTS—continued.						
PASSERES—continued.						
CUCULIDÆ.						
CUCKOO (<i>Cuculus canorus</i>)						
Arrives in spring	1821	1887	29	4th April 1833	27th May 1872	2nd May.
Note last heard	1837	1881	6	18th June 1837	1st July 1838	23rd June.
Young in nest	1842		1	1st July 1842		
Leaves in autumn	1881		1	25th Aug. 1881		
FULICARIÆ.						
RAILLIDÆ.						
LANDRAIL (<i>Oreo pratensis</i>)						
Arrives in spring	1800	1887	12	1st May 1880	29th May 1812	11th May.
Leaves in autumn (last seen)	1881		1	22nd Sept. 1881		
LIMICOLÆ.						
SCOLOPACIDÆ.						
COMMON SANDPIPER (<i>Totanus hypoleucos</i>)						
Arrives in spring	1875	1887	2	28th April 1887	29th April 1875	
<u>Birds which arrive in autumn and leave in spring.</u>						
PASSERES.						
TURDIDÆ.						
REDWING (<i>Turdus iliacus</i>)						
Arrives in autumn	1860	1884	5	27th Oct. 1879	14th Dec. 1878	16th Nov.
Leaves in spring	1877	1879	2	6th April 1877	29th April 1879	17th April.
FIELDFARE (<i>Turdus pilaris</i>)						
Arrives in autumn	1799	1886	22	12th Oct. 1874	19th Dec. 1871	7th Nov.
Leaves in spring	1818	1887	14	6th Feb. 1864	15th May 1887	7th April.
FRINGILLIDÆ.						
BRAMBLING (<i>Fringilla montifringilla</i>)						
Arrives	1857	1881	8	22nd Dec. 1874	15th Jan. 1881	4th Jan.
EMBERIZIDÆ.						
SNOW BUNTING (<i>Plectrophanes nivalis</i>)						
Arrives	1812	1886	16	1st Oct. 1851	20th Jan. 1884	9th Nov.
Leaves	1881		1	23th Mar. 1881		
ANSERES.						
ANATIDÆ.						
BRAN GOOSE (<i>Anser segetum</i>) and PINK-FOOTED GOOSE (<i>Anser brachyrhynchus</i>)						
Arrive in autumn	1800	1886	22	1st. Oct. 1884	15th Dec. 1881	26th Oct.
Leave in spring	1801	1886	23	9th Jan. 1864	1st May 1884	23rd Mar.
BIRD OF PASSAGE.						
LIMICOLÆ.						
CHARADRIIDÆ.						
DOTTEREL (<i>Charadrius morinellus</i>)						
Arrives in spring on passage to the north	1836	1886	13	12th April 1882	19th May 1840	3rd May.
Leaves in spring for north	1836	1888	6	25th April 1882	6th June 1836	20th May.
Seen in autumn on passage to the south	1867	1875	5	26th Sept. 1887	30th Sept. 1875	28th Sept.

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
BIRDS WHICH ARE PARTIAL MIGRANTS.						
PASSERES.						
TURDIDÆ.						
SONO THRUSH (<i>Turdus musicus</i>)						
Sings in spring	1801	1887	20	19th Jan. 1882	12th Mar. 1875	20th Feb.
Has young	1886	1887	10	27th April 1887	1st July 1889	17th May.
MISKEL THRUSH (<i>Turdus viscivorus</i>)						
Sings in spring	1848	1884	10	10th Jan. 1884	10th Mar. 1881	9th Feb.
Nests	1887	1877	8	15th April 1860	6th May 1877	24th April.
Flocks	1882	1881	8	19th Sept. 1822	19th Dec. 1871	26th Oct.
BLACKBIRD (<i>Turdus merula</i>)						
Sings in spring	1801	1888	16	19th Jan. 1882	12th April 1881	26th Feb.
Nests	1887		1	1st May 1887		
Has young	1848	1860	2	10th May 1850	19th June 1848	30th May.
SYLVIIDÆ.						
STONECHAT (<i>Saxicola rubicola</i>)						
Arrives in spring	1837	1886	15	8th Feb. 1864	8th May 1886	21st Mar.
Has young	1874	1884	8	15th June 1874	4th July 1884	21st June.
Leaves in autumn	1887	1884	18	15th Sept. 1849	17th Dec. 1882	31st Oct.
<i>Note.</i> —A few spend the winter in Berwickshire.						
REDBREAST (<i>Erithacus rubecula</i>)						
Sings in spring	1898	1882	10	20th Jan. 1876	25th Feb. 1838	12th Feb.
Has young	1860	1881	5	5th May 1879	22nd June 1881	22nd May.
Sings in autumn	1814	1882	8	16th Aug. 1868	16th Oct. 1836	14th Sept.
WREN (<i>Troglodytes parvulus</i>)						
Sings in spring	1849	1882	6	4th Feb. 1849	21st April 1879	4th April.
Sings in autumn	1868		1	24th Oct. 1868		
MOTACILLIDÆ.						
PIED WAGTAIL (<i>Motacilla lugubris</i>)						
Arrives in spring	1836	1887	24	17th Jan. 1868	26th April 1847	15th Mar.
Leaves in autumn	1878	1888	5	27th Sept. 1888	21st Oct. 1874	4th Oct.
<i>Note.</i> —In mild seasons a few remain in sheltered places in Berwickshire throughout the winter.						
GREY WAGTAIL (<i>Motacilla sulphurea</i>)						
Arrives in spring	1849	1886	21	1st Jan. 1888	18th May 1881	10th Mar.
Leaves in autumn	1878	1879	2	2nd Oct. 1879	18th Nov. 1878	26th Oct.
<i>Note.</i> —A few remain in Berwickshire during mild winters.						
MEADOW PIPIT (<i>Anthus pratensis</i>)						
Arrives in spring	1856	1883	12	4th Mar. 1856	4th May 1880	1st April.
Leaves in autumn	1880	1885	5	4th Sept. 1883	12th Nov. 1880	27th Sept.
<i>Note.</i> —A few remain in Berwickshire during winter.						
ROCK PIPIT (<i>Anthus obscurus</i>)						
Seen on sea-shore in spring	1868	1884	6	17th Jan. 1868	26th April 1879	31st Mar.
Has eggs	1868		1	10th July 1868		
Seen on shore in autumn	1878	1882	2	5th Oct. 1878	6th Oct. 1882	
<i>Note.</i> —A few remain in Berwickshire during winter.						

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
BIRDS WHICH ARE PARTIAL MIGRANTS—continued.						
PASSERES—continued.						
FRINGILLIDÆ.						
LINNET (<i>Linnaea cannabina</i>)	1886	1879	4	6th Feb. 1874	30th April 1886	13th Mar.
Sings	1886	1880	6	2nd Sept. 1874	31st Dec. 1880	11th Oct.
Flocks						
ALAUDIDÆ.						
SKYLARK (<i>Alauda arvensis</i>)	1801	1887	17	2nd Feb. 1801	10th Mar. 1881	17th Feb.
Sings in spring	1833	1875	4	13th Sept. 1875	2nd Oct. 1887	24th Sept.
Sings in autumn	1867	1880	3	26th Oct. 1867	16th Dec. 1880	21st Nov.
Flocks in autumn						
IMMICOLOÆ.						
CHARADRIIDÆ.						
LAFWING (<i>Vanellus vulgaris</i>)	1837	1887	24	3rd Jan. 1835	25th Mar. 1877	16th Feb.
Arrives in spring	1836	1881	5	1st May 1874	10th June 1883	25th May.
Has young	1842	1883	12	15th June 1842	23rd Oct. 1880	20th Aug.
Flocks in autumn						
SCOLOPACIDÆ.						
WOODCOCK (<i>Scolopax rusticola</i>)	1835	1883	12	5th Oct. 1832	9th Nov. 1884	18th Oct.
Arrives in autumn	1836	1836	10	24th Mar. 1833	3rd May 1881	14th April.
Leaves in spring						
Note.—A few remain in Berwickshire and nest during summer.						
COMMON SNIFE (<i>Gallinago caelestis</i>)						
Drums in spring	1837	1879	6	16th Mar. 1840	12th May 1887	15th April.
Nests	1843	1883	3	10th April 1833	17th July 1845	4th June.
GENERAL OBSERVATIONS ON BIRDS.						
PASSERES.						
SYLVIIDÆ.						
HEDGE SPARROW (<i>Acrocor modularis</i>)	1838	1887	10	17th Jan. 1864	15th Mar. 1881	21st Feb.
Sings in spring						
PARIDÆ.						
GREAT TITMOUSE (<i>Parus major</i>)	1849	1883	5	4th Feb. 1849	13th April 1881	5th Mar.
Spring note heard						
BLUE TITMOUSE (<i>Parus caeruleus</i>)	1860		1	2nd Mar. 1860		
Spring note heard						
MUSCICAPIDÆ.						
PIED FLYCATCHER (<i>Muscicapra atricapilla</i>)	1872	1885	3	9th May 1885	12th May 1877	
Seen in spring						
Note.—This bird is occasionally seen in the county about the second week of May.						
FRINGILLIDÆ.						
CHAFFINCH (<i>Fringilla caelebs</i>)	1840	1887	15	30th Jan. 1887	13th April 1886	16th Feb.
Sings in spring	1850	1876	3	2nd May 1857	10th May 1880	6th May.
Nests	1850		1	24th Sept. 1850		
Flocks						
EMBERIZIDÆ.						
CORN BUNTING (<i>Emberiza miliaria</i>)	1849	1884	4	31st Dec. 1863	1st May 1884	20th Feb.
Sings						

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
GENERAL OBSERVATIONS ON BIRDS—continued.						
PASSEGRES—continued.						
YELLOW BUNTING (<i>Emberiza citrinella</i>)						
Sings	1887	1875	7	6th Feb. 1874	29th April 1887	19th Feb.
Flocks	1880		1	24th Sept. 1880		
STURNIDÆ.						
STARLING (<i>Sturnus vulgaris</i>)						
Spring notes heard	1872	1878	5	11th Jan. 1877	22nd Feb. 1872	20th Jan.
Nests	1872	1883	6	3rd Mar. 1883	7th June 1880	25th April.
Flocks	1867	1885	9	25th Aug. 1881	19th Dec. 1871	6th Oct.
COEVIDÆ.						
ROOK (<i>Corvus frugilegus</i>)						
Begins to nest	1884	1887	4	22nd Feb. 1884	4th Mar. 1886	28th Feb.
Young appear on outside of nest	1887		1	29th April 1887		
STEGANOPODES.						
PELICANIDÆ.						
COMMON CORMORANT (<i>Phalacrocorax carbo</i>)						
Seen on sea-coast in spring	1862	1886	17	8th Jan. 1876	20th April 1872	26th Feb.
Seen on sea-coast in autumn	1863	1886	12	6th July 1872	26th Oct. 1877	17th Aug.
GANNET OR SOLAN GOOSE (<i>Sula bassana</i>)						
Seen in spring off coast	1873	1883	7	30th Mar. 1881	3rd May 1877	15th April.
ANSERES.						
ANATIDÆ.						
MALLARD OR WILD DUCK (<i>Anas boschas</i>)						
Leaves sea-coast in spring	1857	1886	18	8th Feb. 1878	22nd April 1857	24th Mar.
Has young	1877	1887	8	30th April 1887	16th June 1877	15th May.
Returns to sea-coast in autumn	1873	1884	11	18th Sept. 1879	3rd Nov. 1873	12th Oct.
COLUMBÆ.						
COLUMBIDÆ.						
RING DOVE (<i>Columba palumbus</i>)						
Coo	1884	1887	4	30th Jan. 1887	12th Mar. 1884	25th Feb.
PHASIANIDÆ.						
COMMON PARTRIDGE (<i>Perdix cinerea</i>)						
Pairs	1849	1882	4	15th Jan. 1882	4th Mar. 1856	12th Feb.
Has eggs	1843	1872	2	18th June 1872	19th June 1843	16th June.
Has young	1837	1885	4	19th June 1872	30th June 1885	25th June.
FULICARIÆ.						
RALLIDÆ.						
MOOR HEN (<i>Gallinula chloropus</i>)						
Returns to ponds in spring	1837	1886	12	24th Feb. 1883	7th April 1886	18th Mar.
COMMON COOT (<i>Fulica atra</i>)						
Returns to ponds in spring	1881	1886	4	7th Mar. 1881	24th May 1882	9th April.
Nests	1882		1	24th May 1882		
Leaves ponds in autumn	1881		1	29th Oct. 1881		

BIRDS.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Latest Date.	Average Date.
GENERAL OBSERVATIONS ON BIRDS—continued.						
LIMICOLÆ.						
CHARADRIIDÆ.						
GOLDEN PLOVER (<i>Charadrius plumialis</i>)						
Spring notes heard	1822	1884	11	8rd Jan. 1857	28th April 1836	24th Feb.
First seen in spring	1800	1836	13	9th Jan. 1864	28th April 1836	10th Mar.
Flocks	1836	1856	3	14th Aug. 1856	30th Sept. 1836	29th Aug.
SCOLOPACIDÆ.						
COMMON CURLEW (<i>Numenius arquata</i>)						
Returns to moors	1837	1887	16	24th Jan. 1880	26th April 1872	12th Mar.
Spring notes heard	1836	1886	11	31st Jan. 1879	30th May 1863	14th Mar.
Returns to sea-shore	1836	1886	12	16th June 1875	30th Sept. 1836	6th Aug.
GAVIÆ.						
LARIDÆ.						
BLACK-HEADED GULL (<i>Larus ridibundus</i>)						
Leaves sea-coast in spring	1813	1886	9	8rd Jan. 1882	9th April 1877	10th Mar.
Returns to sea-coast	1868	1884	14	22nd June 1878	7th Aug. 1872	15th July.
PYGOPODES.						
PODICIPEDIDÆ.						
LITTLE GREEN (<i>Podiceps fusci-</i>						
atilis)						
Returns to pond in spring	1836		1	22nd April 1836		
Leaves pond in autumn	1876		1	1st Nov. 1876		

CALENDAR OF MIGRATIONS & OBSERVATIONS OF BIRDS IN BERWICKSHIRE.

1799—1887.

- Jan. 1. GREY WAGTAIL (*Motacilla sulphurea*) seen 1833. (Earliest of twenty-one observations, 1849-86.)
- „ 3. GOLDEN PLOVER (*Charadrius plumialis*) spring notes heard 1857. (Earliest of eleven observations, 1823-84.)
- BLACK-HEADED GULL (*Larus ridibundus*) left coast 1882. (Earliest of nine observations, 1813-86.)
- LAPWING (*Vanellus vulgaris*) seen inland 1835. (Earliest of twenty-four observations, 1837-87.)
- „ 4. BRAMBLING (*Fringilla montifringilla*) arrives. (Average date of three observations, 1857-81.)
- „ 8. COMMON CORMORANT (*Phalacrocorax carbo*) seen at coast 1875. (Earliest of seventeen observations, 1862-86.)

336 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- Jan. 9. GOLDEN PLOVER (*Charadrius pluvialis*) seen 1864. (Earliest of thirteen observations, 1800-86.)
 WILD GESE (*Anser segetum* and *Anser brachyrhynchus*) last seen 1864. (Earliest of twenty-three observations, 1801-86.)
- „ 10. MISSEL THRUSH (*Turdus viscivorus*) began to sing 1884. (Earliest of ten observations, 1843-84.)
- „ 11. STARLING (*Sturnus vulgaris*) spring notes heard 1877. (Earliest of five observations, 1872-78.)
- „ 15. PARTRIDGE (*Perdix cinerea*) began to pair 1882. (Earliest of four observations, 1849-82.)
 BRAMBLING (*Fringilla montifringilla*) arrived 1881. (Latest of three observations, 1857-81.)
- „ 17. HEDGE SPARROW (*Accentor modularis*) began to sing 1864. (Earliest of ten observations, 1838-87.)
 PIED WAO-TAIL (*Motacilla lugubris*) appeared 1868. (Earliest of twenty-four observations, 1836-87.)
 ROCK PIPIT (*Anthus obscurus*) seen on sea-shore 1868. (Earliest of six observations, 1868-84.)
- „ 19. SONG THRUSH (*Turdus musicus*) began to sing 1882. (Earliest of twenty observations, 1801-87.)
 BLACKBIRD (*Turdus merula*) commenced to whistle 1882. (Earliest of sixteen observations, 1801-83.)
- „ 20. SNOW-BUNTING (*Plectrophanes nivalis*) came 1884. (Latest of sixteen observations, 1812-86.)
- „ 24. CURLEW (*Numenius arquata*) returned to moors 1880. (Earliest of sixteen observations, 1837-87.)
- „ 26. STARLING (*Sturnus vulgaris*) whistles. (Average date of five observations, 1872-78.)
- „ 30. REDBREAST (*Erethaca rubecula*) singing 1876. (Earliest of ten observations, 1838-82.)
 CHAFFINCH (*Fringilla coelebs*) in song 1887. (Earliest of fifteen observations, 1840-87.)
 RING DOVE (*Columba palumbus*) cooing 1887. (Earliest of four observations, 1884-87.)
- „ 31. CURLEW (*Numenius arquata*) first spring notes heard 1879. (Earliest of eleven observations, 1836-86.)
- Feb. 2. SKYLARK (*Alauda arvensis*) singing 1801. (Earliest of seventeen observations, 1801-87.)
- „ 4. WREN (*Troglodytes parvulus*) in song 1849. (Earliest of six observations, 1849-82.)
 GREAT TITMOUSE (*Parus major*) spring notes heard 1849. (Earliest of five observations, 1849-82.)
- „ 6. YELLOW BUNTING (*Emberiza citrinella*) singing 1874. (Earliest of seven observations, 1837-75.)
 LINNET (*Linota cannabina*) began to sing 1874. (Earliest of four observations, 1836-79.)
 FIELDFARE (*Turdus pilaris*) left 1864. (Earliest of fourteen observations, 1813-87.)
- „ 8. STONECHAT (*Saxicola rubicola*) observed 1864. (Earliest of fifteen observations, 1837-86.)

MIGRATIONS AND OBSERVATIONS OF BIRDS. 337

- Feb. 8. WILD DUCK (*Anas boschas*) left sea 1873. (Earliest of thirteen observations, 1857-86.)
- „ 9. MISSEL THRUSH (*Turdus viscivorus*) sings. (Average date of ten observations, 1843-84.)
GOLDEN-EYE (*Fuligula clangula*) appears on coast. (Average date of six observations, 1879-86.)
- „ 12. REDBREAST (*Erithaca rubecula*) sings. (Average date of ten observations, 1838-82.)
PARTRIDGE (*Perdix cinerea*) pairs. (Average date of four observations, 1849-82.)
- „ 15. RING OUZEL (*Turdus torquatus*) seen 1872. (Earliest of thirteen observations, 1860-86.)
- „ 16. CHAFFINCH (*Fringilla caelebs*) sings. (Average date of fifteen observations, 1840-87.)
LAPWING (*Vanellus vulgaris*) appears inland. (Average date of twenty-four observations, 1837-87.)
- „ 17. SKYLARK (*Alauda arvensis*) sings. (Average date of seventeen observations, 1801-87.)
- „ 19. YELLOW BUNTING (*Emberiza citrinella*) sings. (Average date of seven observations, 1837-75.)
- „ 20. SONG THRUSH (*Turdus musicus*) sings. (Average date of twenty observations, 1801-87.)
- „ 21. HEDGE SPARROW (*Accentor modularis*) sings. (Average date of ten observations, 1838-87.)
- „ 22. STARLING (*Sturnus vulgaris*) first spring notes heard 1872. (Latest of five observations, 1872-78.)
ROOK (*Corvus frugilegus*) began to nest 1884. (Earliest of four observations, 1884-87.)
- „ 24. GOLDEN PLOVER (*Charadrius pluvialis*) calls. (Average date of eleven observations, 1823-84.)
MOOR HEN (*Gallinula chloropus*) returned to ponds 1883. (Earliest of twelve observations, 1837-86.)
- „ 25. REDBREAST (*Erithaca rubecula*) began to sing 1838. (Latest of ten observations, 1838-82.)
RING DOVE (*Columba palumbus*) oods. (Average date of four observations, 1884-87.)
- „ 26. BLACKBIRD (*Turdus merula*) whistles. (Average date of sixteen observations, 1801-83.)
COMMON CORMORANT (*Phalacrocorax carbo*) appears at sea-coast. (Average date of seventeen observations, 1862-86.)
- „ 28. WHEATEAR (*Saxicola oenanthe*) arrived 1876. (Earliest of twenty-three observations, 1836-86.)
CORN BUNTING (*Emberiza miliaria*) sings. (Average date of four observations, 1849-84.)
ROOK (*Corvus frugilegus*) begins to nest. (Average date of four observations, 1884-87.)
- Mar. 2. BLUE TITMOUSE (*Parus caeruleus*) spring note heard 1860.
- „ 3. STARLING (*Sturnus vulgaris*) nested 1883. (Earliest of six observations, 1872-83.)

338 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- Mar. 4. MEADOW PIPIT (*Anthus pratensis*) seen 1856. (Earliest of twelve observations, 1856-83.)
 PARTRIDGE (*Perdix cinerea*) began to pair 1856. (Latest of four observations, 1849-82.)
 ROOK (*Corvus frugilegus*) began to nest 1886. (Latest of four observations, 1884-87.)
- „ 5. GREAT TITMOUSE (*Parus major*) calls. (Average date of five observations, 1849-82.)
- „ 7. COOT (*Fulica atra*) returned to ponds, 1881. (Earliest of four observations, 1881-86.)
- „ 10. MISSEL THRUSH (*Turdus viscivorus*) began to sing 1881. (Latest of ten observations, 1843-84.)
 SKYLARK (*Alauda arvensis*) began to sing 1881. (Latest of seventeen observations, 1801-87.)
 GREY WAGTAIL (*Motacilla sulphurea*) arrives at Oldcambus. (Average date of twenty-one observations, 1849-86.)
 GOLDEN PLOVER (*Charadrius pluvialis*) appears in neighbourhood of coast. (Average date of thirteen observations, 1800-86.)
 BLACK-HEADED GULL (*Larus ridibundus*) leaves sea-coast. (Average date of nine observations, 1813-86.)
- „ 12. SONG THRUSH (*Turdus musicus*) commenced to sing 1875. (Latest of twenty observations, 1801-87.)
 RING DOVE (*Columba palumbus*) began to coo 1884. (Latest of four observations, 1884-87.)
 CURLEW (*Numenius arquata*) returns to moors. (Average date of sixteen observations, 1837-87.)
- „ 13. LINNET (*Linota cannabina*) sings. (Average date of four observations, 1836-79.)
- „ 14. CORN BUNTING (*Emberiza miliaria*) arrives at Oldcambus. (Average date of nine observations, 1856-84.)
 CURLEW (*Numenius arquata*) calls. (Average date of eleven observations, 1836-86.)
- „ 15. HEDGE SPARROW (*Accentor modularis*) began to sing 1881. (Latest of ten observations, 1838-87.)
 PIED WAGTAIL (*Motacilla lugubris*) appears. (Average date of twenty-four observations, 1836-87.)
- „ 16. SNIPE (*Gallinago celestis*) "drummed" 1840. (Earliest of six observations, 1837-79.)
- „ 18. MOOR HEN (*Gallinula chloropus*) returns to ponds. (Average date of twelve observations, 1837-86.)
- „ 20. GOLDEN-EYE (*Fuligula clangula*) returned to sea-coast 1886. (Latest of six observations, 1879-86.)
- „ 21. STONECHAT (*Saxicola rubicola*) appears in neighbourhood of coast. (Average date of fifteen observations, 1837-86.)
 ROCK PIPIT (*Anthus obscurus*) on sea-shore. (Average date of six observations, 1868-84.)
- „ 22. RING OUZEL (*Turdus torquatus*) began to sing 1875. (Earliest of three observations, 1875-84.)
- „ 23. CHIFFCHAFF (*Phylloscopus collybita*) arrived 1882. (Earliest of six observations, 1874-87.)

- Mar. 23. WILD GESE (*Anser segetum* and *Anser brachyrhynchus*) leave. (Average date of twenty-three observations, 1801-86.)
- „ 24. SAND MARTIN (*Ottila riparia*) arrived 1884. (Earliest of fourteen observations, 1840-87.)
- WOODCOCK (*Scolopax rusticula*) left 1883. (Earliest of ten observations, 1836-86.)
- WILD DUCK (*Anas boschas*) leaves sea-coast in spring. (Average date of thirteen observations, 1857-86.)
- „ 25. LAPWING (*Vanellus vulgaris*) seen inland 1877. (Latest of twenty-four observations, 1837-87.)
- „ 28. SNOW-BUNTING (*Plectrophanes nivalis*) left 1881.
- „ 30. SOLAN GESE (*Sula bassana*) seen off coast 1881. (Earliest of seven observations, 1873-83.)
- Apr. 1. MEADOW PIPIT (*Anthus pratensis*) arrives. (Average date of twelve observations, 1856-83.)
- „ 4. WREN (*Troglodytes parvulus*) sings. (Average date of six observations, 1849-82.)
- WILLOW WREN (*Phylloscopus trochilus*) arrived 1882. (Earliest of twenty-six observations, 1836-87.)
- CUCKOO (*Cuculus canorus*) arrived 1833. (Earliest of twenty-nine observations, 1821-87.)
- „ 6. REDWING (*Turdus iliacus*) left 1877. (Earliest of two observations, 1877 and 1879.)
- „ 7. FIELDFARE (*Turdus pilaris*) leaves. (Average date of fourteen observations, 1813-87.)
- RING OUZEL (*Turdus torquatus*) arrives. (Average date of thirteen observations, 1860-86.)
- WHINCHAT (*Saxicola rubetra*) came 1872. (Earliest of ten observations, 1837-87.)
- WHEATEAR (*Saxicola cinanthe*) nested 1877.
- MOOR HEN (*Gallinula chloropus*) returned to ponds 1886. (Latest of twelve observations, 1837-86.)
- „ 8. RING OUZEL (*Turdus torquatus*) sings. (Average date of three observations, 1875-84.)
- „ 9. WHEATEAR (*Saxicola cinanthe*) arrives. (Average date of twenty-three observations, 1836-86.)
- CHIFFCHAFF (*Phylloscopus collybita*) comes. (Average date of six observations, 1874-87.)
- COOT (*Fulica atra*) returns to ponds. (Average date of four observations, 1881-86.)
- BLACK-HEADED GULL (*Larus ridibundus*) left coast 1877. (Latest of nine observations, 1813-86.)
- „ 10. SNIBE (*Gallinago caelestis*) had eggs 1883. (Earliest of three observations, 1843-83.)
- „ 11. SWALLOW (*Hirundo rustica*) arrived 1803. (Earliest of forty-three observations, 1800-87.)
- GOLDEN-EYE (*Fuligula clangula*) left coast 1881.
- „ 12. DOTTEREL (*Charadrius morinellus*) arrived 1882. (Earliest of thirteen observations, 1836-86.)

840 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- Apr. 12. BLACKBIRD (*Turdus merula*) began to whistle 1881. (Latest of sixteen observations, 1801-83.)
RING DOVE (*Columba palumbus*) had eggs 1887.
- „ 13. CHAFFINCH (*Fringilla coelebs*) commenced to sing 1886. (Latest of fifteen observations, 1840-87.)
GREAT TITMOUSE (*Parus major*) spring note heard for first time in season 1881. (Latest of five observations, 1849-82.)
- „ 14. WOODCOCK (*Scolopax rusticula*) leaves. (Average date of ten observations, 1836-86.)
- „ 15. MISSEL THRUSH (*Turdus viscivorus*) nested 1860. (Earliest of three observations, 1837-77.)
SNIFE (*Gallinago caelestis*) "drums." (Average date of six observations, 1837-79.)
SOLAN GOOSE (*Sula basanna*) appears off coast. (Average date of seven observations, 1873-83.)
- „ 16. RING OUZEL (*Turdus torquatus*) had young 1882. (Earliest of three observations, 1877-83.)
- „ 17. REDWING (*Turdus iliacus*) leaves. (Average date of two observations, 1877 and 1879.)
- „ 18. BLACKCAP (*Sylvia atricapilla*) arrived 1875. (Earliest of ten observations, 1849-87.)
HOODED CROW (*Corvus cornix*) left 1884.
COMMON CORMORANT (*Phalacrocorax carbo*) seen on coast 1872. (Latest of seventeen observations in spring, 1862-86.)
- „ 21. WREN (*Troglodytes parvulus*) began to sing 1879. (Latest of six observations, 1849-82.)
MARTIN (*Chelidon urbica*) arrived 1874. (Earliest of twenty observations, 1826-86.)
- „ 22. WILD DUCK (*Anas boschas*) left sea-coast 1867. (Latest of thirteen observations, 1857-86.)
LITTLE GREEN (*Podiceps fluviatilis*) returned to ponds 1886.
- „ 23. BLACKCAP (*Sylvia atricapilla*) began to sing 1874. (Earliest of two observations, 1874 and 1881.)
CHIFFCHAFF (*Phylloscopus collybita*) arrived 1874. (Latest of six observations, 1874-87.)
WILLOW WREN (*Phylloscopus trochilus*) arrives. (Average date of twenty-six observations, 1836-87.)
- „ 24. MISSEL THRUSH (*Turdus viscivorus*) nests. (Average date of three observations, 1837-77.)
WOOD WREN (*Phylloscopus sibilatrix*) returned 1874. (Earliest of eleven observations, 1874-87.)
REDSTART (*Phainicura ruticilla*) arrived 1872. (Earliest of seventeen observations, 1850-87.)
- „ 25. ROCK PIPIT (*Anthus obscurus*) seen on sea-shore 1879. (Latest of six observations, 1868-84.)
STARLING (*Sturnus vulgaris*) nests. (Average date of six observations, 1872-83.)
SAND MARTIN (*Ootile riparia*) arrives. (Average date of fourteen observations, 1840-87.)

- Apr. 25. DOTTEREL (*Charadrius morinellus*) left 1882. (Earliest of six observations, 1836-83.)
- „ 26. PIED WAGTAIL (*Motacilla lugubris*) appeared 1847. (Latest of twenty-four observations, 1836-87.)
- SWALLOW (*Hirundo rustica*) arrives. (Average date of forty-three observations, 1800-87.)
- PHEASANT (*Phasianus colchicus*) had young 1887. (Earliest of six observations, 1839-87.)
- CURLEW (*Numenius arguata*) returned to moors 1872. (Latest of sixteen observations, 1837-87.)
- „ 27. SONG THRUSH (*Turdus musicus*) had young 1887. (Earliest of ten observations, 1836-87.)
- „ 28. GOLDEN PLOVER (*Charadrius plumialis*) first spring notes heard 1836. (Latest of eleven observations, 1823-84.)
- GOLDEN PLOVER (*Charadrius plumialis*) seen for first time in spring 1836. (Latest of thirteen observations, 1800-86.)
- COMMON SANDPIPER (*Totanus hypoleucus*) arrived 1887.
- „ 29. REDWING (*Turdus iliacus*) left 1879. (Latest of two observations, 1877 and 1879.)
- YELLOW BUNTING (*Emberiza citrinella*) in song 1837. (Latest of seven observations, 1837-75.)
- ROOK (*Corvus frugilegus*) young appeared outside of nest 1887.
- „ 30. BLACKCAP (*Sylvia atricapilla*) began to sing 1881. (Latest of two observations, 1874 and 1881.)
- TREE PIPT (*Anthus trivialis*) arrived 1887. (Earliest of five observations, 1879-87.)
- LINNET (*Linota cannabina*) in song 1836. (Latest of four observations, 1836-79.)
- WILD DUCK (*Anas boschas*) had young 1887. (Earliest of three observations, 1877-87.)
- May 1. BLACKBIRD (*Turdus merula*) nested 1837.
- WHITETHROAT (*Sylvia rufa*) arrived 1874. (Earliest of sixteen observations, 1857-87.)
- CORN BUNTING (*Emberiza miliaria*) singing 1884. (Latest of four observations, 1849-84.)
- LAPWING (*Vanellus vulgaris*) had young 1874. (Earliest of five observations, 1836-81.)
- LANDRAIL (*Orez pratensis*) arrived 1880. (Earliest of twelve observations, 1800-87.)
- WILD GESE (*Anser segetum* and *Anser brachyrhynchus*) seen 1884. (Latest of twenty-two observations, 1800-86.)
- „ 2. CHAFFINCH (*Fringilla coelebs*) nested 1857. (Earliest of three observations, 1850-76.)
- REDSTART (*Phoenicurus ruticilla*) arrives. (Average date of seventeen observations, 1850-87.)
- CUCKOO (*Cuculus canorus*) arrives. (Average date of twenty-nine observations, 1821-87.)
- „ 3. WOOD WREN (*Phylloscopus sibilatrix*) singing 1875. (Earliest of four observations, 1875-87.)

242 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- May 3. MARTIN (*Ochelidon urtica*) returns. (Average date of twenty observations, 1836-86.)
 WOODCOCK (*Scolopax rusticula*) left 1881. (Latest of ten observations, 1836-86.)
 SOLAN GOOSE (*Sula bassana*) seen off coast 1877. (Latest of seven observations, 1873-83.)
 DOTTEREL (*Charadrius morinellus*) arrives. (Average date of thirteen observations, 1836-86.)
- „ 4. WHEATEAR (*Saxicola ananthe*) arrived 1885. (Latest of twenty-three observations, 1836-86.)
 BLACKCAP (*Sylvia atricapilla*) comes. (Average date of ten observations, 1849-87.)
 MEADOW PIPIT (*Anthus pratensis*) appeared 1890. (Latest of twelve observations, 1856-83.)
- „ 5. REDBREAST (*Erithaca rubecula*) had young 1879. (Earliest of five observations, 1860-81.)
 WHITETHROAT (*Sylvia rufa*) in song 1875. (Earliest of two observations, 1875 and 1881.)
- „ 6. MISSEL THRUSH (*Turdus viscivorus*) nested 1877. (Latest of three observations, 1837-77.)
 CHAFFINCH (*Fringilla caelebs*) nests. (Average date of three observations, 1850-76.)
- „ 7. RING OUZEL (*Turdus torquatus*) has young. (Average date of three observations, 1877-83.)
 RING OUZEL (*Turdus torquatus*) singing 1884. (Latest of three observations, 1875-84.)
- „ 8. STONECHAT (*Saxicola rubicola*) appeared 1886. (Latest of fifteen observations, 1837-86.)
 TREE PIPIT (*Anthus trivialis*) returns. (Average date of five observations, 1879-87.)
 NIGHTJAR (*Caprimulgus europæus*) arrived 1848. (Earliest of eight observations, 1837-86.)
- „ 9. SEDGE WARBLER (*Acrocephalus schoenobaenus*) came 1881. (Earliest of nine observations, 1842-84.)
 WILLOW WREN (*Phylloscopus trochilus*) arrived 1885. (Latest of twenty-six observations of date of arrival, 1836-87.)
 PIED FLYCATCHER (*Muscicapa atricapilla*) seen 1885.
- „ 10. CHAFFINCH (*Fringilla caelebs*) nested 1850. (Latest of three observations, 1850-76.)
 BLACKBIRD (*Turdus merula*) had young 1850. (Earliest of two observations, 1843 and 1850.)
 WOOD WREN (*Phylloscopus sibilatrix*) arrives. (Average date of eleven observations, 1874-87.)
- „ 11. WHITETHROAT (*Sylvia rufa*) arrives. (Average date of sixteen observations, 1857-87.)
 SWALLOW (*Hirundo rustica*) returned 1850. (Latest of forty-three observations, 1800-87.)
 SWIFT (*Cypselus apus*) arrived 1883. (Earliest of thirteen observations, 1849-85.)

- May 11. LANDRAIL (*Orex pratensis*) comes. (Average date of twelve observations, 1800-87.)
- „ 12. SNIFE (*Gallinago caelestis*) "drummed" 1837. (Latest of six observations, 1837-79.)
PIND FLYCATCHER (*Muscicapa atricapilla*) seen 1877.
- „ 13. WHITETHROAT (*Sylvia rufa*) is heard singing. (Average date of two observations, 1875 and 1881.)
- „ 14. MARTIN (*Chelidon urbica*) arrived 1877. (Latest of twenty observations, 1836-86.)
- „ 15. FIELDFARE (*Turdus pilaris*) left 1887. (Latest of fourteen observations, 1813-87.)
WHINCHAT (*Saxicola rubetra*) came 1884. (Latest of ten observations, 1837-87.)
SAND MARTIN (*Cotile riparia*) returned 1877. (Latest of fourteen observations, 1840-87.)
SWIFT (*Cypselus apus*) arrives. (Average date of thirteen observations, 1849-85.)
WILD DUCK (*Anas boschas*) has young. (Average date of three observations, 1877-87.)
- „ 17. SONG THRUSH (*Turdus musicus*) has young. (Average date of ten observations, 1836-87.)
REDSTART (*Phenicura ruticilla*) arrived 1883. (Latest of seven observations, 1850-87.)
NIGHTJAR (*Caprimulgus europæus*) comes. (Average date of eight observations, 1837-86.)
WOOD WREN (*Phylloscopus sibilatrix*) sings. (Average date of four observations, 1875-87.)
- „ 18. GREY WAGTAIL (*Motacilla sulphurea*) appeared 1881. (Latest of twenty-one observations, 1849-86.)
TREE PIPIT (*Anthus trivialis*) arrived 1885. (Latest of five observations, 1879-87.)
- „ 19. SPOTTED FLYCATCHER (*Muscicapa grisola*) came 1881. (Earliest of five observations, 1881-86.)
REDSTART (*Phenicura ruticilla*) nested 1850.
DOTTEREL (*Charadrius morinellus*) arrived 1840. (Latest of thirteen observations, 1836-86.)
- „ 20. DOTTEREL (*Charadrius morinellus*) leaves. (Average date of six observations, 1836-83.)
- „ 21. WHINCHAT (*Saxicola rubetra*) comes. (Average date of ten observations, 1837-87.)
WHITETHROAT (*Sylvia rufa*) singing 1881. (Latest of two observations, 1875 and 1881.)
- „ 22. REDBREAST (*Erithaca rubecula*) has young. (Average date of five observations, 1860-1881.)
GARDEN WARBLER (*Sylvia salicaria*) arrived 1884. (Earliest of two observations, 1879-84.)
SPOTTED FLYCATCHER (*Muscicapa grisola*) arrives. (Average date of five observations, 1881-86.)
RING OUSEL (*Turdus torquatus*) came 1884. (Latest of thirteen observations, 1860-86.)

344 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- May 22. BLACKCAP (*Sylvia atricapilla*) arrived 1880. (Latest of ten observations, 1849-87.)
 WHITETHROAT (*Sylvia rufo*) returned 1885. (Latest of sixteen observations, 1857-87.)
 WOOD WREN (*Phylloscopus sibilatrix*) arrived 1880. (Latest of eleven observations, 1874-87.)
- „ 23. GARDEN WARBLER (*Sylvia salicaria*) comes. (Average date of two observations, 1879-84.)
- „ 24. COOT (*Fulica atra*) returned to ponds 1882. (Latest of four observations, 1881-86.)
- „ 25. SPOTTED FLYCATCHER (*Muscicapa grisola*) arrived 1883. (Latest of five observations, 1881-86.)
 LAPWING (*Vanellus vulgaris*) has young. (Average date of five observations, 1836-81.)
 GARDEN WARBLER (*Sylvia salicaria*) arrived 1879. (Latest of two observations.)
- „ 26. SEDGE WARBLER (*Acrocephalus schoenobaenus*) arrives. (Average date of nine observations, 1842-84.)
- „ 27. CUCKOO (*Cuculus canorus*) arrived 1872. (Latest of twenty-nine observations, 1821-87.)
 NIGHTJAR (*Caprimulgus europæus*) heard 1857. (Earliest of two observations, 1837 and 1843.)
- „ 28. GRASSHOPPER WARBLER (*Acrocephalus navius*) heard 1888. (Earliest of two observations, 1876-88.)
- „ 29. LANDRAIL (*Orez pratensis*) arrived 1812. (Latest of twelve observations, 1800-87.)
- „ 30. SWIFT (*Cypselus apus*) arrived 1863. (Latest of thirteen observations, 1849-85.)
 CURLEW (*Numenius arquata*) spring note heard 1863. (Latest of eleven observations, 1836-86.)
 WOOD WREN (*Phylloscopus sibilatrix*) singing 1883. (Latest of four observations, 1875-87.)
- June 4. SNIFE (*Gallinago calesia*) has eggs. (Average date of three observations, 1843-83.)
- „ 5. NIGHTJAR (*Caprimulgus europæus*) arrived 1896. (Latest of eight observations, 1837-86.)
- „ 6. DOTTEREL (*Ocharadrius morinellus*) left 1836. (Latest of six observations, 1836-83.)
- „ 7. STARLING (*Sturnus vulgaris*) nested 1880. (Latest of six observations, 1872-83.)
- „ 9. GRASSHOPPER WARBLER (*Acrocephalus navius*) heard 1876. (Latest of two observations, 1876-88.)
- „ 10. LAPWING (*Vanellus vulgaris*) had young 1838. (Latest of five observations, 1836-81.)
- „ 13. CORN BUNTING (*Emberiza miliaria*) arrived at Oldcambus 1884. (Latest of nine observations, 1856-84.)
 PARTRIDGE (*Perdix cinerea*) had eggs 1872.
- „ 14. NIGHTJAR (*Caprimulgus europæus*) is heard. (Average date of two observations, 1837 and 1843.)

- June 14. PHEASANT (*Phasianus colchicus*) has young. (Average date of six observations, 1839-87.)
- „ 15. STONECHAT (*Saxicola rubicola*) had young 1874. (Earliest of three observations, 1874-84.)
LAPWING (*Vanellus vulgaris*) began to flock 1842. (Earliest of twelve observations, 1842-83.)
- „ 16. RING OUZEL (*Turdus torquatus*) had young 1877. (Latest of three observations, 1877-83.)
CURLEW (*Numenius arquata*) returned to shore 1875. (Earliest of twelve observations, 1836-86.)
WILD DUCK (*Anas boschas*) had young 1877. (Latest of three observations, 1877-87.)
- „ 18. CUCKOO (*Cuculus canorus*) last heard 1837. (Earliest of six observations, 1837-81.)
- „ 19. BLACKBIRD (*Turdus merula*) had young 1843. (Latest of two observations, 1843 and 1850.)
WHEATEAR (*Saxicola cinerula*) had young 1882.
PARTRIDGE (*Perdix cinerea*) had young 1872. (Earliest of four observations, 1837-85.)
- „ 21. STONECHAT (*Saxicola rubicola*) has young. (Average date of three observations, 1874-84.)
- „ 22. REDBREAST (*Erithaca rubecula*) had young 1881. (Latest of five observations, 1860-81.)
BLACK-HEADED GULL (*Larus ridibundus*) returned to coast 1878. (Earliest of fourteen observations, 1868-84.)
- „ 23. SEDGE WARBLER (*Acrocephalus schoenobaenus*) arrived 1842. (Latest of nine observations, 1842-84.)
CUCKOO (*Cuculus canorus*) last heard. (Average date of six observations, 1837-81.)
- „ 25. PARTRIDGE (*Perdix cinerea*) has young. (Average date of four observations, 1837-85.)
- „ 28. REDSTART (*Phoenicurus phoenicurus*) had young 1874.
- „ 30. PARTRIDGE (*Perdix cinerea*) had young 1885. (Latest of four observations, 1837-85.)
- July 1. SONG THRUSH (*Turdus musicus*) had young 1839. (Latest of ten observations, 1836-87.)
CUCKOO (*Cuculus canorus*) last heard 1838. (Latest of six observations, 1837-81.)
- „ 3. NIGHTJAR (*Caprimulgus europaeus*) first heard 1843. (Latest of two observations, 1837 and 1843.)
- „ 4. STONECHAT (*Saxicola rubicola*) had young 1884. (Latest of three observations, 1874-84.)
- „ 6. COMMON CORMORANT (*Phalacrocorax carbo*) seen on sea-shore 1872. (Earliest of twelve observations, 1863-86.)
- „ 10. ROCK PIPIT (*Anthus obscurus*) had eggs 1868.
- „ 15. BLACK-HEADED GULL (*Larus ridibundus*) returns to sea-coast. (Average date of fourteen observations, 1868-84.)
CUCKOO (*Cuculus canorus*) young were seen flying 1842.

346 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- July 17. SNIFE (*Gallinago calesias*) had eggs 1845. (Latest of three observations, 1843-83.)
- „ 19. PHEASANT (*Phasianus colchicus*) had young 1877. (Latest of six observations, 1839-87.)
- „ 27. NIGHTJAR (*Caprimulgus europæus*) nested 1839.
- Aug. 3. WOOD WREN (*Phylloscopus sibilatrix*) left 1882. (Earliest of two observations, 1882 and 1883.)
- „ 5. SWIFT (*Cypselus apus*) left 1881. (Earliest of seven observations, 1873-85.)
- „ 6. WHEATEAR (*Saxicola œnanthe*) left 1873. (Earliest of ten observations, 1863-85.)
- CURLEW (*Numenius arquata*) returns to sea-shore. (Average date of twelve observations, 1836-86.)
- „ 7. BLACK-HEADED GULL (*Larus ridibundus*) returned to coast 1872. (Latest of fourteen observations, 1868-84.)
- „ 10. SWALLOW (*Hirundo rustica*) flocked 1857. (Earliest of four observations, 1857-85.)
- „ 14. GOLDEN PLOVER (*Charadrius pluvialis*) flocked on moors 1856. (Earliest of three observations, 1836-56.)
- „ 15. WHITETHROAT (*Sylvia rufa*) left 1873. (Earliest of ten observations, 1873-85.)
- WILLOW WREN (*Phylloscopus trochilus*) left 1879. (Earliest of nine observations, 1857-84.)
- „ 16. REDBREAST (*Erithaca rubecula*) in song 1868. (Earliest of eight autumnal observations, 1814-82.)
- „ 17. COMMON CORMORANT (*Phalacrocorax carbo*) first seen on sea-coast. (Average date of twelve observations, 1863-86.)
- „ 20. LAPWING (*Vanellus vulgaris*) flocks. (Average date of twelve observations, 1842-83.)
- „ 21. WOOD WREN (*Phylloscopus sibilatrix*) leaves. (Average date of two observations, 1882 and 1883.)
- MARTIN (*Chelidon urbica*) flocked 1860. (Earliest of four observations, 1857-80.)
- „ 22. SWIFT (*Cypselus apus*) leaves. (Average date of seven observations, 1873-85.)
- „ 25. STARLING (*Sturnus vulgaris*) flocked 1881. (Earliest of nine observations, 1857-85.)
- CUCKOO (*Cuculus canorus*) left 1881.
- „ 27. SPOTTED FLYCATCHER (*Muscicapa grisola*) left 1881.
- „ 29. GOLDEN PLOVER (*Charadrius pluvialis*) flocks on moors. (Average date of three observations, 1836-56.)
- „ 30. SWALLOW (*Hirundo rustica*) flocks. (Average date of four observations, 1857-85.)
- Sept. 1. SPOTTED FLYCATCHER (*Muscicapa grisola*) left 1884.
- WHINCHAT (*Saxicola rubetra*) left 1884.
- SEDGE WARBLER (*Acrocephalus schoenobaenus*) left 1884.

- Sept. 2. LINNET (*Linota cannabina*) flocked 1874. (Earliest of six observations, 1836-80.)
- „ 4. MEADOW PIPIT (*Anthus pratensis*) left 1883. (Earliest of five observations, 1890-85.)
MARTIN (*Chelidon urbica*) flocks. (Average date of four observations, 1857-80.)
- „ 6. REDSTART (*Phoenicurus rubicilla*) left 1878. (Earliest of four observations, 1872-83.)
WILLOW WREN (*Phylloscopus trochilus*) leaves. (Average date of nine observations, 1857-84.)
- „ 7. WHEATEAR (*Saxicola oenanthe*) leaves. (Average date of ten observations, 1863-85.)
- „ 8. WHITETHROAT (*Sylvia rufa*) leaves. (Average date of ten observations, 1873-85.)
- „ 10. WOOD WREN (*Phylloscopus sibilatrix*) left 1883. (Latest of two observations, 1882-83.)
- „ 11. SWALLOW (*Hirundo rustica*) left 1881. (Earliest of twenty-three observations, 1822-85.)
MARTIN (*Chelidon urbica*) left 1881. (Earliest of thirteen observations, 1836-85.)
SAND MARTIN (*Cotile riparia*) left 1881. (Earliest of nine observations, 1836-85.)
- „ 12. SWIFT (*Cypselus apus*) left 1879. (Latest of seven observations, 1873-85.)
- „ 13. SKYLARK (*Alauda arvensis*) singing 1875. (Earliest of four autumnal observations, 1833-75.)
- „ 14. REDBREAST (*Erithaca rubecula*) sings. (Average date of eight observations, 1814-82.)
- „ 15. STONECHAT (*Saxicola rubicola*) left neighbourhood of sea-coast 1849. (Earliest of thirteen observations, 1837-84.)
SAND MARTIN (*Cotile riparia*) flocked 1880. (Earliest of two observations, 1876 and 1890.)
- „ 17. BLACKCAP (*Sylvia atricapilla*) left 1884. (Earliest of two observations, 1883 and 1884.)
GARDEN WARBLER (*Sylvia salicaria*) left 1883 and 1884.
- „ 18. WILD DUCK (*Anas boschas*) returned to sea 1879. (Earliest of eleven observations, 1873-84.)
- „ 19. MISSEL THRUSH (*Turdus viscivorus*) flocked 1822. (Earliest of eight observations, 1822-81.)
- „ 20. GOLDEN PLOVER (*Charadrius plumalis*) flocked on moors 1836. (Latest of three observations, 1836-56.)
- „ 21. SWALLOW (*Hirundo rustica*) flocked 1884. (Latest of four observations, 1857-85.)
- „ 22. SAND MARTIN (*Cotile riparia*) leaves. (Average date of nine observations, 1836-85.)
LANDRAIL (*Orex pratensis*) left 1881.
- „ 24. SKYLARK (*Alauda arvensis*) sings. (Average date of four autumnal observations, 1833-75.)

348 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- Sept. 24. CHAFFINCH (*Fringilla coelebs*) flocked 1850.
 YELLOW-BUNTING (*Emberiza citrinella*) in flocks 1850.
 MARTIN (*Chelidon urbica*) leaves. (Average date of thirteen observations, 1836-85.)
- „ 25. SWALLOW (*Hirundo rustica*) leaves. (Average date of twenty-three observations, 1822-85.)
- „ 26. DOTTEREL (*Charadrius morinellus*) seen 1837. (Earliest of five autumnal observations, 1837-75.)
- „ 27. BLACKCAP (*Sylvia atricapilla*) left 1863.
 PIED WAGTAIL (*Motacilla lugubris*) disappeared 1883. (Earliest of five observations, 1873-83.)
 MEADOW PIPIT (*Anthus pratensis*) leaves neighbourhood of Old-cambus. (Average date of five observations, 1890-85.)
- „ 28. REDSTART (*Phoenicurus ruticilla*) leaves. (Average date of four observations, 1872-83.)
 DOTTEREL (*Charadrius pluvialis*) is seen on migration southwards. (Average date of five autumnal observations, 1837-75.)
- „ 29. WILLOW WREN (*Phylloscopus trochilus*) left 1881. (Latest of nine observations, 1857-84.)
 MARTIN (*Chelidon urbica*) flocked 1876. (Latest of four observations, 1857-80.)
 SAND MARTIN (*Cotile riparia*) flocked 1876. (Latest of two observations, 1876 and 1880.)
- „ 30. DOTTEREL (*Charadrius morinellus*) seen on migration southwards 1875. (Latest of five autumnal observations, 1837-75.)
 CURLEW (*Numenius arquata*) returned to shore 1836. (Latest of twelve observations, 1836-86.)
- Oct. 1. SNOW-BUNTING (*Plectrophanes nivalis*) arrived 1851. (Earliest of sixteen observations, 1812-86.)
 WILD GESE (*Anser segetum* and *Anser brachyrhynchus*) seen 1884. (Earliest of twenty-two observations, 1800-86.)
- „ 2. SKYLARK (*Alauda arvensis*) singing 1837. (Latest of four autumnal observations, 1833-75.)
 GREY WAGTAIL (*Motacilla sulphurea*) left neighbourhood of Old-cambus 1879. (Earliest of two observations, 1878 and 1879.)
- „ 4. PIED WAGTAIL (*Motacilla lugubris*) disappears. (Average date of five observations, 1873-83.)
- „ 5. ROOK PIPIT (*Anthus obscurus*) seen on sea-shore 1878.
 WOODCOCK (*Scolopax rusticula*) arrived 1882. (Earliest of twelve observations, 1835-83.)
- „ 6. STARLING (*Sturnus vulgaris*) flocks. (Average date of nine observations, 1857-85.)
- „ 9. SWALLOW (*Hirundo rustica*) left 1874. (Latest of twenty-three observations, 1822-85.)
 MARTIN (*Chelidon urbica*) left 1874. (Latest of thirteen observations, 1836-85.)
 SAND MARTIN (*Cotile riparia*) left 1874. (Latest of nine observations, 1836-85.)

- Oct. 11. LINNET (*Linota cannabina*) flocks. (Average date of six observations, 1836-80.)
- „ 12. WHINCHAT (*Saxicola rubetra*) left 1883. (Latest of two observations, 1883 and 1884.)
WILD DUCK (*Anas boschas*) returns to sea. (Average date of eleven observations, 1873-84.)
FIELDFARE (*Turdus pilaris*) arrived 1874. (Earliest of twenty-two observations, 1799-1886.)
- „ 13. WHITETHROAT (*Sylvia rufa*) left 1884. (Latest of ten observations, 1873-85.)
- „ 14. WHEATEAR (*Saxicola oenanthe*) left 1879. (Latest of ten observations, 1863-85.)
- „ 16. REDSTART (*Erithaca rubecula*) singing 1836. (Latest of eight autumnal observations, 1814-82.)
- „ 18. WOODCOCK (*Scolopax rusticula*) arrives. (Average date of twelve observations, 1835-83.)
- „ 20. RING OUZEL (*Turdus torquatus*) left 1833. (Earliest of four observations, 1857-83.)
- „ 21. PIED WAGTAIL (*Motacilla lugubris*) disappeared 1874. (Latest of five observations, 1873-83.)
- „ 23. LAFWING (*Vanellus vulgaris*) flocked 1860. (Latest of twelve observations, 1842-83.)
- „ 24. WREN (*Troglodytes parvulus*) singing 1863.
- „ 26. MINSEL THRUSH (*Turdus viscivorus*) flocks. (Average date of eight observations, 1822-81.)
SKYLARK (*Alauda arvensis*) flocked 1857. (Earliest of three observations, 1857-80.)
WILD GEESE (*Anser segetum* and *Anser brachyrhynchus*) are first seen. (Average date of twenty-two autumnal observations, 1800-86.)
COMMON CORMORANT (*Phalacrocorax carbo*) first seen on sea-coast 1877. (Latest of twelve observations, 1863-86.)
- „ 27. REDWING (*Turdus iliacus*) arrived 1879. (Earliest of five observations, 1860-84.)
TREE PIPIT (*Anthus trivialis*) left 1837.
- „ 29. COOT (*Fulica atra*) left ponds 1881.
- „ 31. STONECHAT (*Saxicola rubicola*) leaves neighbourhood of sea-coast. (Average date of thirteen observations, 1837-84.)
- Nov. 1. LITTLE GREEBE (*Podiceps fluviatilis*) left ponds 1876.
- „ 3. WILD DUCK (*Anas boschas*) returned to sea 1873. (Latest of eleven observations, 1873-84.)
- „ 7. FIELDFARE (*Turdus pilaris*) arrives. (Average date of twenty-two observations, 1799-1886.)
- „ 8. REDSTART (*Phoenicurus rubicilla*) left 1872. (Latest of four observations, 1872-83.)
- „ 9. SNOW BUNTING (*Plectrophanes nivalis*) arrives. (Average date of sixteen observations, 1812-86.)
WOODCOCK (*Scolopax rusticula*) arrived 1884. (Latest of twelve observations, 1835-83.)

350 MIGRATIONS AND OBSERVATIONS OF BIRDS.

- Nov. 11. RING OUZEL (*Turdus torquatus*) leaves. (Average date of four observations, 1857-83.)
- „ 12. MEADOW PIPIT (*Anthus pratensis*) left 1880. (Latest of five observations, 1880-85.)
- „ 16. REDWING (*Turdus iliacus*) arrives. (Average date of five observations, 1860-84.)
- „ 18. GREY WAGTAIL (*Motacilla sulphurea*) disappeared 1878. (Latest of two observations, 1878 and 1879.)
- „ 21. SKYLARK (*Alauda arvensis*) flocks. (Average date of three observations, 1857-80.)
- „ 22. RING OUZEL (*Turdus torquatus*) left 1857. (Latest of four observations, 1857-83.)
- Dec. 14. REDWING (*Turdus iliacus*) arrived 1878. (Latest of five observations, 1860-84.)
- LINNET (*Linota cannabina*) left Oldcambus 1878.
- „ 15. WILD GEESE (*Anser segetum* and *Anser brachyrhynchus*) first seen 1881. (Latest of twenty-two observations, 1800-86.)
- „ 16. SKYLARK (*Alauda arvensis*) flocked 1880. (Latest of three observations, 1857-80.)
- „ 17. STONECHAT (*Saxicola rubicola*) disappeared 1882. (Latest of thirteen observations, 1837-84.)
- „ 19. MISSEL THRUSH (*Turdus viscivorus*) flocked 1871. (Latest of eight observations, 1822-81.)
- FIELDFARE (*Turdus pilaris*) arrived 1871. (Latest of twenty-two observations, 1799-1886.)
- STARLING (*Sturnus vulgaris*) flocked 1871. (Latest of nine observations, 1857-85.)
- „ 23. BRAMBLING (*Fringilla montifringilla*) arrived 1874. (Earliest of three observations, 1857-81.)
- „ 26. CORN BUNTING (*Emberiza miliaria*) arrived at Oldcambus 1863. (Earliest of nine observations, 1856-84.)
- „ 31. CORN BUNTING (*Emberiza miliaria*) singing 1863. (Earliest of four observations, 1849-84.)
- LINNET (*Linota cannabina*) flocked 1880. (Latest of six observations, 1836-80.)



TABLE showing the earliest, latest, and average dates of the arrivals and departures of the true migratory birds which visit Berwickshire annually, with approximate notes regarding the average temperatures, and the prevailing winds, during the periods when their migrations took place, 1799-1887.

The following abbreviations are used in the table:—

br. for breeze. fo. for fog. h. for haze. r. for rain. sn. for snow.
 a. " clear. fr. " fresh. l. " light. sh. " showers. sq. " squalls.
 ca. " calm. g. " gale. mo. " moderate. sl. " slight. st. " strong.
 cl. " cloudy.

Birds.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Temperature of month at Milne Graden, in degrees Fahrenheit.		Prevailing wind at St. Abb's Head during week previous to arrival or departure, with notes on weather.	Latest Date.	Temperature of month at Milne Graden, in degrees Fahrenheit.		Prevailing wind at St. Abb's Head during week previous to arrival or departure, with notes on weather.	Average Date of Arrival and Departure.
					Above Average.	Below Average.			Above Average.	Below Average.		
BIRDS WHICH ARRIVE IN SPRING AND LEAVE IN AUTUMN.												
Ring Ouzel (<i>Turdus torquatus</i>)	1860	1886	13	1872 Feb. 15	2.5		From Feb. 8, at br., h.	1884 May 22	0.6		From May 15, W-SW, at br.; 21, W-SW, at br.	April 7
Leaves in autumn	1857	1883	4	1883 Oct. 20	normal		From Oct. 13, S-SE, fr. br.; 16, S-SW, at br., c.	1857 Nov. 23	8.8			Nov. 11
Whinchat (<i>Scolecops oenanthe</i>)	1886	1886	23	1876 Feb. 28		0.9	From Feb. 21, SE-SW, fr. br.; 24, W-SW, g. l. br., h., c.	1885 May 4		0.3	From April 23, SW-SE, l. br.; May 1, SE-E-NE, l. br.	April 9
Leaves in autumn	1863	1885	10	1878 Aug. 6	1.9		From July 31, SW-NW, l. br., h., c.	1879 Oct. 14		1.3	From Oct. 7, SW, l. br.; 11, SW-NW, l. br., h.	Sept. 7
Whinchat (<i>Scolecops rubetra</i>)	1837	1887	10	1872 April 7	3.1		From April 1, E-NE, at br.; 5, SW, l. br., h.	1884 May 15		0.6	From May 8, SE-SW, fr. br.; 12, SW, fr. br., sh.	April 21
Leaves in autumn	1883	1884	3	1884 Sept. 1			From Aug. 25, SW-NW, fr. br.; 27, S-NE, 30, SW, l. br.	1885 Oct. 12			From Oct. 5, NW-N, fr. br.; 7, S-W-W, fr. br.; 10, E, sh.	Sept. 20
Redstart (<i>Phoenicurus phoenicurus</i>)	1860	1887	17	1872 April 24	1.3		From April 17, N-NW; 20, N-NE, fr. br., sh.	1883 May 17		0.5	From May 10, N-NW, l. br., r.; 12, W-SW, fr. br., c.	May 2
Leaves in autumn	1872	1883	4	1878 Sept. 6	0.9		From Aug. 31, E-NNW, fr. br.; Sept. 5, SW-E, fr. br., c.	1873 Nov. 8		1.0	From Nov. 1, WSW-N, l. br.; 4, N-E, g., cl.	Sept. 20

Birds.	First Year of Observation.	Last Year of Observation.	Number of Observations.	Earliest Date.	Temperature of month at Milne Graden, in degrees Fahrenheit.		Prevailing wind at St. Abb's Head during week previous to arrival or departure, with notes on weather.	Latest Data.	Temperature of month at Milne Graden, in degrees Fahrenheit.		Prevailing wind at St. Abb's Head during week previous to arrival or departure, with notes on weather.	Average Date of Arrival and Departure.
					Above Average.	Below Average.			Above Average.	Below Average.		
BIRDS WHICH ARRIVE IN SPRING AND LEAVE IN AUTUMN—continued.												
WHITEROBAT (<i>Sylvia arctica</i>) Arrives in spring Leaves in autumn	1857 1873	1887 1886	16 10	1874 May 1 1878 Aug. 15	2.9 0.4		From April 24, SE-SW, 1 br.; 27, S, 1 br. c. From Aug. 8, W, 8, W-NW; 13 and 14, 8, sh.	1885 May 23 1884 Oct. 18		2.6 normal	From May 14, SW-W, 1 br.; 17, N, 1 br.; From Oct. 6, NW, 1 br.; 9, SW; 11, NNW, 8.	May 11 Sept. 8
BLACKCAP (<i>Sylvia arctophila</i>) Arrives in spring Leaves in autumn	1849 1888	1887 1884	10 2	1876 April 18 1884 Sept. 17	2.1		From April 11, NNE, 1 br., h. fo. all the week. From Sept. 10, SE, 1 br., h.; 13, NW-NE, 1 br., r.	1880 May 23 1883 Sept. 27		0.6	From May 16, NE-NW, 1 br., c.; 19, SE, 1 br.; From Sept. 20, NE-E, 1 br.; 24, SE-SW, 1 br., sh.	May 4 Sept. 14
GARDEN WARBLER (<i>Sylvia silioleuca</i>) Arrives in spring Leaves in autumn	1879 1883	1884 1884	2 2	1884 May 22 1883 Sept. 17	0.6		From May 15, W-NW, 1 br.; 16, W-NW, 1 br. c. From Sept. 10, S-SW, 1 br., h.; 21, E-NW, 1 br., fo.	1879 May 25 1884 Sept. 17		2.2	From May 18, SE, 1 br., h.; 21, E-S, 1 br., r. From Sept. 10, SE, 1 br., h.; 15, NW, 1 br., r.	May 23 Sept. 17
ORIOLEAF (<i>Phylloscopus collybita</i>) Arrives in spring	1874	1887	6	1882 Mar. 23	3.7		From Mar. 16, W-SW, 1 br.; 20, W-SW, 1 br.; 23, W, 8.	1874 April 23	2.9		From April 16, W-SW, 1 br.; SW-SE, 1 br., h.	April 9
WILLOW WREN (<i>Phylloscopus trochilus</i>) Arrives in spring Leaves in autumn	1886 1887	1887 1884	26 9	1882 April 4 1879 Aug. 15	3.7 1.2		From Mar. 29, SW-W, 1 br., c.; 30, 31, April 1, 1 br. From Aug. 8, W-NW, 1 br.; SE-NW, 1 br., c.	1885 May 9 1881 Sept. 29		2.6 1.6	From May 2, SW-SE, 1 br., fo.; 6, NE, 8, br., c. From Sept. 22, E-SE, h.; 25, W, 1 br.; 29, SW, r.	April 22 Sept. 6
WOOD WREN (<i>Phylloscopus sibilatrix</i>) Arrives in spring Leaves in autumn	1878 1889	1887 1888	12 5	1874 April 24 1882 Aug. 8	3.9		From April 17, W-SW, 1 br.; SW-SE, 1 br., h.	1880 May 23 1883 Sept. 10		0.3	From May 15, NE-NW, 1 br., c.; 16, SE-W, 1 br.; 17, SE, 1 br., h.; 18, SE, 1 br., h.; 19, SE, 1 br., h.; 20, SE, 1 br., h.; 21, SE, 1 br., h.; 22, SE, 1 br., h.; 23, SE, 1 br., h.; 24, SE, 1 br., h.; 25, SE, 1 br., h.; 26, SE, 1 br., h.; 27, SE, 1 br., h.; 28, SE, 1 br., h.; 29, SE, 1 br., h.; 30, SE, 1 br., h.; 31, SE, 1 br., h.	May 10 Aug. 27

DATE	NO.	NAME	SEX	AGE	DATE	NO.	NAME	SEX	AGE	DATE	NO.	NAME	SEX	AGE	DATE	NO.	NAME	SEX	AGE	DATE	NO.	NAME	SEX	AGE
1884	1	LEAVES IN AUTUMN			1884	1	LEAVES IN AUTUMN			1884	1	LEAVES IN AUTUMN			1884	1	LEAVES IN AUTUMN			1884	1	LEAVES IN AUTUMN		
1876	1886	GRASSHOPPER WARRLER (<i>Loricophanes</i> <i>novius</i>)	1886	May 26	1886	1886	May 26	1886	May 26	1886	1886	May 26	1886	May 26	1886	1886	May 26	1886	May 26	1886	1886	May 26	1886	May 26
1879	1887	THORN FINCH (<i>Amphispiza bilineata</i>)	1887	April 20	1887	1887	April 20	1887	April 20	1887	1887	April 20	1887	April 20	1887	1887	April 20	1887	April 20	1887	1887	April 20	1887	April 20
1887	1	LEAVES IN AUTUMN	1	Oct. 27	1887	1	LEAVES IN AUTUMN	1	Oct. 27	1887	1	LEAVES IN AUTUMN	1	Oct. 27	1887	1	LEAVES IN AUTUMN	1	Oct. 27	1887	1	LEAVES IN AUTUMN	1	Oct. 27
1881	1886	SPOTTED PLOCEUS (<i>Micropodops</i> <i>griseus</i>)	1886	May 19	1881	1886	May 19	1881	1886	May 19	1881	1886	May 19	1881	1886	May 19	1881	1886	May 19	1881	1886	May 19	1881	1886
1881	1884	LEAVES IN AUTUMN	1884	Aug. 27	1881	1884	Aug. 27	1881	1884	Aug. 27	1881	1884	Aug. 27	1881	1884	Aug. 27	1881	1884	Aug. 27	1881	1884	Aug. 27	1881	1884
1880	1887	SWALLOW (<i>Hirundo rustica</i>)	1887	April 11	1880	1887	April 11	1880	1887	April 11	1880	1887	April 11	1880	1887	April 11	1880	1887	April 11	1880	1887	April 11	1880	1887
1882	1885	LEAVES IN AUTUMN	1885	Sept. 11	1882	1885	Sept. 11	1882	1885	Sept. 11	1882	1885	Sept. 11	1882	1885	Sept. 11	1882	1885	Sept. 11	1882	1885	Sept. 11	1882	1885
1886	1886	MARTIN (<i>Chelidon virens</i>)	1886	April 21	1886	1886	April 21	1886	April 21	1886	1886	April 21	1886	April 21	1886	1886	April 21	1886	April 21	1886	1886	April 21	1886	April 21
1886	1885	LEAVES IN AUTUMN	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885
1840	1887	SAND MARTIN (<i>Oedipoda riparia</i>)	1887	Mar. 24	1840	1887	Mar. 24	1840	1887	Mar. 24	1840	1887	Mar. 24	1840	1887	Mar. 24	1840	1887	Mar. 24	1840	1887	Mar. 24	1840	1887
1886	1885	LEAVES IN AUTUMN	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885	Sept. 11	1886	1885
1849	1885	SWIFT (<i>Oxyechus opus</i>)	1885	May 11	1849	1885	May 11	1849	1885	May 11	1849	1885	May 11	1849	1885	May 11	1849	1885	May 11	1849	1885	May 11	1849	1885
1878	1886	LEAVES IN AUTUMN	1886	Aug. 5	1878	1886	Aug. 5	1878	1886	Aug. 5	1878	1886	Aug. 5	1878	1886	Aug. 5	1878	1886	Aug. 5	1878	1886	Aug. 5	1878	1886
1887	1886	NIGHTJAR (<i>Caprimulgus europaeus</i>)	1886	May 8	1887	1886	May 8	1887	1886	May 8	1887	1886	May 8	1887	1886	May 8	1887	1886	May 8	1887	1886	May 8	1887	1886

Arrives	1812	1826	16	Oct. 1 1881	1.4	From Mar. 21, NW, l. br.; 28, SW, fr. br., c.	Jan. 20	4.6		From Jan. 12, W-NW, fr. br.; 16, SW, l. br., h.	Nov. 9
Leaves	1881		1	Mar. 28							
Belted Gooen (<i>Asar septem</i>) and Fork-footed Gooen (<i>Asar brachy-</i> <i>rhynchos</i>)											
Arrive in autumn	1800	1886	22	1884 Oct. 1	1.2	From Sept. 25, SW-W, fr. br.; 26, SW, st. br., c.	1881 Dec. 16 1884 May 1	0.8	1.6	From Dec. 8, SW, fr. br., c.; 11, N-NE, st. From April 25, SE-E, l. br.; E, l. br., c.	Oct. 20 Mar. 23
Leave in spring	1801	1886	23	1884 Jan. 9							
BIRD OF PASSAGE.											
Dotterel (<i>Charadrius morinellus</i>)											
Arrives in spring on passage to the north	1886	1886	13	1883 April 12 1883	1.1	From April 5, W, l. br.; 8, SW-W, st. br.	1840 May 19 1886		1.6		May 3 May 20
Leaves in spring for the north	1886	1883	6	April 25 1887	1.1	From April 18, SE-S, st. br.; 20, NW, st. br.	June 6 1875	2.4			
Seen in autumn on passage to the south.	1887	1875	5	Sept. 26	2.3		Sept. 20	2.0		From Sept. 23, NE-E, st. br.; W, st. br., r.	Sept. 23

NOTES.—I have to thank the Scottish Meteorological Society, and my friend Dr. Alexander Buchan, their Secretary, for allowing me to have access to the meteorological schedules kept by observers in the lighthouse at St. Abb's Head, from which the above information about the wind and weather has been obtained. The terms used in the table with regard to wind and weather are as they appear in the observers' monthly schedules.

When the arrival or departure of a bird has taken place in the first week of any month, the average temperature of the previous month is given. The average temperatures before 1857 are taken from a table of "Mean Monthly Temperatures at different places in Scotland, from January 1764 to December 1892." See *Journal of the Scottish Meteorological Society*, vol. ix. pp. 228, 229.

MEAN monthly temperatures at Milne Graden, Berwickshire, from 1st January 1857 to 31st December 1887, taken from the *Journals* of the Scottish Meteorological Society, 1857-87.

Milne Graden is situated on the north bank of the Tweed, about nine miles south-west of Berwick-on-Tweed. Its height above the level of the sea is 100 feet.

YEAR.	JAN.	FEB.	MARCH.	APRIL.	MAY.	JUNE.	JULY.	AUG.	SEPT.	OCT.	NOV.	DEC.	MEAN OF YEAR.
1857	36.2	39.5	39.6	43.7	50.8	57.8	58.5	60.4	56.1	51.3	43.8	45.0	48.5
1858	38.6	35.1	40.1	44.9	50.4	61.3	58.8	59.0	55.5	45.9	39.2	38.5	47.1
1859	39.2	40.0	44.5	42.0	51.0	55.9	59.0	58.2	53.1	46.7	39.0	32.8	46.7
1860	36.5	34.6	38.8	41.2	52.5	54.7	57.3	55.3	50.8	47.2	38.4	32.0	44.9
1861	34.8	39.0	40.8	44.8	48.8	56.8	57.4	59.0	54.7	49.7	38.4	36.2	46.7
1862	37.6	40.8	38.4	45.6	52.4	53.4	54.6	56.9	54.0	47.8	36.6	42.6	46.7
1863	39.2	42.0	44.4	45.9	50.1	55.1	56.4	56.4	51.7	47.9	43.6	41.1	47.8
1864	35.5	32.6	39.0	47.4	51.2	54.4	56.8	55.6	53.8	46.6	41.4	39.6	46.1
1865	34.4	32.3	37.4	47.0	51.7	57.0	59.9	56.6	59.4	47.0	41.6	42.0	47.1
1866	40.2	38.0	38.8	43.9	48.8	56.9	57.9	56.3	52.2	49.0	41.6	40.6	47.0
1867	31.2	42.0	37.4	46.4	49.0	55.6	56.2	59.3	55.2	47.4	41.6	38.6	46.6
1868	37.6	42.8	43.4	47.6	52.7	57.2	61.2	60.4	54.8	45.8	40.4	41.9	48.7
1869	40.6	42.9	38.8	47.9	46.0	54.8	61.0	58.0	55.9	47.8	41.0	36.0	47.6
1870	35.2	35.6	39.8	48.1	50.7	56.7	60.6	58.5	54.6	47.2	39.9	34.0	46.6
1871	32.0	41.2	43.4	43.2	50.9	53.2	58.4	60.5	52.8	47.4	38.0	27.2	46.2

1873	39.3	41.0	43.2	45.7	49.2	57.3	60.7	67.2	62.3	50.0	44.7	41.8	38.0	37.3	46.6
1873	40.1	35.5	40.2	45.6	47.8	56.9	60.2	57.2	51.8	44.7	41.8	41.8	30.0	37.3	46.6
1874	41.0	38.1	44.2	47.8	47.4	55.6	61.2	57.2	54.0	47.5	40.1	40.1	30.0	37.7	46.2
1875	39.0	36.2	40.2	47.0	53.1	55.5	58.2	59.2	55.6	47.6	39.4	39.4	38.0	37.7	46.2
1876	37.8	37.6	38.4	44.4	49.6	55.7	60.4	59.0	52.5	49.8	39.6	39.6	39.4	38.2	45.4
1877	37.8	40.4	38.6	42.3	45.8	58.4	57.2	55.6	50.4	46.6	42.7	38.8	38.8	38.2	45.4
1878	37.6	41.4	41.3	45.4	51.0	55.1	59.4	58.5	54.8	48.7	38.0	28.7	28.7	38.2	46.6
1879	29.4	34.0	38.4	41.4	47.4	53.3	55.2	56.4	51.8	45.8	39.8	31.5	31.5	37.2	46.7
1880	35.4	41.8	41.0	45.8	49.3	54.9	56.6	59.0	56.2	43.4	38.4	37.2	37.2	38.1	44.7
1881	24.9	34.7	37.9	42.5	50.6	53.6	57.8	54.6	52.0	44.2	45.0	38.1	38.1	38.1	44.7
1882	41.1	42.2	43.8	48.8	50.4	54.2	58.1	58.4	52.6	48.4	39.0	33.1	33.1	33.1	47.1
1883	38.0	41.6	36.2	45.9	49.1	55.8	57.2	58.1	52.8	47.0	41.0	39.4	39.4	39.4	46.9
1884	41.2	39.6	41.8	43.3	50.2	55.0	58.5	59.6	54.8	47.0	39.9	37.2	37.2	37.2	47.3
1885	35.6	38.5	38.7	44.6	46.8	54.4	58.0	53.0	51.0	43.0	40.1	36.4	36.4	36.4	45.0
1886	33.3	33.8	37.2	43.6	47.0	53.9	57.8	57.0	53.0	49.8	41.8	32.3	32.3	32.3	45.0
1887	35.4	38.6	38.6	41.9	47.7	56.9	60.0	56.5	50.7	43.7	38.9	36.2	36.2	36.2	45.4
Means	36.6	38.5	40.1	44.9	49.6	55.6	58.3	57.6	53.6	47.0	40.0	37.3	37.3	37.3	46.6
Means of Scot- land generally —1867-1887, ¹	37.8	38.3	39.5	44.1	48.8	54.7	57.4	56.7	52.8	46.6	40.4	37.7	37.7	37.7	46.2
Means of N.E. of Scotland for 129 years, ²	36.6	37.9	39.9	44.6	49.8	55.1	57.9	57.2	53.1	46.9	40.9	38.0	38.0	38.0	46.5

¹ Taken from the *Journals* of the Scottish Meteorological Society, 1857-87.

² See *Journal of the Scottish Meteorological Society*, vol. ix. pp. 228, 229.

APPENDIX.

THE HAWFINCH.

GEOSBEAK, CHERRY FINCH.

Coccothraustes vulgaris.

MISS GEORGINA MILNE-HOME, Milne Graden, has kindly informed me that a female Hawfinch was caught in a fruit net in the garden at Ladykirk on the 2nd of September 1892. It was kept in a cage for a few days, when it was identified by Mr. John Brotherston, gardener at Milne Graden, who had frequently seen this species in the south of England.

The Hawfinch has seldom been observed in Scotland. Mr. Eagle Clarke, F.L.S., records in the *Annals of Scottish Natural History*,¹ that on the 3rd of August 1894 a specimen of this bird in immature plumage was captured in a net placed over a strawberry bed in the garden of Mr. Dundas of Arniston, Mid-Lethian.

¹ *The Annals of Scottish Natural History*, 1894, pp. 195, 196.



THE GREAT SPOTTED WOODPECKER.

PIED WOODPECKER, WITWALL, WOOD PIE, FRENCH PIE.

Dendrocopus major.

My friend Dr. Charles Stuart of Chirnside has been so good as to let me know that this species was found by Mr. John Ferguson, Duns, nesting in a hole in an ash tree in the woods of Duns Castle, in the summer of 1894.¹

Mr. William Smith, late gamekeeper at Duns Castle, has informed me that on the 12th of July 1887 he shot a young Great Spotted Woodpecker in Duns Castle woods, which, by its appearance, had only recently left the nest; and that a few days afterwards he noticed three others sitting on the top of a tall larch tree in the same plantations near St. Mary's Cottage.

¹ Mr. William Evans, F.R.S.E., records that he found the Great Spotted Woodpecker rearing its young in the same tree in Duns Castle Woods on the 29th of May 1896.—*Annals of Scottish Natural History*, July 1896.



I.—INDEX TO NAMES OF BIRDS IN VOL. II.

LATIN NAMES.

	PAGE		PAGE
<i>Accipiter</i> ,	1	<i>Dendrocopus major</i> , . . .	352
<i>Ardeida</i> ,	39	<i>Ectopistes migratorius</i> , . .	153
<i>Ardea cinerea</i> ,	39	<i>Falconida</i> ,	1
<i>Anseres</i> ,	66	<i>Falco peregrinus</i> ,	1
<i>Anatida</i> ,	66	<i>Falco subbuteo</i> ,	20
<i>Anser segetum</i> ,	66	„ <i>azalon</i> ,	21
„ <i>brachyrhynchus</i> ,	66	„ <i>tinunculus</i> ,	25
„ <i>albifrons</i> ,	90	<i>Fuligula ferina</i> ,	115
<i>Anas boschas</i> ,	101	„ <i>cristata</i> ,	118
<i>Alectorides</i> ,	207	„ <i>marila</i> ,	119
<i>Agialitis hiaticula</i> ,	224	„ <i>clangula</i> ,	120
<i>Alcida</i> ,	295	<i>Fulicaria</i> ,	194
<i>Alca torda</i> ,	295	<i>Fulica atra</i> ,	204
<i>Botaurus stellaris</i> ,	53	<i>Fratercula arctica</i> ,	307
<i>Bernicla brenta</i> ,	91	<i>Gallina</i> ,	158
„ <i>leucopsis</i> ,	93	<i>Gallinula chloropus</i> ,	202
„ <i>canadensis</i> ,	95	<i>Gallinago major</i> ,	240
<i>Ciconiida</i> ,	64	„ <i>celestis</i> ,	241
<i>Ciconia alba</i> ,	64	„ <i>gallinula</i> ,	244
<i>Cygnus musicus</i> ,	96	<i>Gavia</i> ,	264
„ <i>Bewicki</i> ,	99	<i>Herodiones</i> ,	39
<i>Columba</i> ,	131	<i>Harelda glacialis</i> ,	122
<i>Columbida</i> ,	131	<i>Hæmatopus ostralegus</i> , . . .	231
<i>Columba palumbus</i> ,	131	<i>Hydrochelidon nigra</i> ,	264
„ <i>œnas</i> ,	141	<i>Lagopus scoticus</i> ,	162
„ <i>livia</i> ,	145	<i>Limicola</i> ,	210
<i>Coturnix communis</i> ,	190	<i>Limosa ægocephala</i> ,	257
<i>Orex pratensis</i> ,	194	<i>Larida</i> ,	264
<i>Charadriida</i> ,	210	<i>Larus minutus</i> ,	266
<i>Charadrius morinellus</i> ,	210	„ <i>ridibundus</i> ,	268
„ <i>pluvialis</i> ,	221	„ <i>canus</i> ,	275
<i>Colymbida</i> ,	309	„ <i>argentatus</i> ,	279
<i>Colymbus glacialis</i> ,	309	„ <i>fuscus</i> ,	285
„ <i>septentrionalis</i> ,	311	„ <i>marinus</i> ,	286
<i>Coccothraustes vulgaris</i> , . . .	351	„ <i>glaucus</i> ,	287
<i>Dafila acuta</i> ,	109		

INDEX TO NAMES OF BIRDS.

361

	PAGE		PAGE
<i>Mareca penelope</i> , . . .	118	<i>Querquedula crecca</i> , . . .	110
<i>Mergus merganser</i> , . . .	128	„ <i>circia</i> , . . .	112
„ <i>albellus</i> , . . .	130	<i>Rallida</i> , . . .	194
<i>Machetes pugnax</i> , . . .	248	<i>Rallus aquaticus</i> , . . .	200
<i>Mergulus alle</i> , . . .	205	<i>Rissa tridactyla</i> , . . .	288
<i>Nycticorax griseus</i> , . . .	52	<i>Steganopodes</i> , . . .	30
<i>Numenius arquata</i> , . . .	258	<i>Sula bassana</i> , . . .	35
„ <i>phaeopus</i> , . . .	263	<i>Spatula clypeata</i> , . . .	107
<i>Oedemia nigra</i> , . . .	126	<i>Somateria mollissima</i> , . . .	123
„ <i>fusca</i> , . . .	127	<i>Syrhaptes paradoxus</i> , . . .	155
<i>Otididae</i> , . . .	207	<i>Scolopacidae</i> , . . .	232
<i>Otis tarda</i> , . . .	207	<i>Scolopax rusticula</i> , . . .	233
<i>Pandion haliaetus</i> , . . .	27	<i>Sterna fluviatilis</i> , . . .	265
<i>Pelecanidae</i> , . . .	30	<i>Stercorarius pomatorhinus</i> , . . .	292
<i>Phalacrocorax carbo</i> , . . .	30	„ <i>crepidatus</i> , . . .	293
„ <i>graculus</i> , . . .	33	„ <i>parasiticus</i> , . . .	294
<i>Pterocletes</i> , . . .	155	<i>Tadorna cornuta</i> , . . .	100
<i>Pteroclide</i> , . . .	155	<i>Turtur communis</i> , . . .	151
<i>Phasianidae</i> , . . .	170	<i>Tetraonidae</i> , . . .	158
<i>Phasianus colchicus</i> , . . .	170	<i>Tetrao tetrax</i> , . . .	158
<i>Perdix cinerea</i> , . . .	178	<i>Tringa alpina</i> , . . .	246
<i>Porzana maruella</i> , . . .	198	„ <i>striata</i> , . . .	247
<i>Phalaropus fulicarius</i> , . . .	232	<i>Totanus hypoleucus</i> , . . .	250
<i>Pygopodes</i> , . . .	295	„ <i>ochropus</i> , . . .	252
<i>Podicipedidae</i> , . . .	313	„ <i>calidris</i> , . . .	254
<i>Podiceps cristatus</i> , . . .	313	„ <i>canescens</i> , . . .	256
„ <i>griseigena</i> , . . .	315	<i>Tubinares</i> , . . .	321
„ <i>nigricollis</i> , . . .	317	<i>Uria troile</i> , . . .	297
„ <i>fluviatilis</i> , . . .	318	„ <i>grylle</i> , . . .	303
<i>Procellariidae</i> , . . .	321	<i>Vanellus vulgaris</i> , . . .	225
<i>Procellaria pelagica</i> , . . .	321		

ENGLISH NAMES.

Arctic, or Richardson's Skua, . . .	293	Black-backed Gull, Lesser, . . .	285
Auk, Little, . . .	305	„ „ „ Great, . . .	286
Bittern, Common, . . .	53	Buffon's Skua, . . .	294
Bean Goose, . . .	66	Black Guillemot, . . .	303
Brent Goose, . . .	91	Common Cormorant, . . .	30
Bernacle Goose, . . .	93	Cormorant, Common, . . .	30
Bewick's Swan, . . .	99	„ Green, . . .	33
Black Grouse, . . .	158	Common Heron, . . .	39
Bastard, Great, . . .	207	„ Bittern, . . .	53
Black-tailed Godwit, . . .	257	Canada Geese, . . .	95
Black Tern, . . .	264	Common Shield-Duck, . . .	100
Black-headed Gull, . . .	268	„ Sooter, . . .	126

	PAGE		PAGE
Common Partridge, . . .	178	Grouse, Pallas's Sand, . . .	155
„ Quail, . . .	190	„ Black, . . .	158
Crake, Spotted, . . .	198	„ Red, . . .	162
Common Coot, . . .	204	Great Bustard, . . .	207
Coot, Common, . . .	204	Golden Plover, . . .	221
Catcher, Oyster, . . .	231	Grey Phalarope, . . .	232
Common Snipe, . . .	241	Great Snipe, . . .	240
„ Sandpiper, . . .	250	Green Sandpiper, . . .	252
„ Redshank, . . .	254	Greenshank, . . .	256
Common Curlew, . . .	258	Godwit, Black-tailed, . . .	257
Curlew, Common, . . .	258	Gull, Little, . . .	266
Common Tern, . . .	265	„ Black-headed, . . .	268
„ Gull, . . .	275	„ Common, . . .	275
„ Guillemot, . . .	297	„ Herring, . . .	279
Crested Grebe, Great, . . .	313	„ Lesser Black-backed, . . .	285
		„ Great Black-backed, . . .	286
Duck, Wild, . . .	101	Great Black-backed Gull, . . .	286
„ Pintail, . . .	109	Glaucous Gull, . . .	287
„ Tufted, . . .	118	Gull, Glaucous, . . .	287
„ Scaup, . . .	119	„ Kittiwake, . . .	288
„ Long-tailed, . . .	122	Guillemot, Common, . . .	297
„ Eider, . . .	123	„ Black, . . .	303
Dove, Ring, . . .	131	Great Northern Diver, . . .	309
„ Stock, . . .	141	„ Crested Grebe, . . .	313
„ Rook, . . .	145	Grebe, Great Crested, . . .	313
„ Turtle, . . .	151	„ Red-necked, . . .	315
Dotteral, . . .	210	„ Eared, . . .	317
Dunlin, . . .	246	„ Little, . . .	318
Diver, Great Northern, . . .	309	Great Spotted Woodpecker, . . .	352
„ Red-throated, . . .	311		
Dabchick, . . .	318	Hobby, . . .	20
		Heron, Common, . . .	39
Eider Duck, . . .	123	„ Night, . . .	52
Eared Grebe, . . .	317	Herring Gull, . . .	279
		Hawfinch, . . .	351
Falcon, Peregrine, . . .	1		
		Jacksnipe, . . .	244
Green Cormorant, . . .	33		
Gannet, . . .	35	Kestrel, . . .	25
Goose, Solan, . . .	35	Kittiwake Gull, . . .	288
„ Bean, . . .	66		
„ Pink-footed, . . .	66	Long-tailed Duck, . . .	122
„ White-fronted, . . .	90	Landrail, . . .	194
„ Brent, . . .	91	Lapwing, . . .	226
„ Bernacle, . . .	93	Little Gull, . . .	266
„ Canada, . . .	95	Lesser Black-backed Gull, . . .	285
Garganey, . . .	112	Long-tailed Skua, . . .	294
Golden-Eye, . . .	120	Little Auk, . . .	305
Goosander, . . .	128	„ Grebe, . . .	318

INDEX TO NAMES OF BIRDS.

363

	PAGE		PAGE
Merlin,	21	Shag,	33
Mallard,	101	Solan Goose,	35
Moor Hen,	202	Stork, White,	64
		Swan, Bewick's,	99
Night Heron,	52	Sheld-Duck, Common,	100
Northern Diver, Great,	309	Shoveller,	107
		Scaup Duck,	119
Osprey,	27	Scooter, Common,	128
Oyster Catcher,	231	„ Velvet,	127
		Smew,	130
Peregrine Falcon,	1	Stock Dove,	141
Pink-footed Goose,	66	Sand Grouse, Pallas's,	155
Pintail Duck,	109	Spotted Crake,	198
Pochard,	115	Snipe, Great,	240
Passenger Pigeon,	153	„ Common,	241
Pigeon, Passenger,	153	Sandpiper, Purple,	247
Pallas's Sand Grouse,	155	„ Common,	250
Pheasant,	170	„ Green,	252
Partridge, Common,	178	Skua, Pomatorhine,	292
Plover, Golden,	231	„ Richardson's or Arctic,	293
„ Ringed,	224	„ Buffon's or Long-tailed,	294
Phalarope, Grey,	232	Storm Petrel,	321
Purple Sandpiper,	247		
Pomatorhine Skua,	292	Teal,	110
Puffin,	307	Tufted Duck,	118
Petrel, Storm,	321	Turtle Dove,	151
		Tern, Black,	264
Quail, Common,	190	„ Common,	265
Ring Dove,	131	Velvet Scoter,	127
Rock Dove,	145		
Red Grouse,	162	White Stork,	64
Rail, Water,	200	White-fronted Goose,	90
Ringed Plover,	224	Whooper,	96
Ruff,	248	Wild Duck,	101
Redshank, Common,	254	Wigeon,	113
Richardson's Skua,	293	Water Rail,	200
Razor-Bill,	295	Woodcock,	233
Red-throated Diver,	311	Whimbrel,	263
Red-necked Grebe,	315	Woodpecker, Great Spotted,	352

BERWICKSHIRE NAMES.

Blue Hawk,	1	Cormorant, Black,	30
Black Cormorant,	30	„ Watch,	30
Bull o' the Bog,	53	„ Stair,	30
Black-Cock,	158	Coal-and-Candle-Licht Duck,	122
Bell-poot,	204	Cud-Doo,	123
Blutter, Heather,	241	Culbert,	123

	PAGE		PAGE
Cushie,	131	Mire Snipe,	241
Cushie Doo,	131	Maw, Gull,	275, 279, 285, 286
Corn Crake,	194	Marrot,	297
Crake, Corn,	194	Mother of Carey Chicken,	321
Common Gull,	279		
Coulter Neb,	295	Neb, Coulter,	295
Chicken, Mother of Carey,	221	Norie, Tammie,	307
Drum, Mire,	53	Paitrick,	178
Duck, Wild,	101	Pliver,	221
Duik, Tael,	110	Pluver,	221
Duck, Sea,	120	Peeseweep,	235
„ Coal-and-Candle-Licht,	122	Piet, Sea,	231
Dunter,	123	Pickie,	266
Doo, Cushie,	131	Pickiemaw,	268
Doo,	145	Pictarnie,	268
Dove, Turtle,	303	Peg-birnet,	268
Dipper,	318	Petrel, Stormy,	321
Faisan,	170	Stair Cormorant,	30
		Scart,	30, 33
Goshawk,	1	Solan Guise,	35
Guise, Solan,	35	Swan, Wild,	96, 99
Goose, Wild,	66, 90, 91, 93	Shieldrake,	100
Grey Hen,	158	Sea Duck,	120
Gull Maw,	275, 279, 285, 286	Sea Piet,	231
„ Common,	279	Snipe, Mire,	241
		Sandy Laverock,	250
Hawk, Blue,	1	Sea Snipe,	254
„ Hunting,	1	Snipe, Sea,	254
Hunting Hawk,	1	Sea Swallow,	265
Hawk, Keelie,	25	Swallow, Sea,	265
Hurant,	39	Scoot,	297
Huron,	39	Stormy Petrel,	321
Heronshengh,	39		
Hen, Grey,	158	Tael Duik,	110
„ Water,	202	Teuchit,	225
Heather Blutter,	241	Tirrle,	268
		Turtle Dove,	303
Keelie,	25	Tammie Norie,	307
Keelie Hawk,	25		
Kaitiewake,	288		
		Watch Cormorant,	30
Laverock, Sandy,	250	Wild Goose,	66, 90, 91, 93
		Wild Swan,	96, 99
Mire Drum,	53	Wild Duck,	101
Muir-fowl,	162	Wigeon,	120
Muir-cock,	162	Water Hen,	202
Muir-hen,	162	Whaap,	258

II.—INDEX TO PROVERBS IN VOL. II.

POPULAR RHYMES, SAYINGS, AND WEATHER LORE ABOUT BIRDS.

- | | |
|--|--|
| <p>BERNACLE GOOSE: belief in olden times about origin, 94.</p> <p>COMMON BITTERN: "Bogle of Billie Myre," 53.</p> <p>COMMON CORMORANT: weather prognostic, 31.</p> <p>COMMON CURLEW: name associated with goblins, &c., 260.</p> <p>COMMON GULL: weather prognostic, 275; rhyme, 275; superstition, 276.</p> <p>COMMON HERON: saying of Archibald, seventh Earl of Angus, at Ancrum Moor, 40; weather prognostic, 42.</p> <p>COMMON PARTRIDGE: French proverb, 186; rhyme, 189.</p> <p>GANNET: saying of salmon fishers, 36.</p> <p>GOLDEN PLOVER: weather prognostic, 222, 223.</p> <p>HERRING GULL: weather prognostic, 284.</p> | <p>LANDRAIL: rhyme, 196.</p> <p>LAPWING: weather lore, 226; regarded as a bird of ill-omen, 228, 229; weather prognostic, 229; rhymes and sayings, 229.</p> <p>LESSER BLACK-BACKED GULL: proverb, 285.</p> <p>MALLARD: saying, 106.</p> <p>RED GROUSE: weather prognostic, 169.</p> <p>RED-THOATED DIVER: weather prognostic, 311.</p> <p>ROCK DOVE: superstition, 149; sayings, 149, 150.</p> <p>STORM PETREL: origin of name, 321; weather prognostic, 322.</p> <p>WILD GOOSE: arrival, sign of seasons, 67; belief amongst boys, 88; rhymes, 87, 88; saying about geese, 106.</p> <p>WHOOPER: vows to the Swan, 97.</p> <p>WOODCOCK: popular saying, 239.</p> <p>WOOD PIGEON: sayings, 140.</p> |
|--|--|

III.—TOPOGRAPHICAL INDEX TO VOL. II.

- | | |
|---|---|
| <p><i>Abbey St. Bathans</i>, Parish Wild Geese Report, 72; Golden-Eye on Whitadder, 120; Pallas's Sand Grouse, 156; Black Grouse, 160; Red Grouse, 164; bags got, 162; numbers in end of last century, 163; contents of crop, 168; Partridge shooting, 181; Common Quail, 191; Dotterel, high grounds visited by great numbers in former times, 211, 214; on heights in recent years, 212, 214, 216, 218; Black-headed Gull, 274; Little Auk found dead, 306.</p> <p><i>Abbey Farm, North Berwick</i>, 64.</p> <p><i>Aikenga</i>, Lapwing, 229.</p> | <p><i>Albentum Auvium</i>, 166.</p> <p><i>Alyth, Forfarshire</i>, voracity of Wood Pigeon, 137.</p> <p><i>Ancrum Moor</i>, Common Heron, 40.</p> <p><i>Ancrum Woodhead</i>, 236.</p> <p><i>Angelcrou</i>, Wild Geese, 80.</p> <p><i>Arniston</i>, Hawfinch, 351.</p> <p><i>Auchencrow Mains</i>, 54; drainage of Billie Mire, 58; Wild Geese, 76.</p> <p><i>Auchencrow</i>, notes on Billie Mire by Mr. Thomas Hewit, 61.</p> <p><i>Avenue Bridge at Paxton</i>, 142.</p> <p><i>Ayton</i>, Hawks kept by Mr. Belany, 3; Billie Mire, 54, 57; Parish Wild Geese Report, 72; Pallas's Sand Grouse got at Whitfield,</p> |
|---|---|

- 156; Water Rail, 201; high grounds visited by Dotterel in former times, 211; Woodcock in lambing shed, 234; tame Herring Gull, 284.
- Ayton Castle*, Osprey found, 28; Pheasant shooting, 173; Partridge shooting, 182.
- Backlea Woods*, Black Grouse, 161.
- Bamborough*, 100.
- Bankend*, 156.
- Barnside*, Wild Geese, 72; Black Grouse, 158; Red Grouse shooting in 1813, 164.
- Bass*, Gannet, 35, 36, 37; seen from East Castle, 281; Kittiwake Gull, 290; Razor-bill, 295; Puffin, 306.
- Bastenrig*, Dotterel, 210.
- Bathgate Bog*, James IV. hawking the Common Bittern, 62.
- Bedshiel*, Wild Geese, 80; Black Grouse, 158, 160; Red Grouse shooting in 1812-14, 164.
- Belhaven*, 317.
- Belvidere*, Common Heron, 45.
- Bemersyde*, 62; Little Grebe, 319.
- Bemersyde Loch*, a haunt of the Mallard, 102; a nesting station of Black-headed Gull, 268; Mr. John Thomson's account of loch, 269, 270, 271.
- Berrington*, rhyme about Wild Geese, 87.
- Berrybank*, 54; Partridge shooting, 183.
- Berrywell*, Water Rail, 201.
- Berwick*, Grace Griffith's execution and White Pigeon, 149; popular saying regarding pigeons associating with Rooks, 150; Dr. Colville Brown's account of moulting of Black-headed Gull, 271.
- Berwick Bounds*, Common Quail, 191.
- Berwick Bridge*, 313.
- Berwick-on-Tweed*, Falcons at Highland and Agricultural Society's Show in 1841, 3; Wild Swans, 97; Eared Grebe, 317.
- Berwickshire*, heather burning, 169; migration, 327, 328; Ornithological observations, 329.
- Big Blake Law*, Dotterel, 216.
- Big Byrrips*, nest of Herring Gull, 281.
- Big Wood, Salton*, Cuckats, 134.
- Billie*, Partridge shooting, 182, 183.
- Billie Burn*, drainage of Billie Mire, 57, 59; Water Rail, 201.
- Billie Castle*, ruins of, 55.
- Billie Mains*, 54, 55; Brent Goose shot, 91; Shoveller killed, 107; 273.
- Billie Mill*, 56.
- Billie Mire*, formerly a haunt of the Common Bittern, 53; meeting place of English and Scottish Commissioners, 54; Fosterland Burn, 55; Auchencrow Burn, 55; Billie Mire Burn, 55; Draeden Burn, 55; MS. notes on the plants formerly found here by the late Dr. Henderson, Chirnside, 57; birds, 58; state in end of last century, 58; plan in 1759, 58; Mr. John Blackadder's notes about drainage of the Mire, 59; proposed canal between Duns and Eyemouth, 59; Mire bridge, 59; notes by Mr. William White, Lennel Hill, 60; last Bittern shot, 60; bog oak and hazel nuts discovered, 60; old people in Chirnside having heard the Bull o' the Bog, 61; Wild Duck, 101; Flapper shooting, 104; Spotted Crane, 199; a breeding station of Black-headed Gull in former times, 273.
- Billie Mire Burn*, 55, 56.
- Birch Hill, Norham*, 310.
- Birgham*, Pochard on the Tweed, 116; Black-headed Gull, 271.
- Blackadder*, Kestrel, 26; Common Heron, 45; frequented by the Mallard, 103; Moor Hen, 202; Common Sandpiper, 250.
- Blackadder Estate*, Pistol Plantation, favourite roosting place of Wood Pigeons, 136.
- Blackadder House*, Stock Dove's nest, 143.
- Blackburn*, 54; "Mire Drum" shot, 60; 95; Dotterel, 217.
- Blackburn Mill*, Dotterel, 216.
- Blackburn Riggs Peat Moss*, Land-rail in winter, 196.
- Blackcastle Rings*, Kestrel, 26.
- Blackerton*, Dotterel, 213, 214, 215, 220.
- Black Hill*, Dotterel, 215.
- Black Hill, Longformacus*, 106.
- Black Mask Rock, near Fast Castle*, nests of Herring Gull, 281.
- Black's Mill Burn*, shooting Wild Ducks in 1812-14, 104.
- Blackpotts, Coldingham*, White Stork, 64.

- Blakey*, Peregrine Falcon's nest, 4, 5; Kestrel, 26.
- Blanerne*, Merlin, 21; Billie Mire, 58, 59; Teal on Whitadder, 111; Partridge shooting, 184; 273; Little Grebe found on Whitadder, 319.
- Blanerne, East*, Wild Geese, 72.
- Bleak Heugh, near Burnmouth*, 280.
- Blue Braes*, Peregrine Falcon's nest, 5, 6.
- Blythe*, Wild Geese, 82.
- Blythe Edge*, Dotterel, 219.
- Blythe Moor*, Common Heron, 47.
- Blythe Water*, Dotterel, 219.
- Boiling Park*, Common Heron, 43.
- Bonkyl*, Partridge shooting, 182.
- Bonkyl Lodge*, 56.
- Boon*, Wild Geese, 82; White Partridge, 189; Dotterel, 219.
- Borthuik*, 134.
- Boundreigh Water*, Dotterel, 219.
- Bowerhouse*, Wild Geese, 73; Common Quail, 190.
- Bowshiel*, Wild Geese shot, 71; Wild Geese, 74; Dotterel, 217.
- Braid Bog*, Penmanshiel, Wild Geese, 71.
- Brander Cliffs*, nests of Herring Gulls, 280.
- Brander Cove*, Green Cormorant nesting, 33, 34.
- Brighton Aquarium*, Guillemot, 201.
- Broad Bog*, Dotterel, 215.
- Broad Bog*, Penmanshiel, Wild Geese, 67.
- Broadhaugh*, effects of severe weather on Moor Hen, 203.
- Broadhaven Bay*, 280; small colony of Common Guillemots, 299.
- Broadmeadows*, Wild Geese, 80.
- Broadshawrig*, Merlin nesting, 24.
- Brokholes*, Dotterel, 213, 218.
- Broomhouse*, Pheasant shooting, 174; Partridge shooting, 184.
- Brotherstone Tower*, 270.
- Bruntaburn*, Common Heron, 44.
- Bruntaburn*, Peregrine Falcon's nest, 6.
- Buncle*, 54.
- Buncle Church*, 56.
- Buncle Parish*, report on Wild Geese, 72; Mallard, 106; Black Grouse, 160; Dotterel in former times, 211, 215; Woodcock, 234.
- Bunle Wood*, Common Heron, 43, 56; a favourite haunt of Woodcock, 234.
- Burnmouth*, Peregrine Falcon's nest, 2, 4; Osprey, 29; Rock Dove, 145; Coot, 204; female Ruff shot, 248; Herring Gull, 280; fishermen collecting eggs of Gulls for sale, 282; Captain Norman's account of Herring Gull feeding on shoal of herrings, 283.
- Butterdean*, Wild Geese, 84; Common Quail, 190.
- Byreclough*, Merlin, 24; Common Heron, 47; bags of game got by the Duke of Roxburghe in 1886 and 1872, 164, 165; White Grouse shot, 168; Partridge, 179.
- Byrke Houses*, 141.
- Byreloch Heugh*, Green Cormorant, 33.
- Cairncross*, Wild Geese, 76.
- Cairnsmill*, Wild Geese, 77.
- Caldra*, Partridge shooting, 184.
- Caldron Cove*, Green Cormorant, 33.
- Cammer Laws*, Wild Geese, 85.
- Cardross*, falconry, King Robert the Bruce's Hawk-house, 13.
- Carfrae Mill*, large bags of Red Grouse got in 1886, 165.
- Castleholes Heugh*, Peregrine Falcon, 9.
- Cattleshiel*, Black Grouse, 160, 161; George Home of Kimmerghame hawking Grouse, 163; Red Grouse shooting, 166.
- Caulderon Cove*, Rock Dove, 145.
- Causewaybank*, 54, 56; plan of Billie Mire, 59, 60; bog oak and hazel nuts found in Billie Mire, 60.
- Cavers*, 154.
- Channelkirk*, Dotterel, 218.
- Channelkirk Parish*, report on Wild Geese, 73; Black Grouse, 160; Red Grouse, 164.
- Chapel*, Woodcock shooting, 236.
- Chapel, near Duns*, Gannet, 35.
- Chapelhill*, flock of Bernacle Geese, 93.
- Charterhall*, Pheasant shooting, 174; Partridge shooting, 184.
- Cherrytrees*, 212.
- Chesterbank*, Dotterel, 210, 215; Mr. John Renton's account of the Sea-fowl at St. Abb's Head, 288.
- Chirnside*, 54; Dr. Henderson, 55; Billie Mire drainage, 59; Shelduck shot, 100; Dr. Henderson's lamentations about change on the face of Nature, 102; Wood Pigeons eating vegetables in gardens, 138; Pallas's Sand Grouse, 156; Com-

- mon Quail, 191; Lapwing, 225; 248; Green Sandpiper shot, 252; 273; 352.
- Chirnside Mill*, 57.
- Chirnside Parish*, report on Wild Geese, 73; Pallas's Sand Grouse, 156; Water Rail, 201; Woodcock, 235.
- Choicelee*, Wild Geese, 81.
- Circle Plantation*, Common Heron, 44.
- Cleaver Rock, St. Abb's Head*, 146; nest of Herring Gull, 280; Lesser Black-backed Gull breeding, 285; nesting of Kittiwake Gull in former times, 290; colonies of Common Guillemots, 298.
- Clairvale Wood*, Greenshank, 256.
- Clarabad*, Common Heron, 45; Wild Geese, 81; Coot, 204.
- Clarabad Mill*, Green Sandpiper seen, 253.
- Clarabad Mill Cauld*, Red-necked Grebe shot, 315.
- Coal Point, Lamberton*, Kestrel, 26.
- Cockburn*, Pochard shot on Whitadder, 116; Partridge, 178; 213.
- Cockburn Braes*, Osprey, 28.
- Cockburn Law*, popular rhyme about the weather, 87.
- Cockburn Mill*, Osprey, 273.
- Cockburnspath*, Peregrine Falcon, 2; flock of Bernacle Geese at Chapel-hill, 93; 115; Albino Black-headed Gull shot, 273; migration, 328.
- Cockburnspath Parish*, Common Heron, 45; Common Bittern, 61; report on Wild Geese, 73; Pallas's Sand Grouse, 156; Black Game, 160; Red Grouse in 1835, 164; Common Quail, 190; Dotterel, 210; Dotterel in former times, 211; Dotterel in recent years, 212.
- Cocklaw, Ayton*, Wild Geese, 72.
- Coldingham*, Peregrine Falcon, entry of two series of Falcons in ancient rental, 1; falconry, 13; priory falconry, 13, 54; immigration of Ring Dove, 133; Rock Dove, 149; shrine of St. Ebba and White Pigeon, 149; 286; Kittiwake Gull, 289; occurrence of Arctic or Richardson's Skua in unusual numbers, 293; Mr. Andrew Wilson's list of birds which frequent St. Abb's Head, 296, 297; Black Guillemot, 303; incident in great storm of 14th October 1881, 322.
- Coldingham Lock*, Pochard shot, 115; Coot, 204; occurrence of Little Gull, 266.
- Coldingham Moor*, Curlew plentiful, 258.
- Coldingham Parish*, report on Wild Geese, 75; Velvet Scoter, 127; Pallas's Sand Grouse, 156; Black Grouse, 160; Red Grouse, 164; Dotterel, 210; Dotterel in former times, 211; Dotterel in recent years, 212; Woodcock, 234; Little Gull, 266, 267.
- Coldingham Priory, Fosterland Burn*, 55, 56; 208.
- Coldinghamshire*, "*Crachochtre*," 56.
- Coldinghamshire*, Peregrine Falcon, 2; Osprey, 29; Long-tailed Duck, 122; 145; Common Redshank, 255; visit of Mr. Archibald Hepburn in 1850, 277; 281; 290; Arctic or Richardson's Skua shot, 293; Common Guillemot, 298; notes about Guillemots' eggs, 300; Red-necked Grebe shot, 315; Storm Petrel, 321, 322.
- Coldlands*, 55.
- Coldstream*, Cistercian Abbey of, falconry, 15; Wild Swans shot, 96; 146; priory "*columbia*" and "*columbarijs*," 148; Ringed Plover, 224; 299; Great Northern Diver killed, 310.
- Coldstream Bridge*, Black-headed Gull haunting Tweed there, 272.
- Coldstream Parish*, Common Heron, 43; report on Wild Geese, 76; Black Tern, 264; Eared Grebe, 317.
- Corbie's Heugh*, Peregrine Falcon's nest, 6.
- Corbie*, Wild Geese, 82.
- Corbie Bog*, a breeding quarter of the Black-headed Gull in former times, 274.
- Corbie Tower*, 268.
- Cove Harbour*, Eider Duck, 123.
- Cove, near Cockburnspath*, 279; 297; Great Northern Diver found in nets, 309.
- Cove Shore*, Wigeon, 113.
- Coveyheugh House*, 315.
- Cowdenknowes*, 54; Stock Dove, 143; 199; 293.
- Craig Taw*, Common Cormorant, 31.
- Cramond*, 293.
- Cranshaw*, Wild Geese, 77; Land-rail in October, 196; 209; Storm Petrel got, 321.

- Cranshaw Hill*, autumnal flights of Woodcock, 233.
Cranshaw Parish, report on Wild Geese, 77; Black Grouse, 160; Red Grouse 164; Dotterel in former times, 211; Dotterel in recent years, 212.
Cribbs, Wild Geese, 82.
Crichness, 315.
Crosslaw, Wild Geese, 78.
Crow Dean Wood, *Paxton*, Woodcock, 235.
Crumles Bridge, Common Heron, 44.
Cumledge, Common Bittern shot, 61; Wild Swan killed, 97.

Dawnae, 217.
Dawikie, Common Heron, 40.
Daye, 166.
Derringtons, *Great and Little*, popular rhymes about the weather, 87.
Derrington Law, Wild Duck shooting, 104.
Dod Mill, Common Heron, 47; Bernacle Goose, 93.
Dogden Moss, 86; Water Rail, 201; a breeding station of the Black-headed Gull in former times, 274.
Dow Cave, 145.
Dowlaw, Peregrine Falcon's nest, 2; Merlin's nest, 24; Common Cormorant, 30; Canada Geese shot, 95; Velvet Scoter, 127; derivation of name, 149; Common Quail, 190; Coot, 204; a favourite haunt of Dotterel, 212, 216, 217, 218; Black-tailed Godwit shot, 257; 279.
Dowlaw Braes, arrival of Woodcock, 234.
Dowlaw Burn, Peregrine Falcon's nest, 5.
Dowlaw Burn Foot, nests of Herring Gulls, 281.
Dowlaw Dean, 217.
Dowlaw Mill Pond, 146; Common Snipe nesting, 243.
Draeden Burn, 55.
Draeden Field, *Heughhead*, Earl of Wemyss stalking Wild Geese, 69.
Drake Mire, derivation of name, 106.
Drakestruther, name derived from Wild Duck, 106.
Dronshiel, Dotterel, 219.
Dryburgh, Common Heron, 49; Stock Dove, 143; Oyster Catcher, 231.
Dryburgh Estate and Bemersyde Loch, 270.

Drygrange, Stock Dove, 143.
Dunbar, falconry, 11, 12; Pallas's Sand Grouse seen, 155; Black Tern, 264.
Dunglass, Wood Pigeon destroying broccoli, 138; Partridge shooting, 183; Dotterel, 217.
Dunglass Dean, Common Heron, 45.
Dunglass Woods, large bag of Woodcock, 237.
Dunkirk, 282.
Duns, Hobby, 20; 59; 219; 248; 273; Little Auk caught, 306; 321; 352.
Duns Castle, Common Heron, 47; Pintail Duck seen, 109; Stock Dove shot, 142; Stock Dove's nest, 143; Pheasant shooting, 173; Partridge shooting, 183; 219; 220; Black-headed Gull at Hen Poo in former times, 273.
Duns Castle Lake, a favourite retreat of Mallard, 102; Shovellers observed, 107; visited by Pochard, 116; Tufted Duck, 118; Golden-Eye, 120; Long-tailed Duck, 122; Eider Duck, 124; Velvet Scoter seen, 127; Water Rail shot, 201; Moor Hen, 202; Coot, 204, 205.
Duns Castle Woods, Common Heron, 43; young Woodcock found, 238; Woodcock's nest found, 238; Great Spotted Woodpecker, 352.
Duns Law, 141.
Duns Parish, report on Wild Geese, 78; Black Grouse, 160; Red Grouse, 164; introduction of Pheasant, 171.
Duns Railway Station, Spotted Crane found dead, 198.
Dye, Common Heron, 44, 45, 47; frequented by the Mallard, 108; Lesser Black-backed Gull, 285; Little Grebe shot, 319.
Dye Cottage, 106.
Dykegatehead, 223.

Earlston, Falconry, 11; Teal, 110; Black Grouse, 160; 200; Curlew on moors, 258.
Earlston Parish, Black Grouse, 160; Red Grouse, 164; Dotterel in former times, 211; Black-headed Gull, 274.
Earl's Tower at Earlston, Falconry, 11.
East Blarney, 56, 215, 218, 220.
East Linton, Woodcock in January 1881, 235.

- East Lothian*, rhyme about Wild Geese, 87; Shoveller breeding, 108; increase of Cushats about 1859-60, 134; Wood Pigeon nesting in hawthorn hedges, 139; heather burning, 169; popular name of Whimbrel, 263; Common Gull on shore, 277; migration, 327, 328.
- East Lothian Coast*, 281.
- East Mains, Lauder*, White Partridge, 189.
- East Reston*, 56.
- Ecclaw*, Wild Geese, 73.
- Ecclaw Hill*, Dotterel, 216.
- Ecclas Parish*, Common Heron, 43; report on Wild Geese, 77; Woodcock shooting, 237; Green Sandpiper shot, 253; Greenshank, 256; Eared Grebe, 317.
- Eden*, Common Heron, 45; frequented by the Mallard, 103, 105; Wigeon near Nenthorn, 113.
- Edington*, Peregrine Falcon captured, 7; Partridge shooting, 181, 182; cream coloured Partridge, 189.
- Edington Hill Wood*, a favourite haunt of Woodcock, 234; large bag of Woodcock, 234.
- Edington Mains*, Wild Geese, 73; Common Quail, 190; occurrence of Water Rail, 199; Mr. John Wilson's account of country in former times, 208; 213.
- Edington Mains Mill Pond*, Ruff shot, 248.
- Edington Mill Cauld*, Great Northern Diver shot, 309.
- Edmondsdean*, Wild Geese, 73; Dotterel, 217.
- Ednam*, 271.
- Edrington*, Turtle Dove shot, 151; introduction of Pheasants, 172.
- Edrom Mains*, Teal frequenting burn, 111.
- Edrom Parish*, Common Heron, 45; report on Wild Geese, 77; Golden Plover, 221.
- Eildons*, 88.
- Elfole*, 59.
- Ellemford*, Common Heron, 44; Wild Geese, 83; Teal on Whitadder, 110; Golden-Eye, 120; bags of Red Grouse got, 163, 166; Great Snipe seen, 240; Common Snipe, 241.
- English Lake District*, nesting of Dotterel, 210.
- Ernesheugh*, Peregrine Falcon's eyrie, 2, 5; colony of the Common Gull in 1850, 277, 278.
- Esbdale*, Falconry, 11.
- Everett Moss*, 199; or *Dowie Den Moss*, *Pickie Moss*, or *Legerwood Loch*, a nesting place of Black-headed Gull, 268, 269.
- Ewe*, Osprey, 28; Common Heron, 46; 54; 57; frequented by the Mallard, 103; Common Sandpiper, 250; tame Herring Gull, 284.
- Eyemouth*, 59; Wild Swans, 96; Smew shot, 130; 145; Lapwing, 229; 275; 283; young Glaucous Gull shot, 287; Long-tailed Buffon's Skua shot, 294; 297; Storm Petrel, 321.
- Eyemouth Parish*, Dotterel in former times, 211.
- Fairlaw*, 54, 55.
- Fairneyside*, Rock Dove, 145; Coot, 204; Woodcock in lambing shed, 234; Herring Gull, 282.
- Fairmeside*, Peregrine Falcon's nest, 2.
- Fala*, Dotterel, 218.
- Faldonside*, 218.
- Fallside*, Wild Geese, 79.
- Fangrist*, Kestrel, 26.
- Fannanside*, Wild Geese killed, 71; Pallas's Sand Grouse shot, 156.
- Farne Islands*, Common Cormorant nesting, 30; Eider Duck, 123; Common Snipe seen on migration, 242; Common Tern breeding, 265; Kittiwake Gull, 290; migration, 323.
- Fast Castle*, Peregrine Falcon's eyrie, 1, 2, 3, 5, 8; Kestrel, 26; Green Cormorant, 33; Eider Duck breeding, 123; nest with young found, 124; Rock Dove's resorts, 146; Rock Dove, 146; Woodcock's arrival in autumn, 234; Black-tailed Godwit, 257; 279; cry of Herring Gull, 279; Herring Gull, 281.
- Fellolough*, Common Heron, 44; Wild Geese, 83; Stock Dove, 143.
- Fenham Flats*, immense flocks of Brent Geese, 91.
- Fenham Slakes*, Wild Geese, 70.
- Fentonbarns*, near *Drem*, shooting Wild Geese, 69.
- Ferneycastle*, 54, 55.

- Ferneyrig Covers*, Woodcock shooting, 237.
Finchy, Long-tailed Duck on the Tweed, 122.
Firth of Forth, Common Cormorant, 30; Ruff, 249; Black Guillemot, 304; Storm Petrel, 322; migration, 327.
Flass, Black Grouse, 161.
Flass Moor, Red Grouse shooting, 166.
Fleura, Shoveller obtained, 107.
Flodden, 261.
Flood or Flot Carr, St. Abb's Head, Great Black-backed Gull breeding in 1851, 286.
Flot Carr, St. Abb's Head, Herring Gulls' nests, 280; colonies of Common Guillemots, 296.
Fogo Parish, report on Wild Geese, 78.
Fogorrig, Wild Geese, 78.
Ford, 303.
Forres, Falconry, 11.
Fosterland Burn, 54, 55.
Foulden, Common Quail, 191; Dotterel sent to London for Mr. Wilkie of Foulden, 213; 220.
Foulden Basile, voracity of Wood Pigeon, 137; Common Quail, 191; Little Auk shot, 305.
Foulden Estate, Little Auk, 305.
Foulden New Mains, Wild Geese, 79; flock of Canada Geese, 95; visit of Wild Swans, 97; Wigeon on Mill Pond, 113; Little Grebe, 319.
Foulden West Mains, Wild Geese, 79; Garganey shot, 112; Pochard shot on mill pond, 116; Pallas's Sand Grouse caught, 155; Partridge shooting, 181; Coot, 204; Dotterel, 219.
Foulden Parish, Common Heron, 44; report on Wild Geese, 79; Pallas's Sand Grouse, 156; Dotterel in former times, 211; in recent years, 212.
Foul Carr, St. Abb's Head, principal breeding quarters of the Herring Gull, 280; Lesser Black-backed Gull breeding, 285; colony of Common Guillemots, 298; taking of Guillemots' eggs, 300; Puffin nesting in 1851, 308.
Foul Carr Cove, Razor Bill nesting in 1855, 296.
Foul Carr Rd., nesting of Kittiwake Gull in former times, 289, 290.
Foulshotlaw Wood, Black Grouse, 161.
Gateside School, Common Heron, 44.
Geddes' Haven, 281.
Gibbs' Cross, Wedderlie, Wild Geese, 70.
Girrick, Parish of Nenthorn, Kestrel, 26; Mallard feeding on "laid" barley, 103; shooting Wild Duck on the Eden, 105; Wigeon, 114; Grey Phalarope, 232; 241.
Glengelt, Wild Geese, 73.
Glen Urquhart, Inverness-shire, Merlin, 23.
Godscroft, Wild Geese, 72; Pallas's Sand Grouse, 156; Black Grouse, 158; Red Grouse shooting in 1813, 164; bag of Red Grouse got in 1878, 166; Common Quail, 191; number of Dotterel shot, 213, 214.
Godscroft Woodheads, Wild Geese trapped, 71.
Gordon, Dotterel, 219.
Gordon Bog, Wigeon killed, 113.
Gordon Moss, Shovellers got, 107.
Gordon Parish, report on Wild Geese, 79; Black Grouse, 160; Red Grouse, 164; Black-headed Gull, 274.
Gosford, East Lothian, Canada Goose, 95.
Gowkscroft, Lapwing abundant, 229.
Grampians, nesting of Dotterel, 210; Dotterel, 211.
Grange Wood, a favourite rest of Woodcock, 234.
Greenburn, 54.
Greenhaugh, Mallard, 102.
Greenhead, 54, 55.
Greenheugh, Rock Dove, 146.
Greenheugh, Oldcambus, Common Redshank in small flocks, 254.
Greenheugh Point, near Oldcambus, Purple Sandpiper occasionally seen, 247.
Greenknowe, Wild Geese, 77; White-fronted Wild Goose shot, 88; Spotted Crane shot, 198.
Greenlaw, Merlin, 22; Water Rail, 200; Coot, 204.
Greenlaw Dean, Wild Goose, 80; Dotterel, 219.
Greenlaw Moor, Kestrel, 26; Wild Geese at the Hule Moss, 80, 86, 87.
Greenlaw Parish, report on Wild Geese, 80; Hule Moss, 86; Black Grouse, 160; Red Grouse, 164;

- Dotterel in former times, 211 ;
 Dotterel in recent years, 212 ;
 Whimbrel, 263 ; Black-headed
 Gull, 274.
Greenriggs, Wild Geese, 84.
Green Stane, Common Cormorant,
 30.
Grey Mare, 246.
Grey Mare's Foal, 246.
Gull Rock, Peregrine Falcon's
 nest, 2.
Gull Rock, Fast Castle, Rock Dove,
 146.
Gull Rock, near Burnmouth, 280.
*Gull Rock, near mouth of Wolden
 Lee Burn*, one of the most westerly
 breeding places of the Herring
 Gull on the Berwickshire coast,
 281.
Gullane Sands, Wild Geese, 70.
Gumgreen, "Dow Cave," 145 ; tame
 Herring Gull, 284 ; 297.
Haddo House, Aberdeenshire, 160,
 161.
Hallyburton, Wild Geese, 80 ;
 Dotterel, 219.
Halterneloup, nesting of Peregrine
 Falcon, 2.
Handaze Wood, falconry, 18 ; hunt-
 ing lodge of Sir George Home of
 Wedderburn, 162.
Harbour Loch, Coldingham Shore,
 Long-tailed Duck, 122.
Harcarse, Water Rail, 201.
Hardens, Wild Geese, 78.
Harehead, Common Snipe, 241.
Harelaw, Wild Geese, 85 ; 156 ;
 Dotterel, 220.
*Harelaw, Craig's Wood, Duns Castle
 Estate*, Woodcock shooting, 237.
Harelaw Cove, Green Cormorant,
 33.
Harelaw, Westruther, 274.
Harelaw Moor, Golden Plover's
 nest, 222 ; Common Snipe, 241.
Harelawside, Wild Geese killed, 71 ;
 Lapwing, 227.
Harperton, 253.
Harryburn House, Lauder, Little
 Ank caught, 305.
Hartlaw, derivation of name, 209.
Hartside, Wild Geese, 73 ; deriva-
 tion of name, 208.
Hatchelnize, Wild Geese, 76.
Haugh Head, near Earleton, 274.
Hawk Kaim at Earleton, Falconry,
 11.
Hawksheugh, sheep's fleece used to
 capture young Peregrine Falcons,
 4.
Hawksheugh, near Burnmouth, de-
 rivation of name, 9.
Hawksheugh, near Cockburnspath,
 derivation of name, 9.
Hawksheugh, near Fast Castle, Pere-
 grine Falcon's nest, 3, 5 ; deriva-
 tion of name, 9.
Hawkslaw, Wild Geese, 76.
Hawkslaw in Parish of Coldstream,
 derivation of name, 9.
*Hawkslaw, formerly a part of Hally-
 down Estate*, 9.
Headcheater, appearance of Dotterel
 in September, 217.
Hebrides, 293.
Heligoland, 221.
Hen Poo, Duns Castle, a breeding
 station of Black-headed Gull in
 former times, 273.
Heron Scaur on the Dye, 47.
Heron's Hole on the Dye, 47.
Herrington, rhyme about Wild
 Geese, 87.
Heughhead, Earl of Wemyss stalk-
 ing Wild Geese, 68, 69 ; Wild
 Swan captured, 97.
Hezpath, Wild Geese, 79.
Hind's Cleugh, derivation of name,
 209.
Hindsidehill, Wild Geese, 85.
Hirsel, Common Heron, 43 ; Night
 Heron shot by the Earl of Home,
 52 ; Common Bittern shot, 61 ;
 Smew killed, 130 ; Pheasant
 shooting in 1810, 1816, and 1821,
 171.
Hirsel Lake, a favourite haunt of
 the Mallard, 102.
Hirsel Loch, Coot, 204.
Holy Island, Brant Geese, 91 ;
 Sheld-Duck, 100 ; Greenshank
 frequently seen, 256.
Home, falconry, visit of King James
 iv., 14.
Home Castle, 268.
Horn Burn, 56 ; drainage of Billie
 Mire, 57.
Horncliffe, 213.
Horsecastle Cove, St. Abb's Head,
 303.
Horseley, Dotterel, 213, 218.
Houndslow, Dotterel, 20.
Howpark, Dotterel, 213, 216, 218.
Hule Moss, in parish of Greenlaw,
 Wild Geese, 67 ; 86 ; description
 of situation, 87 ; Shoveller shot,
 107.

Hullidean Mill Pond, Bemersyde, nesting of Little Grebe, 318.

Humbie Wood, 134.

Hume Castle, visit of James IV. with falconers, 62.

Huntleywood Moss, formerly a haunt of the "Bull o' the Bog," 61.

Hutton, Red-throated Diver caught, 311.

Hutton Bridge, 142.

Hutton Hall, Peregrine Falcon, 5, 6.

Hutton Hall Mill, Peregrine Falcon's nest at Blue Braes, 5, 6.

Hutton Mains, Wild Geese, 81.

Hutton Parish, Common Heron, 45; report on Wild Geese, 80; Pallas's Sand Grouse, 156; Water Rail, 201; Coot, 204; Woodcock shooting, 237.

Hutton, in parish of Coldingham, derivation of name, 9.

Iceland, Red-throated Diver, 312.

Inverwick, Dotterel, 218.

Isle of May, migration of Cuckats, 133; Common Snipe seen on migration, 242; Black Guillemot, 304; migration, 328.

Jura, Red-throated Diver, 312.

Kaeter Well, 225.

Kaimes, turnips first sown in Berwickshire, 132.

Kelloe, Partridge shooting, 184.

Kelso, white Wood Pigeon, 140; 154; 248; 253; 256; Mr. Andrew Brotherston's account of moulting of Black-headed Gull, 272; 317.

Kettlehill, hawking at, 18; Black Grouse shooting, 1803-14, 158; Red Grouse shooting, 1812-14, 164; Dotterel, 220.

Kidshielhaugh, Wild Geese, 78.

Kimmerghame, Hobby, 20; George Home of Kimmerghame hawking Grouse at Kettlehill, 163; Water Rail, 201.

Kimmerghame Estate, White-fronted Wild Goose shot, 88.

Kimmerghame Mains, Wild Geese, 78.

Kirkcubbin, Rock Dove, 145.

Knebs Rocks, Common Bittern shot, 61.

Knock Hill, Merlin, 22.

Kyleshill, Black Grouse, 161.

Ladykirk, Common Cormorant, 31; Hawfinch, 351.

Ladykirk Lodge, 69.

Ladykirk Parish, Wild Geese, 81.

Lake Ladoga, Russia, Little Gull's breeding quarters, 267.

Lambden, occurrence of Whimbrel, 263.

Lamberton, Wild Geese, 83, 97; Rock Dove, 145; Turtle Dove obtained, 151; a favourite haunt of Dotterel, 212; bag of Dotterel killed in 1857, 213; Dotterel shooter, 215; Dotterel, 220; Woodcock's arrival in autumn, 234; 279; 298.

Lamberton Coal Point, Kestrel, 26.

Lamberton Kirk, 281.

Lamberton Moor, "Cockit-Hat" plantation, occurrence of Merlin, 22; Merlin pursuing Snipe, 22; Black Grouse, 160.

Lammerlaw, large bags of Red Grouse got in 1888, 165.

Lammermuir Whaaps, 259, 260.

Lammermuir Hills, Peregrine Falcon nesting in precipices, 5; Sir George Home's hunting lodge, Falconry, 18; Stock Dove, 143; Sir George Home of Wedderburn hawking Red Grouse in olden times, 162; Partridge, 178; Dotterel, 218; Common Redshank nesting, 255; Curlew abundant from spring to autumn, 258.

Lammermuirs, Merlin, 21; popular rhyme about the weather, 87; Black Grouse, 161; Red Grouse scarce in 1812-14, 164; large bags of Red Grouse got in 1886 and 1872, 165; Grouse disease, 167; cries of Red Grouse, 168; heather burning, 169; Common Quail, 190; Golden Plover plentiful, 221; Lapwing, 226, 227; Curlew nesting, 261; Red-necked Grebe killed, 315; occurrence of Storm Petrel, 321, 322; migration, 328.

Lammyrios montes, 166.

Lanele, Falconry, 15.

Lang Belt plantation, Mordington, Green Sandpiper, 253.

Langshaw, Black Grouse, 159.

Langstruther Bog, nest of Golden Plover, 222.

Langton, Pheasant shooting, 175; Partridge shooting, 185.

Langton Burn, Common Heron, 47;

- Wild Duck shooting, 105; Teal, 110.
- Langton House*, 274.
- Langton Lees*, Wild Geese, 81.
- Langton Parish*, report on Wild Geese, 81; Black Grouse, 160; Red Grouse, 164; 209.
- Lapland*, 294.
- Lauder*, Falconry, visit of King James iv., 14; Hobby, 20; visit of King James iv., Common Heron, 41; *Lauder*, Common Heron, 43; visit of James iv. with falconers, 62; Pochard in *Lauder*, 116; Black Grouse, 159; 223, 224; Little Auk caught, 305; Little Grebe, 319; 321.
- Lauderdale*, Merlin, 21; Wild Duck, 101; Wigeon, 113; folklore about Pigeons, 149; Black Grouse, 159; introduction of Pheasant, 171; 216; Dotterel, 219.
- Lauder Parish*, Peregrine Falcon's nest, 7; report on Wild Geese, 82; Mallard, 106; Black Grouse, 160; Red Grouse, 164; Dotterel in former times, 211; Dotterel in recent years, 212.
- Leader*, Osprey, 28; Common Heron, 46; Canada Geese killed, 96; Teal breeding near *Lauder*, 110; flock of Wigeon, 113; Pochard near *Lauder*, 116; Golden-Eye, 120; Goosander, 128; Water Rail, 201; Moor Hen, 202; Ringed Plover, 224; Black-headed Gull, 271; Black-headed Gull frequenting stream near *Earlston*, 272; Common Sandpiper, 250.
- Leader Haughs*, 226.
- Lees*, Wild Geese, 76; Pheasant shooting, 174; Partridge shooting, 184.
- Leet*, Wild Ducks' eggs, 106.
- Leetside*, Wild Geese, 86; Mallard visiting barley fields, 103.
- Legerwood*, Wild Geese, 82; Mallard damaging barley fields, 103; Red Grouse in end of last century, 163; Woodcock shooting, 236, 237.
- Legerwood Loch*, a haunt of Mallard, 102; Shovellers shot, 107; Teal, 110; Water Rail, 201; Coot, 204; Common Snipe found in considerable numbers, 241; Little Grebe abundant, 319.
- Legerwood Parish*, report on Wild Geese, 82; Black Grouse, 160; Red Grouse, 164; Dotterel in former times, 211; Black-headed Gull, 265.
- Leithholm*, Peregrine Falcon killed, 7.
- Lennel*, Earl of Wemyss stalking Wild Geese, 69.
- Lennel Hill Farm*, Mr. William White's notes on drainage of Billie Mire, 60.
- Lennel, near Coldstream*, occurrence of Ruff, 249.
- Lightfield, near Mellerstain*, Great Snipe shot, 240.
- Lighthouse, St. Abb's Head*, 146; Herring Gull, 280; Common Guillemot, 298.
- Linthill*, Wild Swan, 96; sign of bad weather, 227.
- Linthill House*, Dotterel, 219.
- Lintlaw*, 54, 55; Wild Geese, 73; occurrence of white Wood Pigeon, 139.
- Lintlaw Burn*, 55, 56.
- Litthillum or Ferneyrig Bog*, Common Bittern seen and heard, 62.
- Litthillum Loch*, Common Heron, 43; Eared Grebe shot, 317.
- Little Billie*, 55.
- Little Channeller Rock, St. Abb's Head*, colony of the Herring Gull, 280.
- Little Rooks*, Eider Duck, 124; 281.
- Little Swinton*, Wild Geese, 84.
- Little Swinton Farm*, Earl of Wemyss stalking Wild Geese, 69.
- Lochend*, Pheasant, 171.
- Lochton*, Wild Geese, 77; Sheld-Duck killed, 100; Water Rail, 201; Green Sandpiper shot, 253; Greenshank killed, 256, 257.
- Long Birgham*, Pintail Duck on the Tweed, 109.
- Longcroft Water*, nesting of Peregrine Falcon, 7.
- Longformacus*, Common Heron, 47; Wild Geese, 83; Black Grouse, 158; Red Grouse shooting, in 1813, 164; autumnal flights of Woodcock, 233; Woodcock shooting, 237; Common Snipe nesting, 242; Dunlin shot in July, 246; 319.
- Longformacus House*, Pallas's Sand Grouse, 156.
- Longformacus Parish*, Common Heron, 43; report on Wild Geese, 83; Duck ponds, 106; Mallard, 106; Pallas's Sand Grouse, 156; Black Grouse, 160; Red Grouse,

- 164; Dotterel in former times, 211; Dotterel in recent years, 212; Woodcock, 235.
- Low Bells*, Landrail's nest, 196.
- Luggy*, Common Heron, 43.
- Lumsden Moss*, Teal, 110.
- Lumsden Rocks*, Peregrine Falcon's nest, 5.
- Lurgie Loch*, Common Snipe, 241.
- Magdalen Fields*, Falcons at Highland and Agricultural Society's Show in 1841, 3.
- Maggie Shaw's Crookie*, 275.
- Manderston*, Pheasant shooting, 173; Partridge shooting, 183.
- Marchmont*, Common Heron, 44, 86; Wild Geese shot at the Hule Moss, 87; Tufted Duck killed, 118; 131; Wood Pigeon breaking topmost shoots of fir trees, 138; Pheasant shooting, 176; Partridge shooting, 184; 219.
- March Wood*, Common Heron, 44.
- Marygold*, 54; white Wood Pigeon, 139.
- Marygold Burn*, 56.
- Maw Carr*, nest of Herring Gull, 280.
- Maw Craig, near mouth of Wolden Lee Burn*, one of the most westerly breeding places of the Herring Gull on the Berwickshire coast, 281.
- Maxton*, 253.
- Mayfield*, Merlin, 21; 54; Wild Geese, 73; Dotterel, 215.
- Meikle Law*, Merlin, 24.
- Mellerstain*, last Common Bittern, 61; Passenger Pigeon shot, 153; Pheasant shooting, 174; Partridge shooting, 183; peculiarly marked Partridge, 189; late Landrail, 196.
- Mellerstain Downs*, Dotterel, 210.
- Melrose*, falconry, 11.
- Merlin Grain*, a ravine near Meikle Law, Merlin, 24.
- Merse*, falconry, visit of King James iv., 14; formerly covered with bogs and morass, Common Bittern, 62.
- Mertoun*, heronry, 48, 49; Stock Dove, 143; Oyster Catcher, 231; nesting of Little Grebe, 318.
- Mertoun House*, Common Heron, 43, 50, 51.
- Mertoun Parish*, Common Heron, 43; Black-headed Gull, 268.
- Middlethird*, Wild Geese, 79.
- Millfield*, 303.
- Milne Graden*, Teal on the Tweed, 111; Pheasant shooting, 173; Meteorological Notes, 351-57; 358.
- Milne Graden West Mains*, Wild Geese, 76.
- Minchie Moss*, Common Bittern, 61.
- Mont Albane*, Wild Geese, 75.
- Monynut*, Black Grouse, 158; Red Grouse shooting in 1813, 164.
- Moor Baits*, nest of Herring Gull, 281.
- Moor Plantation, Whitechester*, a favourite resort of Woodcock, 235.
- Mordington*, Stock Dove, 143; Black Grouse, 159, 160; Pheasant shooting, 175; Partridge shooting, 185; ten brace of Dotterel shot, 220; 253.
- Mordington Mains*, Wild Geese, 83; Common Quail, 191; Green Sandpiper observed, 253.
- Mordington Parish*, report on Wild Geese, 83; Red Grouse, 164; Dotterel, 210; Dotterel in former times, 211; Dotterel in recent years, 212; Woodcock, 234.
- Moristons*, Dotterel, 210.
- Moss Maw*, Lapwing's nest, 227.
- Mucklesane Moor*, Hobbie Elliot's "lang-nebbit things," 260.
- Muirkirk, Ayrshire*, story about the "wheaple of a whasp," 258.
- Murraylawrig*, Merlin, 22.
- Nabdean*, Woodcock frequenting plantation, 235.
- Nabdean Mill Pond*, Water Rail, 201; Little Grebe, 319.
- Nenthorn*, Wigeon on the Eden, 113; Dotterel, 210.
- Nenthorn Parish*, Dotterel in former times, 211.
- Nesbit House*, Common Heron, 45.
- Netherbyres Mill*, Osprey, 28.
- Newbigging, Lauder*, Wigeon in pond, 113.
- Newbyth*, Peregrine Falcons got from Burnmouth by Sir David Baird, Bart., 2; Falcons kept there, 19.
- Newmills, Lauder*, Wigeon on Leader, 113.
- Ninewells*, Green Sandpiper shot, 253.
- Ninewells Old Bridge*, Osprey, 27.
- Nisbet*, Pheasant shooting, 174; Partridge shooting, 184.
- Nisbet House*, Common Quail, 191.
- North Berwick*, Gannet, 37.

- North Berwick Law*, 231.
North Cleugh, Coot, 205.
North Falaknooe, Wild Geese, 76.
Northumberland, Shoveller breeding, 108; Tufted Duck breeding, 118; migration, 327.
Northumberland Coast, 100.
- Oak Wood near Penmanshiel*, Woodcock nesting, 237.
Old Bound Road near Paxton, Pochard shot on Whitadder, 116.
Oldcambus, Peregrine Falcon, 2; Kestrel, 25; Common Heron, 46; Rock Dove, 146; effects of wet summer on Partridges, 186; Moor Hen, 203; 213; 218; Green Sandpiper frequenting Dean, 252; Common Redshank on coast, 254; Curlew on shore, 260; Black-headed Gull leaving coast in spring, 269; 279; Herring Gull feeding on fragments of bottle-nosed whale, 282; ways of catching Gulls with hooks, 284; 289; Razor Bills washed ashore in severe winter of 1878-79, 296; Great Northern Diver found on shore, 309; ornithological observations, 329.
Oldcambus and Cockburnspath Parish, Red Grouse in 1835, 164.
Oldcambus East Mains, arrival of Woodcock, 234.
Old Camp at Milne Graden, Common Corncrake, 31.
Oldcastles, 54; Billie Mire, 60, 61.
Old Crao Ha', Osprey, 28.
Old Greenlaw, Wild Geese, 80.
Oldhamstocks, Dotterel, 218.
Oldhamstocks Parish (detached) report on Wild Geese, 84; Red Grouse, 164; Common Quail, 190; Common Quail nesting on Springfield Farm, East Lothian, 191.
Old Heronry Wood, Paxton, Common Heron, 45; Stock Dove's nest, 141; Woodcock, 235.
Olister Dub, Common Heron, 43.
Orkney, Falconry, 13; Dotterel nesting, 211; Whimbrel, 263.
Orleans, France, Common Quail, 192.
Overhoulden, Wild Geese, 73.
Oxton, occurrence of Storm Petrel, 321.
- Park*, 218.
"Patie's Pat," pool on the Whitadder, Peregrine Falcon's nest, 5.
- Paxton, Orro Dean Wood*, Merlin, 21; Finchy, Merlin, 21; Common Cormorant, 31; Common Heron, 35; Wild Swans on the Tweed, 97; Sheldrake on the Tweed, 100; Teal on the Tweed, 111; Wigeon on Tweed, 113; Pochard on Tweed, 115; Tufted Duck on Tweed, 118; Scaup Duck on Tweed, 119; Long-tailed Duck on Tweed, 122; Eider Duck on Tweed, 124; Common Scoter on Tweed, 126; Ring Dove feeding on beechnuts, 133; migration of Cushats, 133; Shooting Cushats in Wester Park, 133; Wood Pigeon feeding on young leaves of beech tree, 138; Pigeon nesting near house, 139; popular saying comparing frost-rime to White Pigeon, 150; 155; Pheasant shooting, 174; Common Quail, 191; Landrail, 194; Moor Hen's nest in wooden spout, 203; favourite retreats of Woodcock, 235; Woodcock shooting, 237; Red-throated Diver on Tweed, 311; Little Grebe, 319.
Paxton House, Peregrine Falcon seen, 7; Stock Dove's nest, 141, 142, 143; Green Sandpiper shot, 252; Greenshank shot, 256.
Paxton North Mains, Greenshank shot, 256.
Paxton South Mains, Wild Geese, 81.
Pease Burn, Coot, 205.
Pease Sands, Kittiwake Gull, 290.
Peck Stane, 55.
Peelwalls, 273.
Peely Braes Wood, Duns Castle, Woodcock's nest discovered, 238.
Penmanshiel, Kestrel, 25; Wild Geese, 71; Wild Goose trapped, 71; Wild Geese, 74, 75; Wood Pigeon, 137; Dotterel, 215, 216; Golden Plover, 221; Lapwing, 227; Woodcock's nest, 238; Common Snipe bleating, 242, 243; Curlew's cry, 259; Little Ank found, 305.
Perthshire, Tufted Duck feeding, 118.
Petticovick Cove, Peregrine Falcon's eyrie, 2.
Petticovick Harbour, 146; 280; Common Guillemot, 296.
Pickie Moss, Dowie Den Moss, Everett Moss or Legerwood Lock,

- nesting station of the Black-headed Gull, 268.
Piper's Cove, Rock Dove, 145.
Piper's Knowe, 54.
Pistol Plantation, Common Heron, 43; Blackadder, a favourite roosting place of Wood Pigeons, 183.
Plover's Cairn, 223.
Plovering Haugh, 223.
Pohorath, 131.
Pohorath Parish, Common Heron, 44; Black Grouse, 160; Red Grouse, 164.
Prendergust, 56; Partridge shooting, 181, 182.
Press, Wild Swan captured, 97.
Preston, Wild Geese, 72; Dotterels' wing feathers used for fly dressing, 215.
Preston Cleugh, 56.
Prestonkirk, 93; 235.
Printonian, Wild Geese, 77, 78.
Pyper Knowes, Landrail, 195.
- Quirkwood*, Peregrine Falcon trapped, 7; Merlin, 22; Wild Geese, 72; Pallas's Sand Grouse, 156; Black Grouse, 158; Red Grouse shooting in 1813, 164; bags of Red Grouse got in 1889 and 1891, 166; Partridge shooting, 181; Dotterel, 213, 214, 215.
- Raeleugh*, derivation of name, 208.
Raeleugh Farm, Peregrine Falcon's nest, 6.
Raeleugh Head, Pallas's Sand Grouse shot, 156; derivation of name, 208.
Rammel Cove, Peregrine Falcon breeding, 2; Rock Dove's resorts, 146.
Rampart, St. Abb's Head, 280; nesting of Kittiwake Gull in former times, 289, 290; Razor Bill nesting in 1885, 296; colonies of Common Guillemots, 296; taking of Guillemot's eggs, 300.
Raven's Craig, Faldcleugh, Stock Dove's nest, 143.
Ravensheugh, St. Abb's Head, nest of Herring Gulls, 280; colony of Common Guillemots, 299.
Raven's Knowe, near Tibbie Fowler's Glen, Kestrel, 26.
Rawburn, Wild Geese, 77; Dotterel, 218.
Redheugh, Peregrine Falcon, 2; Common Bittern, 61; Wild Geese, 74; Bewick's Swan east ashore, 99; high grounds in neighbourhood a favourite haunt of Dotterel, 212; Dotterel in autumn, 216, 217; Oyster Catcher, 231; Woodcock's arrival in autumn, 234; arrival of Woodcock, 234; Herring Gull's nest, 281.
Redheugh Shore, 146.
Redpath Bog, 199, 200; Common Snipe, 241; a breeding station of the Black-headed Gull in former times, 274.
Redpath, near Earleton, 274.
Redshank's Rock, Coldingham Shore, 255.
Rentonbarns, Wild Geese, 75.
Renton Bell, Dotterel, 216.
Renton Hall, Haddington, Common Quail, 192.
Restalrig, 281.
Retreat, Osprey, 28; Wild Geese, 83; Pallas's Sand Grouse shot, 156; Dotterel, 213, 215, 218.
Romorantin, Loir-et-Cher, France, Turtle Doves plentiful, 151.
Ross-shire, Dotterel nesting, 211.
Rough Head, Common Heron, 45.
Roxburghshire, Tufted Duck breeding, 118.
Rumbleton, Wild Geese, 79.
Rumbleton Law, Wild Geese, 79; 219.
Ryselaw, Wild Geese, 78.
- St. Abb's Head*, Peregrine Falcon's eyrie, 1, 2, 3; Green Cormorant, 34; Rock Dove, 145, 146; Common Tern, 265; Common Gull, 276, 277, 278; Herring Gull in great numbers, 279; cry of Herring Gull, 279; boys killed while searching for Gulls' eggs, 282; Great Black-backed Gull occasionally seen, 286; breeding of Kittiwake Gull in former times, 288, 289, 290; Razor Bills plentiful in 1832 and 1851, 295; Razor Bills now scarce, 296; a favourite haunt of the Common Guillemot, 297; notes on Guillemots by Mr. Archibald Hepburn in 1851, 299; Guillemots not so plentiful as formerly, 300; Guillemots leaving cliff after breeding season, 301; Ringed Guillemot, 302; Black Guillemot shot, 303, 304; Puffin, 307, 308; incident in connection with Storm Petrel in

- great storm of 14th October 1881, 322; migration, 328, 351-355.
St. Abb's Nunnery, 280.
St. John's Farm, Foulden, Common Quail, 191.
St. Leonard's Cauld, on Leader, Goosander, 198; Little Grebe shot, 319.
St. Mary's Cottage, Duns, 273.
Salthugh, Common Heron, 45.
Salton, Wild Geese, 87; Cushats on wheatfield, 134; "Big Wood," 134; Pheasant, 171.
Salton's Wood, Common Heron, 42.
Sandy Knowe Tower, 270.
Sauldre River, Loir-et-Cher, France, Turtle Dove's nest, 151.
Scarlaw, Black Grouse, 158; Red Grouse shooting in 1813, 164.
Scartheugh, Milne Graden, Common Cormorant, 31.
Scart Rock, Common Cormorant, 30.
Scout Cave, near Eyemouth, 297.
Scouts' Croft, near Coldingham, 297.
Scouts' Point, near Gunsgreen, 297.
Shannobank, Wild Geese, 72; number of Dotterel shot, 213, 214.
Shannobank Farm, field called the Gull Mire, a breeding station of Black-headed Gull in former times, 274.
Shellands, Whimbrel, 263.
Shillum Dikes, 55.
Siccar, 146; Herring Gull's nest, 281.
Siccar Bay, Golden-Eye, 120.
Siccar Point, Kestrel, 26; Common Cormorant, 30, 31; Heron's nest, 45; Oyster Catcher, 231; Herring Gull on rocks, 283; Common Redshank in small flocks, 254.
Simprim Mains, Earl of Wemyss stalking Wild Geese, 69; Wild Geese, 84.
Sisterpath, Wild Geese, 78.
Skasithmuir, Wild Geese, 76.
Skelly, Razor Bill nesting in 1855, 296; colonies of Common Guillemots, 298.
Skelly, St. Abb's Head, Herring Gull's nest, 280.
Skelly Rock, St. Abb's Head, Great Black-backed Gull breeding in 1851, 286; nesting of Kittiwake Gull in former times, 289, 290.
Slighouses, 54; source of Draeden Burn, 55, 56.
Snuffehole Stells, nests of Herring Gulls, 280.
Soldier's Dyke, Dowlaw, locality frequented by Dotterel, 217.
Spott, 217.
Spottiswoode, Hawking at, 19; Gannets, 35; Common Heron, 47; Teal, 110; Black Grouse, 161; introduction of Pheasants, 171; Pheasant shooting, 176; Partridge shooting, 185; Coot, 204; 220; Woodcock shooting, 237; Curlew abundant, 258; Little Grebe, 319.
Spottiswoode Estate, bags of Red Grouse got, 166.
Spital, Pheasant shooting, 174; Partridge shooting, 184; 315.
Spital House, Pallas's Sand Grouse, 156; Water Rail, 201; Great Snipe shot, 240.
Spital Mains, Wild Geese, 81.
Springhill, near Coldstream, Black Tern captured, 264.
Standing Man or Souter Rock, Peregrine Falcon's eyrie, 4; nest of Herring Gulls, 281.
Stoneshiel, 54, 55.
Stirling Fauld, Dowlaw, locality frequented by Dotterel, 217.
Sunnyside, 55, 60.
Swanwick, Wild Geese, 81.
Sutherlandshire, Whimbrel, 263.
Swallow Craig, Common Heron, 45; Rock Dove's cave, 146.
Swinton, Partridge shooting, 185; Common Redshank, 255.
Swinton Hill, Wild Geese, 84; Common Redshank nesting, 255.
Swinton Mill, Wild Duck shooting, 104.
Swinton Parish, report on Wild Geese, 84; Mallard, 106.
Tantallon Castle, falconry, Mary of Lorraine and Earl of Angus, 11.
The Anchorage, Berwick-on-Tweed, 284.
The Camp, near Foulden, 305.
The Isles, falconry, 13.
Thirlestane, Wild Geese, 82; Dotterel, 219.
Thirlestane Castle, Hobby, 20; Common Heron, 43; Black Game, 159; introduction of Pheasants to coverts, 171; Common Quail, 190; Great Snipe got, 240.
Thirlestane Castle Sawmill, Kestrel, 26.
Thrummie Carr, nest of Herring Gull, 280; the most westerly

- breeding station of Common Guillemot in Berwickshire, 299.
Tookey Cove, St. Abb's Head, Black Guillemot, 303.
Townhead, Cockburnspath, Coot, 204, 205.
Townhead Mill Pond, Teal, 110.
Townhead Pond, near Cockburnspath, Little Grebe nesting, 318.
Tweed, Osprey, 27; Common Cormorant, 31; Common Heron, 42, 45, 48, 49; Wild Swans in severe winter of 1879-80, 97; Sheld-Duck near Paxton, 100; Pintail Duck shot, 109; Teal near Paxton, 111; Wigeon at Paxton, 113; Pochard at Paxton, 115; Pochard at Birgham, 116; Tufted Duck at Paxton, 118; Scaup Duck at Paxton, 119; Golden-Eye, 120; Golden-Eye at Lochton, 120; Long-tailed Duck, 122; Eider Duck seen at Paxton, 126; Goosander, 128; Stock Dove's nest near Paxton, 141; Rock Dove, 148; Landrail, 194, 196; Ringed Plover, 224; Woodcock shooting, 237; Common Sandpiper, 250; Green Sandpiper, 252; Black-headed Gull in small flocks, 271; Lesser Black-backed Gull, 285; Kittiwake Gull occasionally seen in spring, 290; Great Northern Diver shot, 310; Red-throated Diver sometimes seen on river, 311; Black-throated Diver, 312; Great Crested Grebe, 313; Eared Grebe, 317; Little Grebe at Paxton, 319.
Tuchit Yells, 225.
Twinlawford, 223.
Twinlaw Cairns, 87.
Twinzell House, 234.
Tyne, East Lothian, Common Sandpiper, 251.
Tyne Estuary, Ruff, 249.
Ulystrand Brae, nests of Herring Gull, 280.
Warlawbank, 54; source of Fosterland Burn, 55.
Watch Cover, Woodcock shooting, 237.
Watch Water, Woodcock, 233.
Waulkmill (Cumledge) Common Bittern, 61.
Wedderburn, falconry, 17, 18; Sir George Home's Hawks called Mer-lins, 22; Red Grouse hawking in olden time, 162; Pheasant shooting, 173; Sir George Home hawking Partridges, 179; Partridge shooting, 183.
Wedderburn Castle, Common Heron, 47; Wild Duck shooting, 105; Teal, 110.
Wedderburn North Lodge, former haunt of Teal, 110.
Wedderlie, late stay of Wild Geese, 71; Wild Geese, 85, 87.
Wedderlie Farm, White Grouse seen, 168.
Wellmire Wood, Paxton, migration of Ring Dove, 133; Woodcock, 235.
Welnage, notes by Mr John Wilson on Billie Mire, 57; 60; 214.
West Fishwick, Wild Geese, 87.
West Hurker, Common Guillemot, 298.
West Mains Brae, Common Heron, 43.
West in Thirle Bay, nests of Herring Gull, 280.
Westruther, 200; Golden Plover, 222, 223; 274; Little Grebe, 319.
Westruther Mains, Wild Geese, 85; Dotterel, 220.
Westruther Parish, Common Heron, 44; report on Wild Geese, 85; Black Grouse, 160; 209; Dotterel in former times, 211, 220; Common Snipe, 241.
Whitadder, Peregrine Falcon's nest in former times, 5, 6; Kestrel, 26; Osprey, 27, 28; Common Heron, 45; 54, 56, 57; Wild Swan killed, 97; frequented by the Mallard, 103; Wild Duck's nest, 104; Teal near Ellemford, 110; Teal near Blanterne, 111; Pochard shot near Old Bound Road, 116; Pochard killed above Cockburn, 116; Golden-Eye at Abbey St. Bathans, 120; Goosander, 128; Ring Dove, 132, 133; near Hutton Bridge, Stock Dove's nest, 142; Stock Dove's nest near Edrington, 143; Stock Dove's nest near Falloleugh, 143; Rock Dove, 148; Turtle Dove shot near Edrington, 151; Moor Hen, 202; Coot, 204; Dotterel, 214; 235; Common Sandpiper, 250; Green Sandpiper seen, 253; Greenshank, 256; Lesser Black-backed Gull, 285; Great Northern Diver at Edrington Mill Cauld,

- 309; Red-throated Diver sometimes found on river, 311; Red-throated Diver killed near Preston, 311; Red-necked Grebe shot at Clarabad Mill Cauld, 315; Little Grebe found at Blanerne, 319.
- Whitburn*, Common Quail, 190.
- Whitchester*, Black Game, 159; Red Grouse shooting in 1814, 164; Little Grebe shot on Dye, 319.
- Whiteburn*, Wild Geese, 72; Dotterel, 214.
- Whitefield near Cowdenknowes*, Arctic or Richardson's Skua shot, 293.
- Whitehall*, 59; Pheasant shooting, 173; Partridge shooting, 182.
- Whiteheugh*, Peregrine Falcon's eyrie in 1857, 2.
- Whiteheugh, near Coldingham Shore*, colony of Common Guillemots, 298.
- Whitelaw*, a favourite haunt of Golden Plover, 221.
- Whiterig*, Partridge shooting, 181, 182.
- Whitesomehill*, Wild Geese, 86.
- Whitfield near Ayton*, 156; Woodcock shooting, 237.
- Whirig Bog*, Mr. John Thomson's account of Wildfowl found there, 271.
- Whirig Tower*, 270.
- Whitelaid*, Woodcock shooting, 237.
- Whitesomehill*, a favourite haunt of Golden Plover, 221.
- Whitsomelaw*, Wild Geese, 86.
- Whitsome Parish*, Common Heron, 43; report on Wild Geese, 86; Golden Plover, 221.
- Whitsome Village*, Water Rail, 201.
- Whittingham*, Pheasant, 171.
- Whytwater*, 166.
- Wild Duck Ha'*, derivation of name, 106.
- Winden Cairn*, Golden Plover's nest, 222.
- Windylaw Cove*, Rock Dove's nest, 146.
- Winfield*, Wild Geese, 86.
- Wolf's Crag*, 281.
- Woodend*, Wild Geese, 81.
- Woodhead Hill, Lauder*, Black Grouse first seen, 159.
- Yarrow*, 226.
- Yetholm Loch*, Tufted Duck breeding, 118.

IV.—MIGRATION AND OBSERVATION INDEX TO VOL. I. AND VOL. II.

- Ank, Little (*Mergulus alle*), ii. 305.
- Bean Goose (*Anser segetum*). See Goose, Bean.
- Blackcap (*Sylvia atricapilla*), i. 60, 61; ii. 329, 340, 341, 342, 344, 347, 348, 352.
- Blackbird (*Turdus merula*), i. 27, 30; ii. 332, 336, 337, 340, 341, 342, 344, 345.
- Brambling (*Fringilla montifringilla*), i. 166, 167; ii. 331, 335, 336, 350, 354.
- Bullfinch (*Pyrrhula europæa*), i. 176.
- Bunting, Corn (*Emberiza miliaria*), i. 181; ii. 333, 337, 338, 341, 344, 350.
- Bunting, Reed (*Emberiza schoeniclus*), i. 187.
- Bunting, Snow (*Plectrophanes nivalis*), i. 189, 190; ii. 331, 336, 339, 348, 349, 355.
- Bunting, Yellow (*Emberiza citrinella*), i. 183; ii. 334, 336, 337, 341, 347.
- Buzzard (*Buteo vulgaris*), i. 302.
- Buzzard, Rough-legged (*Buteo lagopus*), i. 305.
- Chaffinch (*Fringilla caelebs*), i. 163, 164; ii. 333, 336, 337, 340, 341, 342, 347.
- Chiffchaff (*Phylloscopus collybita*), i. 69, 70; ii. 330, 338, 339, 340, 352.
- Coot, Common (*Fulica atra*), ii. 334, 338, 339, 344, 349.
- Cormorant, Common (*Phalacrocorax*

- carbo*), ii. 334, 335, 337, 340, 345, 346, 349.
 Crane, Spotted (*Porzana maculata*), ii. 198.
 Crow, Carrion (*Corvus corone*), i. 210, 211.
 Crow, Hooded (*Corvus cornix*), i. 214; ii. 340.
 Cuckoo (*Cuculus canorus*), i. 274; ii. 331, 339, 342, 344, 345, 346, 354.
 Curlew, Common (*Numenius arquata*), ii. 260, 261, 335, 336, 338, 341, 344, 345, 346, 348.
 Diver, Great Northern (*Colymbus glacialis*), ii. 309.
 Diver, Red-throated (*Colymbus septentrionalis*), ii. 311.
 Dotterel (*Charadrius morinellus*), ii. 210-220, 324, 331, 339, 341, 342, 343, 344, 348, 355.
 Dove, Ring (*Columba palumbus*), ii. 132, 133, 334, 336, 337, 338, 340.
 Dove, Turtle (*Turtur communis*), ii. 151.
 Duck, Long-tailed (*Harelda glacialis*), ii. 122.
 Duck, Pintail (*Dasila acuta*), ii. 109.
 Duck, Tufted (*Fuligula cristata*), ii. 118.
 Duck, Scaup (*Fuligula marila*), ii. 119.
 Duck, Wild (*Anas boschas*). See Mallard.
 Dunlin (*Tringa alpina*), ii. 246.
 Fieldfare (*Turdus pilaris*), i. 18; ii. 331, 336, 339, 343, 349, 350, 354.
 Flycatcher, Pied (*Muscicapa atricapilla*), i. 133; ii. 333, 342, 343.
 Flycatcher, Spotted (*Muscicapa grisola*), i. 131; ii. 330, 343, 344, 346, 353.
 Gannet or Solan Goose (*Sula bassana*), ii. 35, 36, 334, 339, 340, 342.
 Garganey (*Querquedula circia*), ii. 112.
 Godwit, Black-tailed (*Limosa ogocephala*), ii. 257.
 Golden-Eye (*Fuligula clangula*), ii. 120, 337, 338, 339.
 Goosander (*Mergus merganser*), ii. 128.
 Goose, Bean (*Anser segetum*) and Goose, Pink-footed (*Anser brachy-*
rhynchus), ii. 66-89, 324, 331, 336, 338, 341, 348, 349, 350, 355.
 Goose, Barnacle (*Bernicla leucopsis*), ii. 93.
 Goose, Brent (*Bernicla brenta*), ii. 91.
 Goose, Solan (*Sula bassana*). See Gannet.
 Goose, White-fronted (*Anser albifrons*), ii. 90.
 Grebe, Eared (*Podiceps nigricollis*), ii. 317.
 Grebe, Great Crested (*Podiceps cristatus*), ii. 313.
 Grebe, Little (*Podiceps rivialis*), ii. 335, 340, 349.
 Grebe, Red-necked (*Podiceps grisigena*), ii. 315.
 Greenfinch (*Coccothraustes chloris*), i. 154.
 Greenhank (*Totanus canescens*), ii. 256.
 Gull, Black-headed (*Larus ridibundus*), ii. 335, 338, 339, 345.
 Gull, Glaucous (*Larus glaucus*), ii. 287.
 Gull, Little (*Larus minutus*), ii. 267.
 Hen, Moor (*Gallinula chloropus*), ii. 334, 337, 338, 339.
 Hobby (*Falco subbuteo*), ii. 20.
 Jacksnipe (*Gallinago gallinula*), ii. 244.
 Kestrel (*Falco tinnunculus*), ii. 25.
 Landrail, (*Orex pratensis*), ii. 194, 196, 331, 341, 343, 344, 347, 354.
 Lapwing (*Vanellus vulgaris*), ii. 225, 226, 333, 335, 337, 339, 341, 344, 345, 346, 349.
 Linnet (*Linola cannabina*), i. 170; ii. 333, 336, 338, 341, 346, 349, 350.
 Mallard or Wild Duck (*Anas boschas*), ii. 334, 336, 339, 340, 341, 343, 345, 347, 349.
 Martin (*Chelidon urbica*), i. 141, 143; ii. 330, 340, 342, 343, 346, 347, 348, 353.
 Martin, Sand (*Cotile riparia*), i. 144, 145; ii. 330, 339, 340, 343, 347, 348, 353.
 Nightjar (*Caprimulgus europæus*), i. 258; ii. 330, 342, 343, 344, 345, 346, 353.

- Osprey (*Pandion haliaetus*), ii. 27.
 Ouzel, Ring (*Turdus torquatus*), i. 32, 34; ii. 329, 337, 338, 339, 340, 342, 344, 345, 349, 350, 351.
 Owl, Long-eared (*Asio otus*), i. 287.
 Owl, Short-eared (*Asio accipitrinus*), i. 289.
- Partridge, Common (*Perdix cinerea*), ii. 334, 336, 337, 338, 344, 345.
 Pheasant (*Phasianus colchicus*), ii. 341, 344, 345.
 Pink-footed Goose (*Anser brachyrhynchus*). See Goose, Bean.
 Pipit, Meadow (*Anthus pratensis*), i. 114, 115; ii. 332, 337, 339, 342, 347, 348, 350.
 Pipit, Rock (*Anthus obscurus*), i. 118; ii. 332, 336, 338, 340, 345, 348.
 Pipit, Tree (*Anthus trivialis*), i. 116; ii. 330, 341, 342, 343, 349, 353.
 Plover, Golden (*Charadrius pluvialis*), ii. 221, 335, 336, 337, 338, 341, 346, 347.
 Pochard (*Fuligula ferina*), ii. 115, 116.
 Puffin (*Fratercula arctica*), ii. 307.
- Quail, Common (*Coturnix communis*), ii. 190.
- Rail, Water (*Rallus aquaticus*), ii. 200.
- Redbreast (*Erithaca rubecula*), i. 50, 51; ii. 324, 332, 336, 337, 342, 343, 345, 346, 347, 349.
 Redpoll, Lesser (*Linota rufescens*), i. 172.
 Redshank, Common (*Totanus calidris*), ii. 254.
 Redstart (*Phoenicurus ruticilla*), i. 47; ii. 329, 340, 341, 343, 345, 347, 348, 349, 351.
 Redwing (*Turdus iliacus*), i. 14, 15; ii. 331, 339, 340, 341, 349, 350, 354.
 Rook (*Corvus frugilegus*), ii. 334, 337, 338, 341.
 Ruff (*Machetes pugnax*), ii. 248.
- Sandpiper, Common (*Totanus hypoleucus*), ii. 250, 331, 341, 354.
 Sandpiper, Green (*Totanus ochropus*), ii. 252, 253.
 Sandpiper, Purple (*Tringa striata*), ii. 247.
 Sooter, Common (*Edemia nigra*), ii. 126.
- Sooter, Velvet (*Edemia fusca*), ii. 127.
 Shoveller (*Spatula clypeata*), ii. 107.
 Siskin (*Carduelis spinus*), i. 152.
 Skua, Arctic, or Richardson's (*Stercorarius crepidatus*), ii. 293.
 Skua, Long-tailed, or Buffon's (*Stercorarius parasiticus*), ii. 294.
 Skua, Pomatorhine (*Stercorarius pomatorhinus*), ii. 292.
 Skylark (*Alauda arvensis*), i. 251, 252; ii. 333, 336, 337, 338, 347, 348, 349, 350.
 Snipe, Common (*Gallinago caelestis*), ii. 242, 333, 338, 339, 340, 343, 344, 345.
 Snipe, Great (*Gallinago major*), ii. 240.
 Smew (*Mergus albellus*), ii. 130.
 Sparrow, Hedge (*Accentor modularis*), ii. 333, 336, 337, 338.
 Sparrow, House (*Passer domesticus*), i. 158, 159.
 Sparrow, Tree (*Passer montanus*), i. 160.
 Starling (*Sturnus vulgaris*), i. 194, 195; ii. 334, 336, 337, 340, 344, 346, 348, 350.
 Stonechat (*Saxicola rubicola*), i. 44, 45; ii. 332, 336, 338, 342, 344, 345, 347, 349, 350.
 Swallow (*Hirundo rustica*), i. 135, 136, 138; ii. 324, 330, 339, 341, 343, 346, 347, 348, 353.
 Swan, Bewick's (*Cygnus Bewicki*), ii. 99.
 Swift (*Cypselus apus*), i. 256; ii. 330, 343, 344, 346, 347, 353.
- Teal (*Querquedula crecca*), ii. 110.
- Tern, Common (*Sterna fluvialis*), ii. 265.
- Thrush, Missel (*Turdus viscivorus*), i. 9, 10, 11, 12; ii. 332, 336, 337, 338, 340, 342, 347, 349, 350.
 Thrush, Song (*Turdus musicus*), i. 3, 4, 5; ii. 324, 332, 336, 337, 338, 341, 343, 345.
 Titmouse, Blue (*Parus caeruleus*), i. 98; ii. 333, 337.
 Titmouse, Cole (*Parus ater*), i. 93.
 Titmouse, Great (*Parus major*), i. 91; ii. 333, 336, 338, 340.
 Titmouse, Long-tailed (*Acredula caudata*), i. 89.
- Wagtail, Grey (*Motacilla sulphurea*), i. 111, 112; ii. 332, 335, 338, 343, 348, 350.

- Wagtail, Pied (*Motacilla lugubris*), i. 108, 109; ii. 332, 336, 338, 341, 348, 349.
- Warbler, Garden (*Sylvia salicaria*), i. 63, 64; ii. 329, 343, 344, 347, 352.
- Warbler, Grasshopper (*Acrocephalus naevius*), i. 79; ii. 330, 344, 353.
- Warbler, Sedge (*Acrocephalus schoenobaenus*), i. 76; ii. 330, 342, 344, 345, 346, 353.
- Wheatear (*Saxicola oenanthe*), i. 36, 37; ii. 329, 337, 339, 342, 345, 346, 347, 349, 351.
- Whimbrel (*Numenius phaeopus*), ii. 263.
- Whinchat (*Saxicola rubetra*), i. 41, 42; ii. 329, 339, 343, 346, 349, 351.
- Whitethroat (*Sylvia rufa*), i. 57, 58; ii. 329, 341, 342, 343, 344, 346, 347, 349, 352.
- Whooper (*Cygnus musicus*), ii. 96, 97.
- Wigeon (*Mareca penelope*), ii. 113.
- Wild Goose. See Goose, Bean, and Pink-footed.
- Woodcock (*Scolopax rusticula*), ii. 233, 234, 333, 339, 340, 342, 348, 349.
- Woodpecker, Great Spotted (*Dendrocopos major*), i. 263.
- Wren (*Troglodytes parvulus*), i. 102; ii. 332, 336, 339, 340, 349.
- Wren, Golden-crested (*Regulus cristatus*), i. 65, 66.
- Wren, Willow (*Phylloscopus trochilus*), i. 71, 72; ii. 330, 339, 340, 342, 346, 347, 348, 352.
- Wren, Wood (*Phylloscopus sibilatrix*), i. 73, 74; ii. 330, 340, 342, 343, 344, 346, 347, 352.



V.—INDEX TO NAMES OF BIRDS IN VOL. I. AND VOL. II.

LATIN NAMES.

	VOL. AND PAGE		VOL. AND PAGE
<i>Accipiter</i> ,	ii. 1	<i>Buteo lagopus</i> ,	i. 306
<i>Ardeida</i> ,	ii. 39	<i>Ciconiida</i> ,	ii. 64
<i>Ardea cinerea</i> ,	ii. 39	<i>Ciconia alba</i> ,	ii. 64
<i>Anseres</i> ,	ii. 66	<i>Oxynclida</i> ,	i. 85
<i>Anatida</i> ,	ii. 66	<i>Oxynclis aquaticus</i> ,	i. 85
<i>Anser segetum</i> ,	ii. 66	<i>Oygnus musicus</i> ,	ii. 96
„ <i>brachyrhynchus</i> ,	ii. 66	„ <i>Bewicki</i> ,	ii. 99
<i>Acrocephalus schœnobæus</i> ,	i. 75	<i>Columba</i> ,	ii. 131
„ <i>nævius</i> ,	i. 79	<i>Columbida</i> ,	ii. 131
<i>Accentor modularis</i> ,	i. 83	<i>Columba palumbus</i> ,	ii. 131
<i>Acredula caudata</i> ,	i. 89	<i>Chelidon urbica</i> ,	i. 141
<i>Anser albifrons</i> ,	ii. 90	<i>Columba ænas</i> ,	ii. 141
<i>Anas boschas</i> ,	ii. 101	<i>Cotile riparia</i> ,	i. 144
<i>Anthus pratensis</i> ,	i. 113	<i>Columba livia</i> ,	ii. 145
„ <i>trivialis</i> ,	i. 116	<i>Certhiida</i> ,	i. 146
„ <i>obscurus</i> ,	i. 118	<i>Certhia familiaris</i> ,	i. 146
<i>Ampelida</i> ,	i. 129	<i>Carduelis elegans</i> ,	i. 148
<i>Ampelis garrulus</i> ,	i. 129	„ <i>spinus</i> ,	i. 152
<i>Alectorides</i> ,	ii. 207	<i>Coccothraustes chloris</i> ,	i. 154
<i>Ægialitis hiaticula</i> ,	ii. 224	<i>Coturnix communis</i> ,	ii. 190
<i>Alaudida</i> ,	i. 250	<i>Orex pratensis</i> ,	ii. 194
<i>Alauda arvensis</i> ,	i. 250	<i>Corvidæ</i> ,	i. 197
<i>Alcedinida</i> ,	i. 267	<i>Corvus monedula</i> ,	i. 207
<i>Alcedo ispida</i> ,	i. 267	„ <i>corone</i> ,	i. 210
<i>Aluco flammeus</i> ,	i. 280	<i>Charadriida</i> ,	ii. 210
<i>Asio otus</i> ,	i. 287	<i>Charadrius morinellus</i> ,	ii. 210
<i>Asio accipitrinus</i> ,	i. 289	<i>Corvus cornix</i> ,	i. 214
<i>Alcida</i> ,	ii. 295	„ <i>frugilegus</i> ,	i. 216
<i>Alca torda</i> ,	ii. 295	<i>Charadrius plumialis</i> ,	ii. 221
<i>Accipiter</i> ,	i. 296	<i>Corvus corax</i> ,	i. 240
<i>Accipiter nius</i> ,	i. 311	<i>Cypselida</i> ,	i. 256
<i>Botaurus stellaris</i> ,	ii. 53	<i>Cypselus apus</i> ,	i. 256
<i>Bernicla brenta</i> ,	ii. 91	<i>Caprimulgida</i> ,	i. 258
„ <i>leucopsis</i> ,	ii. 93	<i>Caprimulgus europæus</i> ,	i. 258
„ <i>canadensis</i> ,	ii. 95	<i>Oculida</i> ,	i. 273
<i>Buteo vulgaris</i> ,	i. 302	<i>Oculus camorus</i> ,	i. 273

INDEX TO NAMES OF BIRDS IN VOL. I. AND VOL. II. 385

	VOL. AND PAGE		VOL. AND PAGE
<i>Circus cyaneus</i> ,	i. 296	<i>Ictus torquilla</i> ,	i. 265
<i>Olymbida</i> ,	ii. 309	<i>Laniida</i> ,	i. 123
<i>Olymbus glacialis</i> ,	ii. 309	<i>Lanius excubitor</i> ,	i. 123
„ <i>septentrionalis</i> ,	ii. 311	„ <i>collurio</i> ,	i. 127
<i>Otocathraustes vulgaris</i> ,	ii. 351	<i>Lagopus scoticus</i> ,	ii. 162
<i>Dafila acuta</i> ,	ii. 109	<i>Linota cannabina</i> ,	i. 168
<i>Dendrocopus major</i> , i. 261; ii. 352		„ <i>rufescens</i> ,	i. 172
<i>Brithaca rubecula</i> ,	i. 50	„ <i>flavivestris</i> ,	i. 174
<i>Betopistes migratorius</i> ,	ii. 153	<i>Loxia curvirostra</i> ,	i. 179
<i>Emberizida</i> ,	i. 186	<i>Limicola</i> ,	ii. 210
<i>Emberiza miliaria</i> ,	i. 186	<i>Limosa algocephala</i> ,	ii. 257
„ <i>citrinella</i> ,	i. 183	<i>Larida</i> ,	ii. 264
„ <i>schanichus</i> ,	i. 186	<i>Larus minutus</i> ,	ii. 266
<i>Falconida</i> ,	ii. 1	„ <i>ridibundus</i> ,	ii. 268
<i>Falco peregrinus</i> ,	ii. 1	„ <i>canus</i> ,	ii. 275
„ <i>subbuteo</i> ,	ii. 20	„ <i>argentatus</i> ,	ii. 279
„ <i>asealon</i> ,	ii. 21	„ <i>fuscus</i> ,	ii. 285
„ <i>tinunculus</i> ,	ii. 25	„ <i>marinus</i> ,	ii. 286
<i>Fuligula ferina</i> ,	ii. 115	„ <i>glaucus</i> ,	ii. 287
„ <i>cristata</i> ,	ii. 118	<i>Motacillida</i> ,	i. 106
„ <i>marila</i> ,	ii. 119	<i>Motacilla lugubris</i> ,	i. 106
„ <i>clangula</i> ,	ii. 120	„ <i>sulphurea</i> ,	i. 111
<i>Fringillida</i> ,	i. 148	<i>Mareca penelope</i> ,	ii. 113
<i>Fringilla caelebs</i> ,	i. 162	<i>Mergus merganser</i> ,	ii. 128
„ <i>montifringilla</i> ,	i. 166	„ <i>albellus</i> ,	ii. 130
<i>Fulicaria</i> ,	ii. 194	<i>Muscicapida</i> ,	i. 131
<i>Fulica atra</i> ,	ii. 204	<i>Muscicapa grisola</i> ,	i. 131
<i>Falconida</i> ,	i. 296	„ <i>atricapilla</i> ,	i. 133
<i>Fratercula arctica</i> ,	ii. 307	<i>Machetes pugnax</i> ,	ii. 248
<i>Gallina</i> ,	ii. 158	<i>Mergulus alle</i> ,	ii. 305
<i>Garrulus glandularius</i> ,	i. 200	<i>Nycticorax griseus</i> ,	ii. 52
<i>Gallinula chloropus</i> ,	ii. 268	<i>Numenius arquata</i> ,	ii. 258
<i>Gallinago major</i> ,	ii. 240	„ <i>phaeopus</i> ,	ii. 263
„ <i>caelestis</i> ,	ii. 241	<i>Oriolida</i> ,	i. 190
„ <i>gallinula</i> ,	ii. 244	<i>Oriolus galbula</i> ,	i. 190
<i>Gavia</i> ,	ii. 284	<i>Oidemia nigra</i> ,	ii. 196
<i>Herodiones</i> ,	ii. 39	„ <i>fusca</i> ,	ii. 197
<i>Harelda glacialis</i> ,	ii. 122	<i>Otidida</i> ,	ii. 207
<i>Hirundinida</i> ,	i. 135	<i>Otis tarda</i> ,	ii. 207
<i>Hirundo rustica</i> ,	i. 135	<i>Paseres</i> ,	i. 1
<i>Hamatopus ostralegus</i> ,	ii. 231	<i>Pandion haliaetus</i> ,	ii. 27
<i>Hydrochelidon nigra</i> ,	ii. 264	<i>Pelecanida</i> ,	ii. 30
<i>Halizetus albicilla</i> ,	i. 307	<i>Phalacrocorax carbo</i> ,	ii. 30
		„ <i>graculus</i> ,	ii. 33

VOL. II.

2 B

386 INDEX TO NAMES OF BIRDS IN VOL. I. AND VOL. II.

	VOL. AND PAGE		VOL. AND PAGE
<i>Phanicura rutililla</i> ,	i. 47	<i>Sylvia atricapilla</i> ,	i. 60
<i>Phylloscopus collybita</i> ,	i. 68	„ <i>salicaria</i> ,	i. 63
„ <i>trochilus</i> ,	i. 71	<i>Sittida</i> ,	i. 100
„ <i>sibilatrix</i> ,	i. 73	<i>Sitta cæsia</i> ,	i. 100
<i>Parida</i> ,	i. 89	<i>Spatula clypeata</i> ,	ii. 107
<i>Parus major</i> ,	i. 91	<i>Somateria mollissima</i> ,	ii. 123
„ <i>ater</i> ,	i. 93	<i>Syrnhaptes paradoxus</i> ,	ii. 155
„ <i>palustris</i> ,	i. 95	<i>Sturnida</i> ,	i. 102
„ <i>cæruleus</i> ,	i. 97	<i>Sturnus vulgaris</i> ,	i. 192
<i>Pterocletes</i> ,	ii. 155	<i>Scolopacida</i> ,	ii. 232
<i>Pterocida</i> ,	ii. 155	<i>Scolopæ rusticula</i> ,	ii. 233
<i>Passer domesticus</i> ,	i. 156	<i>Sterna fuvialis</i> ,	ii. 285
„ <i>montanus</i> ,	i. 160	<i>Striges</i> ,	i. 280
<i>Phasianida</i> ,	ii. 170	<i>Strigida</i> ,	i. 280
<i>Phasianus colchicus</i> ,	ii. 170	<i>Strix aluco</i> ,	i. 292
<i>Pyrhula europæa</i> ,	i. 176	<i>Stercorarius pomatorhinus</i> ,	ii. 292
„ <i>enucleator</i> ,	i. 178	„ <i>crepidatus</i> ,	ii. 293
<i>Pardix cinerea</i> ,	ii. 178	„ <i>parusiticus</i> ,	ii. 294
<i>Plectrophanes nivalis</i> ,	i. 189	<i>Turdida</i> ,	i. 1
<i>Pyrhacoraz graculus</i> ,	i. 197	<i>Turdus musicus</i> ,	i. 1
<i>Porzana marsetta</i> ,	ii. 198	„ <i>viciivorus</i> ,	i. 8
<i>Pica rustica</i> ,	i. 202	„ <i>iliacus</i> ,	i. 14
<i>Phalaropus fulicarius</i> ,	ii. 232	„ <i>pilaris</i> ,	i. 18
<i>Picida</i> ,	i. 261	„ <i>varius</i> ,	i. 22
<i>Pygopodes</i> ,	ii. 295	„ <i>merula</i> ,	i. 25
<i>Podicipedida</i> ,	ii. 313	„ <i>torquatus</i> ,	i. 32
<i>Podiceps cristatus</i> ,	ii. 313	<i>Tadorna cornuta</i> ,	ii. 100
„ <i>griseigena</i> ,	ii. 315	<i>Troglodytida</i> ,	i. 102
„ <i>nigricollis</i> ,	ii. 317	<i>Troglodytes parvulus</i> ,	i. 102
„ <i>fuvialis</i> ,	ii. 318	<i>Turtur communis</i> ,	ii. 151
<i>Procellariida</i> ,	ii. 321	<i>Tetraonida</i> ,	ii. 158
<i>Procellaria pelagica</i> ,	ii. 321	<i>Tetrao tetrix</i> ,	ii. 158
<i>Querquedula crecca</i> ,	ii. 110	<i>Tringa alpina</i> ,	ii. 246
„ <i>circia</i> ,	ii. 112	„ <i>striata</i> ,	ii. 247
<i>Regulus cristatus</i> ,	i. 65	<i>Totanus hypoleucus</i> ,	ii. 250
<i>Rallida</i> ,	ii. 194	„ <i>ochropus</i> ,	ii. 252
<i>Rallus aquaticus</i> ,	ii. 200	„ <i>calidris</i> ,	ii. 254
<i>Rissa tridactyla</i> ,	ii. 288	„ <i>chæscens</i> ,	ii. 256
<i>Steganopodes</i> ,	ii. 30	<i>Tubinares</i> ,	ii. 321
<i>Sula bassana</i> ,	ii. 35	<i>Upupa</i> ,	i. 271
<i>Sylviida</i> ,	i. 36	<i>Upupa epops</i> ,	i. 271
<i>Saxicola ananthe</i> ,	i. 36	<i>Uria troile</i> ,	ii. 297
„ <i>rubetra</i> ,	i. 41	„ <i>grylle</i> ,	ii. 303
<i>Saxicola rubicola</i> ,	i. 44	<i>Vanellus vulgaris</i> ,	ii. 225
<i>Sylvia rufa</i> ,	i. 57		

ENGLISH NAMES.

	VOL. AND PAGE		VOL. AND PAGE
Arctic or Richardson's Skua,	ii. 293	Common Quail, . . .	ii. 190
Auk, Little, . . .	ii. 305	Chough, . . .	i. 197
Blackbird, . . .	i. 25	Crake, Spotted, . . .	ii. 198
Bittern, Common, . . .	ii. 53	Common Coot, . . .	ii. 204
Blackcap, . . .	i. 60	Coot, Common, . . .	ii. 204
Bean Goose, . . .	ii. 66	Carrian Crow, . . .	i. 210
Brent Goose, . . .	ii. 91	Crow, Carrian, . . .	i. 210
Bernacle Goose, . . .	ii. 93	„ Hooded, . . .	i. 214
Blue Titmouse, . . .	i. 97	Catcher, Oyster, . . .	ii. 231
Bewick's Swan, . . .	ii. 99	Common Snipe, . . .	ii. 241
Black Grouse, . . .	ii. 158	„ Sandpiper, . . .	ii. 250
Brambling, . . .	i. 166	„ Redshank, . . .	ii. 254
Bullfinch, . . .	i. 176	„ Curlew, . . .	ii. 258
Bunting, Corn, . . .	i. 180	Curlew, Common, . . .	ii. 258
„ Yellow, . . .	i. 183	Common Tern, . . .	ii. 265
„ Reed, . . .	i. 186	Cuckoo, . . .	i. 273
„ Snow, . . .	i. 189	Common Gull, . . .	ii. 275
Bustard, Great, . . .	ii. 207	Common Guillemot, . . .	ii. 297
Black-tailed Godwit, . . .	ii. 257	Crested Grebe, Great, . . .	ii. 313
Black Tern, . . .	ii. 264	Dipper, . . .	i. 85
Black-headed Gull, . . .	ii. 268	Duck, Wild, . . .	ii. 101
Barn Owl, . . .	i. 280	„ Pintail, . . .	ii. 109
Black-backed Gull, Lesser, . . .	ii. 285	„ Tufted, . . .	ii. 118
„ „ Great, . . .	ii. 286	„ Scaup, . . .	ii. 119
Buffon's Skua, . . .	ii. 294	„ Long-tailed, . . .	ii. 122
Buzzard, . . .	i. 302	„ Eider, . . .	ii. 123
Black Guillemot, . . .	ii. 303	Dove, Ring, . . .	ii. 131
Buzzard, Rough-legged, . . .	i. 305	„ Stook, . . .	ii. 141
„ Honey, . . .	i. 315	„ Rock, . . .	ii. 145
Common Cormorant, . . .	ii. 30	„ Turtle, . . .	ii. 151
Cormorant, Common, . . .	ii. 30	Dotteral, . . .	ii. 210
„ Green, . . .	ii. 33	Dunlin, . . .	ii. 246
Common Heron, . . .	ii. 39	Diver, Great Northern, . . .	ii. 309
„ Bittern, . . .	ii. 53	„ Red-throated, . . .	ii. 311
Chiffchaff, . . .	i. 68	Dabchick, . . .	ii. 318
Cole Titmouse, . . .	i. 93	Eider Duck, . . .	ii. 123
Canada Goose, . . .	ii. 95	Eagle, Sea, . . .	i. 307
Common Sheld-Duck, . . .	ii. 100	Eared Grebe, . . .	ii. 317
„ Scoter, . . .	ii. 126	Falcon, Peregrine, . . .	ii. 1
Creepers, Tree, . . .	i. 146	Fieldfare, . . .	i. 18
Chaffinch, . . .	i. 162	Flycatcher, Spotted, . . .	i. 131
Common Partridge, . . .	ii. 178	„ Pied, . . .	i. 133
Crossbill, . . .	i. 179		
Corn Bunting, . . .	i. 180		

388 INDEX TO NAMES OF BIRDS IN VOL. I AND VOL. II

	VOL. AND PAGE		VOL. AND PAGE
Green Cormorant, . . .	ii. 33	Great Crested Grebe, . . .	ii. 313
Gannet, . . .	ii. 35	Grebe, Great Crested, . . .	ii. 313
Goose, Solan, . . .	ii. 35	„ Red-necked, . . .	ii. 315
Garden Warbler, . . .	i. 63	„ Eared, . . .	ii. 317
Golden-crested Wren, . . .	i. 65	„ Little, . . .	ii. 318
Goose, Bean, . . .	ii. 66		
„ Pink-footed, . . .	ii. 66	Hobby, . . .	ii. 90
Grasshopper Warbler, . . .	i. 79	Heron, Common, . . .	ii. 39
Goose, White-fronted, . . .	ii. 90	„ Night, . . .	ii. 52
Great Titmouse, . . .	i. 91	Hedge Sparrow, . . .	i. 83
Goose, Brent, . . .	ii. 91	House „ . . .	i. 156
„ Bernacle, . . .	ii. 93	Hen, Moor, . . .	ii. 203
„ Canada, . . .	ii. 95	Hooded Crow, . . .	i. 214
Grey Wagtail, . . .	i. 111	Hoopoe, . . .	i. 271
Garganey, . . .	ii. 112	Herring Gull, . . .	ii. 279
Golden Oriole, . . .	i. 190	Hen-Harrier, . . .	i. 296
Golden-Eye, . . .	ii. 190	Harrier, Hen, . . .	i. 296
Great Grey Shrike, . . .	i. 123	Hawfinch, . . .	ii. 351
Grey Shrike, Great, . . .	i. 123		
Geosander, . . .	ii. 128	Jay, . . .	i. 900
Goldfinch, . . .	i. 148	Jackdaw, . . .	i. 907
Greenfinch, . . .	i. 154	Jacksnipe, . . .	ii. 244
Grouse, Pallas's Sand, . . .	ii. 155		
„ Black, . . .	ii. 158	Kestrel, . . .	ii. 25
„ Red, . . .	ii. 162	Kingfisher, . . .	i. 267
Grosbeak, Pine, . . .	i. 178	Kittiwake Gull, . . .	ii. 288
Great Bustard, . . .	ii. 207		
Golden Plover, . . .	ii. 221	Long-tailed Titmouse, . . .	i. 80
Grey Phalarope, . . .	ii. 232	„ Duck, . . .	ii. 128
Great Snipe, . . .	ii. 240	Lianet, . . .	i. 168
Green Sandpiper, . . .	ii. 252	Lesser Redpoll, . . .	i. 172
Greenshank, . . .	ii. 256	Landrail, . . .	ii. 194
Godwit, Black-tailed, . . .	ii. 257	Lapwing, . . .	ii. 225
Great Spotted Woodpecker, . . .	i. 261; ii. 352	Little Gull, . . .	ii. 266
Gull, Little, . . .	ii. 266	Lesser Black-backed Gull, . . .	ii. 285
„ Black-headed, . . .	ii. 268	Long-eared Owl, . . .	i. 287
„ Common, . . .	ii. 275	Long-tailed Skua, . . .	ii. 294
„ Herring, . . .	ii. 279	Little Auk, . . .	ii. 305
„ Lesser Black-backed, . . .	ii. 285	„ Grebe, . . .	ii. 318
„ Great „ „ . . .	ii. 286		
Great Black-backed Gull, . . .	ii. 286	Missel Thrush, . . .	i. 8
Glaucous Gull, . . .	ii. 287	Marlin, . . .	ii. 21
Gull, Glaucous, . . .	ii. 287	Marsh Titmouse, . . .	i. 95
„ Kittiwake, . . .	ii. 286	Mallard, . . .	ii. 101
Guillemot, Common, . . .	ii. 297	Meadow Pipit, . . .	i. 113
„ Black, . . .	ii. 308	Martin, . . .	i. 141
Great Northern Diver, . . .	ii. 309	Martin, Sand, . . .	i. 144
		Magpie, . . .	i. 202

INDEX TO NAMES OF BIRDS IN VOL. I. AND VOL. II. 369

	VOL. AND PAGE		VOL. AND PAGE
Moor Hen,	ii. 302	Red Grouse,	ii. 163
Night Heron,	ii. 52	Redpoll, Lesser,	i. 172
Nuthatch,	i. 100	Reed-Bunting,	i. 186
Nightjar,	i. 256	Rail, Water,	ii. 200
Northern Diver, Great,	ii. 300	Rook,	i. 216
Osprey,	ii. 27	Ringed Plover,	ii. 224
Ouzel, Ring,	i. 32	Raven,	i. 240
Oriole, Golden,	i. 120	Ruff,	ii. 248
Oyster Catcher,	ii. 231	Redshank, Common,	ii. 254
Owl, Barn,	i. 280	Richardson's Skua,	ii. 293
„ Long-eared,	i. 287	Razor-Bill,	ii. 295
„ Short-eared,	i. 289	Rough-legged Buzzard,	i. 305
„ Tawny,	i. 293	Red-throated Diver,	ii. 311
		Red-necked Grebe,	ii. 315
Peregrine Falcon,	ii. 1	Song Thrush,	i. 1
Pink-footed Goose,	ii. 66	Shag,	ii. 33
Pied Wagtail,	i. 108	Solan Goose,	ii. 35
Pintail Duck,	ii. 109	Stonechat,	i. 44
Pipit, Meadow,	i. 113	Sterk, White,	ii. 64
Pochard,	ii. 115	Sedge Warbler,	i. 75
Pipit, Tree,	i. 116	Sparrow, Hedge,	i. 83
„ Rock,	i. 118	Swan, Bewick's,	ii. 99
Pied Flycatcher,	i. 133	Sheld-Duck, Common,	ii. 100
Passenger Pigeon,	ii. 153	Shoveller,	ii. 107
Pigeon, Passenger,	ii. 153	Scap Duck,	ii. 119
Pallas's Sand Grouse,	ii. 155	Shrike, Great Grey,	i. 123
Pheasant,	ii. 170	Sooter, Common,	ii. 126
Pine, Grosbeak,	i. 178	„ Velvet,	ii. 127
Partridge, Common,	ii. 178	Shrike, Red-backed,	i. 127
Plover, Golden,	ii. 221	Smew,	ii. 130
„ Ringed,	ii. 224	Spotted Flycatcher,	i. 131
Phalarope, Grey,	ii. 232	Swallow,	i. 135
Purple Sandpiper,	ii. 247	Stock Dove,	ii. 141
Pomatorhine Skua,	ii. 292	Sand Martin,	i. 144
Puffin,	ii. 307	Siakin,	i. 152
Petrel, Storm,	ii. 321	Sand Grouse, Pallas's,	ii. 155
		Sparrow, House,	i. 156
Quail, Common,	ii. 190	„ Tree,	i. 160
Redwing,	i. 14	Snow-Bunting,	i. 189
Ring Ouzel,	i. 32	Starling,	i. 192
Redstart,	i. 47	Spotted Crane,	ii. 198
Redbreast,	i. 50	Snipe, Great,	ii. 240
Rock Pipit,	i. 118	„ Common,	ii. 241
Red-backed Shrike,	i. 127	Sandpiper, Purple,	ii. 247
Ring Dove,	ii. 131	„ Common,	ii. 250
Rock „	ii. 145	Skylark,	i. 250
		Sandpiper, Green,	ii. 252

390 INDEX TO NAMES OF BIRDS IN VOL. I AND VOL. II

	VOL. AND PAGE		VOL. AND PAGE
Swift,	i. 256	White's Thrush,	i. 22
Short-eared Owl,	i. 289	Wheatear,	i. 36
Skua, Pomatorhine,	ii. 292	Whinchat,	i. 41
„ Richardson's, or Arctic, ii. 293		Whitethroat,	i. 57
„ Buffon's, or Long-tailed, ii. 294		Warbler, Garden,	i. 63
Sea Eagle,	i. 307	White Stork,	ii. 64
Sparrow-Hawk,	i. 311	Wren, Golden-crested,	i. 65
Storm Petrel,	ii. 321	„ Willow,	i. 71
		Willow Wren,	i. 71
Thrush, Song,	i. 1	Wren, Wood,	i. 73
„ Missel,	i. 8	Wood Wren,	i. 73
„ White's,	i. 23	Warbler, Sedge,	i. 75
Titmouse, Long-tailed,	i. 89	„ Grasshopper,	i. 79
„ Great,	i. 91	White-fronted Goose,	ii. 90
„ Cole,	i. 93	Whooper,	ii. 96
„ Marsh,	i. 95	Wild Duck,	ii. 101
„ Blue,	i. 97	Wren,	i. 102
Teal,	ii. 110	Wagtail, Pied,	i. 108
Tree Pipit,	i. 116	„ Grey,	i. 111
Tufted Duck,	ii. 118	Wigeon,	ii. 113
Tree Creeper,	i. 146	Waxwing,	i. 129
Turtle Dove,	ii. 151	Water Rail,	ii. 200
Tree Sparrow,	i. 160	Woodcock,	ii. 233
Twite,	i. 174	Woodpecker, Great Spotted,	i. 261 ; ii. 352
Tern, Black,	ii. 264	Whimbrel,	ii. 263
„ Common,	ii. 265	Wryneck,	i. 265
Tawny Owl,	i. 292		
Velvet Sooter,	ii. 127	Yellow-Bunting,	i. 183



3 2044 107 21

